The successive numbers, from 1 to 50, contain one set of this draught; the numbers 1 to 7, commence the second draught. The treading may be in the same order as the draught, or varied at pleasure.

The fancy tweels, which have been described, are chiefly employed in the manufacture of table linens and cottons. Besides these, a very great variety of pattern is produced, in the weaving of thick goods, for garments of different kinds. Some of these are woven of silk, or woollen, but cotton is the substance by far the most extensively employed.

The difference, in the effects of these, depends entirely upon the succession of the draught, the application of the cording, and the order of treading. Some of these goods, such as velvets, corduroys, &c. have the flushing cut, at certain intervals, after the weaving is finished, to complete the effect. But the investigation of this, and many other ways of finishing cloth, does not come within the plan of this work.

I have had the good fortune to procure a very extensive, and, I believe, accurate collection of patterns, applicable to these kinds of work. With them I shall conclude this Essay.

The numbers, showing the draught in all these plans, are placed in the order of drawing, and each number denotes one thread. The raising cords are, as usual, represented by cyphers, and the order of treading is pointed out by the numbers placed under each plan.

No. 1.

No. 2.

PILLOW FUSTIAN.

PLAIN VELVERET.

0		Π	Γ	1 4	}	5	1	- 11		0		$\Box$			3
	0				3 6	: :	2	1		0	0			5	
		0		6	2	3		1	0			0	0	Π	2
		Γ	0	5	1	4		1				0	i	6	4
2	4	3	1						4	6	2	3	1		
											-				

No. 3.

No. 4.

## DOUBLE JEAN.

PLAIN THICKSET.


01			0	ı	1		0		Γ		8	
o i	_	0	i	2	i i	i	0	0	i –	<b> </b>	6	4
-j-	0	0		3					0		5	2
1	0		0	4	H	0			0	0	7	3 1
4	2	3	1			4	6	2	3	1		
								5		7		
								_				

No. 5.

No. 6.

#### BEST THICKSET.

ST	ററ	KI	NE	т.



No. 7.

No. 8.

STRIPE.

### VELVET TUFT.

0	0	0		6	1	1		0		1	Γ	531	
Ī	0	0	0	7	+	1		0	0				+ 2
0	0				5 2	l I	0	Ī	Ī	0	0	4 2	
0		0	0	8	3	·	i	<u> </u>	İΠ	0	1	5	3 1
		·—	•										

6 4 2 3 1

No. 9.

No. 10.

PRINCE'S CORDS.

Ī			Γ	0	7 3 1	1	000	1
10	Γ	<u> </u>	0	0	9 5	1		0 2
T	0	0	Ī		10 4	l l	0	3
Ì	0	i -	İ		86 2	1		0   4
6	4	2	3	ı			2 3	1
		5					4	

No. 11.

No. 12.

CORD AND VELVERET.

BARLEY CORN.

T	0		1		3 1	3 1	- 13				0	5 1
1	0	0	Ī	1	5 7 5	5	1			0		7 3
10	<u> </u>	i-	0	0	6 8	2	"	1	0	Ī	Γ	8 6
i			0	Ī	4 2 6	4	N_	0				4 2.
4	3	2	3	1				4	2	3	1	
	6	5										

No. 13.

No. 14.

#### DI AINI CORD

BOLTON CORD.

		P	LAI	N	CON	D.			•	BOL		, 14	CORD.
•	_	i		_	0	3 1	-	F		0		0	5 3 l
-		0	<del>                                     </del>	i	i	4 2	- i	$\neg \neg$	0	Γ	Î	Π	4 2
-	0	i –	i —	0	0	5		Ti-	Ϊ	Γ	Γ	0	9 7
•	-	iō	0	i	i	6	ı	0	0	Π	0		10 8 6
•	5	4	2	3	1	<del> </del>		6	4	2	3	1	
										4			


No. 15.

No. 16.

THICKSET CORD.

ROUND TOP.

101 1010	531		_	0	0		6	2	_
10	4 2		_		0		10 8	4	_
1	97	0	0		I	0	7		Ī
00	10 8 6		0				9	5 3	
		4	_	0	a	1			



No. 25.

No. 26.

QUEEN'S CORDS.

1	0			0	Ι	1	1			0	0				1
ì	0	0	Γ			2	-11	П		0		0			2
		0		0		3	1	0			0	0		0	3
Ϊ	0			0	Ī	4	1	Ī	0	0	0		0		4
Ī	0	0	0	_		5	N N	Ì		0	Γ	0			5
0	i —	0	<u> </u>	0	0	6	1				0	0			6
4	6	8	2	3	1			4	2	9	6	3	5	1	
			5					10	8	18	15	12	11	7	
			7					16	14				17	13	

No. 27.

No. 28.

# QUEEN'S VELVETEENS.

7	_	10	Π	0	0		1	ii i	T			0		0	1
Ì		Ì	0	İ	0	Γ	2	ı			0		0	0	2
1		i	0	Ô			3	1				0	0		3
Î	_	Π	Г	0	0	0	4			0		0		0	4
Ï		i –	0	i	0		5	l I					0	0	5
Ť	0		0	0			6		0			0	0		6
	1	3	12	8	4	2			2	4	3			1	
	5	7				6			·· 6	8	7		5		
	9	11	•			10			10	12	11	9			

No. 29.

No. 30. Genoa velveteen.

### PLAIN VELVETEEN.

			ō		0	1
	0	0				2
0	0		0			9
		0	0			4
	0	0		0		5

٦			0	0	[	4	#		l	0	0		<u> </u>	<u> </u>
1		<del>                                     </del>	İТ	İ	a	5	 ı		0	0	$\Box$	0		5
1		0	i	0		6 ·	 1		0		0			6
_	1	3	2	4	8			2	4	8	12	3	1	
	5	7	6					6				7	5	
								10				11	9	

No. 31.

No. 32.

### GENOA VELVERETS.

	0	<u> </u>		0		ı	§							
	0				0	2	Ş							
		0		0	0	3	ş	T	0			0		4 1
T	0	<u> </u>		0		4	§		0	Γ			0	5 2
	0	<u> </u>			0	5	ş	0			0	0	0	6
0			0	0	0	6	Ş			0		0	0	3
4	6	2	7	3	1			8	6	4	2	3	1	
16	14	5	10	11	9		-				5	11	9	
	,	8	13					12	14	10				
		12								13	15			
		15								16				

No. 33.

No. 34

PLAIN BOLTON CORD.

		PL.	AIN	C	RI	<b>).</b>
\$	Ī	0				1
ş	_			0		2
ş		0				3
ş				0		4
§	$\Box$	0	0	J		5
8	O			O	0	6

4 6 2 S 1 5

No. 35.

No. 36.

KING'S CORD.

CO	RDE	D M	USL	INE

•		ī	Т	<u> </u>	0	0	1	ş	0		Π		0	0	1
•	i –	一	0	_	i	0	2	\$	0		0		0	O	2
•	Ϊ	1	0	0	i		7 3	ş		0		Ī.		0	3
-		i –	ÌΠ	0	0		8 4	\$	0				0	0	4
•		0	i	·	0	0	5	\$	0	0	0		0		5
	0	1	0		1	0	6	Ş				O	0	0	6
•	$\overline{}$	0		-					0	4	6	5	q	1	

5 7

No. 37. No. 38. FANCY TWEEL. RIB AND JEAN. 0 00 0 10 0 0 0 0 0 0 00 8 0 0 0 7 5 0 6 00 1 6 4 2 4 2 12 1 3 5 3 5 7 9 11 10

No. 40. No. 39. VELVET WITH GENOA BACK. VELVET WITH PLAIN BACK. 000 ¥ 00 3 ş 3  $\overline{o}$ 8 12 3 1 1 3 4 2 6 7 5 5 7 6 10 11 9

No. 41. No. 42. HONEY COMB. JEAN RIB. 0 0 1 0 0 3 0 0 3 000 0 00 0 0 0 6 2 5 3 1 8 2 5 3 1 10 4 11 9 7 4 12 6 6

No. 43. CORD WITH GENOA BACK.

		0	0		28	25	22	19	16	13	10	7	4	1
		0		0	29	26	23	20	17	14	11	8	5	2
			0	0								9		3
0			0	0		27	21		1	5				
	0		0	õ	i ·	2	4		18					-
0	0	i-	0	0	30					12			5	

14 2 5 3 1

16 4 11 9 7

18 6 17 15 13

20 8 23 21 19

22 10

24 12

No. 44.

No. 45.

SATINET FACE.

GENOA VELVETEEN.

$\neg \vdash$	T	Т	Г		1	ş					0	0	
0	Ī	Ϊ	ı	0	3	ş	0			0		0	2
0	1	Ī	0	Π	5	\$	0				0		3
0	1	0	0	Π	2	§		0			0	0	4
10	ī	T	Г	Π	4	ş	0					0	5
0	0	Т	_	0	6	Ş	0		0		0		6
7 5	3	2	4	1			7	5	3	2	4	1	
_		_						_		_			

9 8 6

9 8 6

No. 47.

No. 46. DUTCH CORD.

MOCK MARSEILLE.

									Γ	Γ	Γ	1	0	ı
T	Ī	0		(	4	1 §		0		0				2
T	0		Ĭ	0	5 9	? §	i				0	0		3
0		<u> </u>	0	i	6 3	S			0					4
ï	0	0	<u> </u>	0	7	Š	$\neg$				0	0		5
0	T	ō	0		8	Ş	i	0		0				6
10	0	_	0	0	9	Ş							0	7

2 4 6 5 3 1

No. 48.
ANOTHER CORD.

		1	0	0	28	25	22	19	16	13	1	0 7	4	1
	i -	0	0	<u> </u>	29	26	23	20	17	14	11	8	5	2
		0	T	0	Ì							9	_	3
0	i —	0		0		27		21		15				_
	0	0		0	i		24		18					_
0	0	0		0	30					1	2		6	

2 14 5 3 1

4 16 11 9 7

6 18 17 15 13

8 20 23 21 19

10 22

12 24

No. 49.

No. 50.

CENOA VELVETEEN.

QUILTING SEED WORM.

				0	0	1	•	0	0			0	Γ.			4
0			0		0	2	Ş	7	0	0		0	0	7	7	1
0				0	Π	3	5	0	0	0	0	Г	0		5	
	0			0	0	4	-§-	0		0	0	-		8		2
0					0	5	ş	0	0	0	0	0	0		6	
0		0		0		6	ş	10	0	0		0	0	9		3

7 5 8 2 4 1

7 3 1 4 6 2 9 5 8

10

No. 51. silk cord.

			0			0	39	35	31	27	23	19	15	11	7 3
					0	0	38	34-	30	26	22	18	14	10	6 2
				0	0		37	33	29	25	21	17	13		5 1
]	0	0	Ó	0			40	3	2	2	4				
٦		$I^-$	0	0			3	6		28					
	0		0	0	ı —	<u> </u>					2	20		12	4
		0	0	0	1			· · · · ·					6		8

10 2 7 5 3 1

12 4 15 13 11 9

14 6

16 3

No. 52. RIB AND DICE.

7		0			33	31	29	26	24	21	19	17	15	13	11	9	7.	531
ì	_	0	<b>Т</b>	0	Ī		28		23									
1		0	0	0	34							8			12		6	
1	0		İΤ		3	2	27	,	2	2		1	6	4		0	8	42
1	0		0			9	Ю	2	5		20 .					_		

2 8 3 1 4 10 5 7 6 9

6 9 12 11

No. 53. Genoa back velveret cord.

 0				0		1
	0			0		2
0	0			<b>1</b>	Ī	3
0			Π	0		4 .
	0	0	<u> </u>	0	0	3
0	0		0			6

8 6 4 2 3 1

14 7 5 11 13

16 10 9

12

15

No. 54. Another cord.

			0	0	0		31		26		21							_
	0		0	0										1	1		5	_
<u> </u>	i		0			39	3	0 28	25	23	19	17	15	13	9	7	3	1
0	0	0					•	29		24								_
0	0	0	Т	0	0	34					1	8						
0		0	Γ	_	0									12				_
Т	$\vdash$	0	Ϊ	<del>                                     </del>	1	_	32	9	27	22	20	1	6 1	4 1	0 1	3 6	4	2

1 3 2 4

5 7 6 8 . . .

9 11 10 12

13 15 17 14 16

19 21 18 20

23 22 24

No. 55. GENOA BACK CORD DOUBLE TOP.

	0			0	0	0		1
			0	0				2
		0	0	Г	Π			3
 i		0			0		Ī	4
	_			0	0	İ		5
	_		0	0	i	ĬΠ		6
		0	0	Г	Г			7
 0		0	Г	Г	0		0	8
 4	2	12	9	6	3	5	1	
10						11	7	

No. 56. ROYAL DOUBLE TOP.

		0	0		Г	0	Π.	0	1
	0	Г	<u> </u>	Г	0	0	0		2
				0	0	Γ	Ī.		11 3
	-	П	0	0	Г	Ī	Γ		12 4
i	_	Ì_	0			0			9 5
		Ī		Г	0	0			10 6
—i		0		0	0	Ī	1	0	7
	0		0	0			0		8
	2	10	12	9	6	3	5	1	
	Q	4					11	7	

No. 57.

No. 58. SATIN CORD.

JEAN BACK AND FACE.

0 0

0 0 0

1				0	1
1					2
	0		0		8
ı		0			4
Γ	0		0	0	5
		0	0	0	6
H	0	0		וסו	7

2 4 7 5 3 1 4 2 3 1 6 8

10

No. 59. PLAIN AND WILD WORM.

No. 60. VELVETEEN.

6 4 2 5 3 1

-					Γ	0	l	H				0		0	1
_				0	0		2	1			0		0		2
-			0	1	0	0	3	# _						0	3
		0	Ī	0	0		4	H				I	0		4
	0		0			0	5	#		0				0	5
		0			0		6	H	0				0		6
-	0					0	7	1						0	7
-					0		8	1					0		8

8 6 4 2 3 1 7 5 11 9 10 12 14 16 15 13

No. 61.

GENOA BOLTON CORD.

	0	Π			0	13 7 1
		Π		0	0	11 8 2
	0	Ī		0	Π	12 6 3
0	0	Ī	0		0	4
		0	<u> </u>	0	0	5
 0	0	<b></b>	0	0		9
	0	0			0	10
0			0	0	0	14
	0	0		0		15

8 6 4 2 3 1 12 14 7 5 11 9 10 15 13

No. 62. GENOA BACK CORD.

	Г	Г		0	0	28	2	2	1	6	13		7	1
	0				0	26	23		17		1	1 8	3	2
_	0			0		27		21	18		12		6	3
0	0		0		0	29						1	5	
_		0		0	0							10	-	ł
0	0		0	0						15		9		
_	0	0			0			20		14				
0			0	0	0	2.	5	1	9					
	0	ō		ō	ii	30	24							

8 6 4 2 3 1 12 14 7 5 11 9 10 13 15 16

No. 63.

# ROYAL JEAN CORD.

		<u> </u>	0	0	0	15 13
		Γ	0		0	14 12
		0				16 11
		0	Π			10
			0	0	0	. 9
		i —			0	5
0	0	Ī	1	ĺ	0	4
0	0	0		1		7 3
		0				6 2
0	0				0	8 1

2 4 6 5 3 1

No. 64.

### WILD WORM CORD.

					0	97 31
0	0	0	0		0	5
0		0			0	11
0					0	13
 <b> </b>	-	-	0	_	ō	15
	0		0		0	17
		Ī		0		14 8642
 0	0	0	0	0		18 10
	0			0		12
		0	i	0	1	16

8 6 4 2 3 1

10 12 14 16 7 5

24 22 20 18 11 9

15 1

19 17

23 21

No. 65.

7	_	_	0	Г	10	_	_	0	20
-	_	-		0		0	0	<u> </u>	19
i				i	0			0	18
T)			Ī	Ī		0	0		17
		0						0	16
	0	0	0				0		15
		0	0	0	0			0	14
	0	0	0	O	0	0	0		13 7 1
				$\Box$			_	0	12 10 8 6 4 2
							0		11 9 5 3

12 10 8 6 4 2 1 3 14 16 18 20 22 24 5 7 9 11 13 15 17 19 21 23

No. 68. Mock quilting and satin rib.

	DRAUGHI	•	
32			2
31			3
30			4
29			5
28			6
27	1	7	7
26	18	16	8
25	19	15	9
24	20	14	10
23	21	13	11
	22	1	2

·											
				С	ORI	אוכ	;.				
	0		0	0	0	0		0	0	0	
	0	0	0	0	ı —	0	0	0	0	Π	
	0	0		0	0	0	0		0	0	
		0	0	0	0		0	0	0	0	
	σĮ	0	0	Γ	0	0	0	0		0	
										0	
	0								0		
		0						0			i
	$\neg$		0				0				<del></del>
				0		0			Т		
i	٦				0				İ	0	
3	0	9	8	7	6	5	4	3	2	1	·

No. 67. small king's cord.

		0	0			12
			0	0		11
				0	0	10 6
		0			0	9 5
	Γ	0	0			4
	Ī	į-,	0	0		3
0	П	0	0			8
0	Г	Γ		0	0	2
	0		0	0		7
	0	0			0	1

No. 68.

DOUBLE BOUND VELVETEEN.

	T	10	0	Π	0		Г	0	1
	$\top$	T	1	0	0	Г	<u> </u>	Г	2
0	Ϊ	1	v	0	İ			0	3
— <u> </u>	Ϊ	ì –	O	i –	0				4
0			Г	0	0	Г	0		5
	İΤ	<b>†</b>	0	0	Ī	Г	Г	Г	6
	0	厂	0	i –	0	Ī	0		7
<u> </u>	ì_	Ť		0	0	Ī	Γ		8
	10	i –	0	0		0			9
	İ	i –	Ó		0				10
	Т	0		0	0	0			11
	1	1		0		T			12

No. 69.

		Γ	0	0	Γ	0	1
		0		0			2
İ		0	0				3
			0			0	4
				0	Π	0	5
T T		0	0	0			6
	0	0			0		7
					0	0	8
	0					0	9
	0	0					10
	_	0			0		11
	0				v	0	12

THE explanations given of the principles of tweeling, and the great variety of examples of its application to different species of manufactures, it is presumed, will be sufficient to convey an adequate knowledge to those who peruse this Essay with attention.

It will be proper to observe, however, that a kind of tweel is used in weaving some goods, which forms an exception to the general rule; that the flushing upon one side of the cloth is by the warp, and upon the other by the weft. Here the warp and weft are equally flushed, and the appearance of the cloth is the same upon both sides.

The following are plans of the draught and cording employed to effect this, upon a scale of four leaves, and four treddles, which is the number generally used. In the first, the treading is progressive; in the second, alternate.

In weaving very fine silk tweels, such as those of sixteen leaves, the number of threads drawn through each interval of the reed is so great, that, if woven with a single reed, they would obstruct each other in rising and sinking, and the shed would not be sufficiently opened to allow the shuttle a free passage. To avoid this inconvenience, other reeds are placed behind that which strikes up the weft; and the warp threads are so disposed, that those which pass through the same interval in the first

reed, are divided in passing through the second, and again in passing through the third. By these means, the obstruction, if not totally removed, is greatly lessened.

In the weaving of plain thick woollen cloths, to prevent obstructions of the same kind, arising from the closeness of the set and roughness of the threads, only one fourth of the warp is sunk and raised by one treddle, and a second is pressed down to complete the shed, between the times when every shot of weft is thrown across.

Note. In the representation of the back harness, Plate 8. the leaves, both of the harness and front heddles, are drawn upon a scale greatly larger than the other parts. This was done for the purpose of showing, more distinctly, the construction of the eyes; and the other parts could not have been represented on the same scale, without extending the plate to a very inconvenient size.

## ESSAY III.

ON THE

## WEAVING OF DOUBLE CLOTH.

THE next variety of weaving which claims our attention, is that of double cloth. It is composed of two webs, each of which consists of separate warp and separate weft; but the two are interwoven at intervals. The junction of the two webs is formed by passing each of them occasionally through the other, so that each particular part of both is sometimes above, and sometimes below.

This species of weaving is, almost exclusively, confined to the manufacture of carpets, in this country. The texture is generally the same as that of plain cloth, although some are manufactured with cut flushing, similar to velvet. The material employed is generally dyed woollen, and, as almost all carpets are decorated with fanciful ornaments, the colours of the two webs are different; and they are made to pass through each other, at such intervals as will form the pattern required. Hence it arises, that the pattern on each side of a carpet is the same, but the colours are reversed.

More colours than two are frequently introduced into carpets, but as the most simple mode of illustrating the general principle and process, we shall, in the first instance, confine our attention to

#### CARPETS OF TWO COLOURS.

As we have formerly supposed the warp of tweels to be white, and the weft black, we shall now suppose that a carpet is to be woven, one web of which shall be white, and the other black. Let us also suppose the pattern to be the same with that given as the first example of fanciful tweeling; that is, a representation of a checker board, the squares of which are black and white alternately, as in Fig. 1. Plate 6. already referred to.

A web of this kind may be wrought with eight leaves of heddles, moved by eight treddles. The draught of the warp, and application of the raising cords, will appear by the plan of draught and cording which follows:

Black above. White above.

T	Г		0   0	П	0 0	7 5 3 1	White 1
1	0		10	0	0	8 6 4 2	White 2
1	0	0	0		0	7 5 3 1	Black 3
10	0		010			8 6 4 2	Black 4
To		0	0	$\Box$	10	7 5 3 1	White 5
10	0	0	· II	0		8 6 4 2	White 6
		0	1	0	010	7 5 3 1	Black 7
0			#0	01	10	8 6 4 2	Black 8

2d Black Shot 2 2d White Shot 4 1st Black Shot 5 2d Black Shot 4 2d White Shot 4 2d White Shot 6 1st Black Shot 7 1st White Shot 7

White above. Black above.

By examining the preceding plan, the draught of the two warps will plainly appear, for in each of the two sets of heddles, two leaves contain the white warp, and two the black, and one splitful of each, containing two threads, is drawn alternately. The web is also wefted, by throwing across a shot of white and a shot of black, alternately.

Now, we are to suppose, that in the portion of warp, which is represented as drawn through the four front leaves, the black warp is to be wrought above, and the white warp below; and, that the four back leaves exactly reverse this operation. Let us then examine what effect each treddle will produce, when the cording is applied according to the plan. Let the treddle 1 be pressed down, and a shot of white weft be thrown across. The cording which connects this treddle with the leaves, raises the white leaves 1 and 5, and sinks those marked 2 and 6. Thus one half of the white warp is raised, the other half is sunk, and as the warp is drawn through each leaf alternately, plain white cloth will be produced. At this tread, the black warp is not interwoven at all, for, in the back set of leaves, where the white is to be above, both the black leaves 3 and 4 are sunk; and in the front set, where the reverse takes place, both the black leaves 7 and 8 are raised. The white west, therefore, passes over the former, and under the latter, perfectly clear of both. Let the treddle 2 be next pressed down, and a black shot be thrown across. This treddle raises the black leaves 3 and 7, and sinks those marked 4 and 8. This, therefore, produces plain black cloth, as the former did white. Here the white is not interwoven, for the white leaves 1 and 2, in the back set, are both raised, and those in the front set, 4 and 5, are both sunk. The third treddle again weaves white

cloth, sinking the white threads which were raised by the treddle 1, and raising those which were sunk. The fourth treddle again produces black cloth, in the same way.

So long as the weaver continues to tread these treddles in succession, the effect, as in tweeling, will continue the same, and the web, when finished, would have the appearance of a black and white stripe. But, to produce the checker, when one set of squares are completed, he shifts to the second set of treddles 5, 6, 7, 8, which reverse the effect, raising the white where it was formerly sunk, and sinking it where it was raised.

This is the principle upon which all double cloth is woven, and its application to fanciful ornament forms the only variety in the mounting of the looms. Carpets are seldom wrought with leaves and treddles, nor are they well fitted for this branch of weaving. The materials being coarse and ponderous, the webs frequently broad, and the range of pattern generally extensive, there would neither be room for the leaves required, nor could the weaver exert the power necessary for treading.

An apparatus, similar to the back harness, formerly described, may be used for some patterns; and when the range is extensive, carpets must be woven in the draw loom.

Very few carpets, if any, are woven in this country, excepting in draw looms. It will be curious, however, to explain how they may be wrought by a back harness, and to trace the analogy, which subsists between tweeling and double cloth. The mode of weaving carpets, as now practised, will then be investigated.

To illustrate the application of the harness to carpet weaving, we shall again recur to the checker pattern, and compare the effect of working it by a harness, with the explanation already given of mounting it with leaves.

1st	Ha	nes	lea	ſ	W	w	w	w		-		8	•	•	 
2d	Har	ness	lea	f			3	В	8	w	w	w	W		 
	2d Black Shot	2d White Shot	Ist Black Shot	1st White Shot											
1	x		x	0		7	5	5	1		7	5	3	1	 White
2	x	0	x		8	6	4	12		8	6	4		?	White
3	Т	x	0	x	7		5 :	3	ī	7		;	3	1	 Black
1	Ō	x		x	8	6	- 4	2		8	6	4	2		 Black
	4	3	2	1											

The checker pattern may be wrought by this mounting, and will produce exactly the same effect as the former. A comparison of the two will be useful to illustrate the difference between leaves and harness mounting. In the former, eight leaves and eight treddles were necessary; in this, six leaves and four treddles are sufficient. The two back leaves form the harness, and are raised by levers and cords, suspended over the weaver's head, as described in the last Essay, and represented in Fig. 1. Plate 8. The letter w represents one splitful, or two threads, of white warp; the letter B, one splitful of black. In this kind of weaving, when the harness is used, two threads are drawn through each eye. The front mounting consists of four leaves, moved by four treddles. The draught of both warps, through the harness, will appear by inspecting the plan; each letter representing two threads, as above stated. Of the front leaves, two contain the white, and two the black warp. The succession of drawing is denoted by the figures.

When the first leaf of the harness is raised, press down the first treddle, and throw a white shot across. The white and black warp, being, alternately, drawn through

the harness leaf, according to the range of the pattern, the white will be raised in the one set of checkers, and the black in the other. The cording applied to the first treddle raises the white leaf 1, and sinks the leaf 2. This treddle has no connection with the two black leaves, which remain stationary. In this instance, the letter x is used, where no connection between the heddles and treddles ought to be made. The same letter will be used, wherever a similar case occurs. The leaf 1 raises one thread of every splitful of white in the second harness leaf, and the leaf 2 sinks one thread of every splitful in the first leaf. Plain white cloth is, therefore, produced by the operation of this treddle. The white will be above, or below, according to the situation of the harness leaf through which the warp passes. The second treddle produces the same effect upon the black warp, which the first does upon the white. The third and fourth treddles complete the operation. When one range of checkers has been completed, the first harness leaf is lowered, and the second raised. This reverses the situation of the two warps, and the operation proceeds as before. The eyes of the heddles in the front mounting, are of a length rather more than the whole depth of the shed, as in tweeling. The eyes of the harness leaves are made of tin or copper, and are called mails, by weavers.

There are many different plans for raising the harness leaves, whether used for fancy tweeling or for double cloth. It is not easy to determine which is the best; for upon this, as in all other practical applications of the mechanical powers, much diversity of opinion has existed, and probably will continue to exist. In general, the superiority of one plan to another must be ascertained

by particular circumstances, rather than by precise rules. In the representations given in Plate 8. the harness leaves are raised by means of two parallel levers, moving upon When there is sufficient room for an apparatus of this kind, it seems well adapted to the purpose for which it is intended. If accurately constructed, the two ends of the leaf will rise equally, and, consequently, the shed will be equally deep in every part. It is, however, much more common, in extensive harness mountings, to raise all the leaves, by means of cords passing over pullies. A cord is fixed to either side of the leaf, near the extremity, and the two cords meet in the centre, in an oblique direction, nearly similar to what is represented in Fig. 1. Plate 5. Each cord, passing over a pully, is then brought, in a horizontal direction, over the weaver's seat, and made fast to a piece of wood, generally nailed to the upper cross rail of the loom. To each of these cords another is attached, which passes through the board, Fig. 3. Plate 8, as formerly described. When the handle at the lower end of one of these cords is pulled down, the leaf or leaves attached to the cording rise, and as before, the knot upon the cord is secured by the notch in the board, until an alteration becomes necessary.

In comparing these ways of mounting a back harness, it will be obvious, that the plan exhibited in the Plate is more steady and secure than the other. The parallel levers by which the leaves are raised, if made of sound wood, and properly seasoned, will be little affected by the variation of the weather, and the leaves, of course, will rise regularly and equally at both ends. This is very important in weaving tweels and carpets, where the breadth of the web is frequently two or three yards. The mounting by cords, however, is cheaper, and occupies

less room. But hempen cords, which are generally used, besides their tendency to stretch when new, are very considerably affected by every vicissitude of the atmosphere, and, therefore, less dependence ought to be placed upon their operation.

I have often thought that when looms are mounted for fancy weaving, particularly where the fabric is thick, and the power required great, the substitution of wires for cords would be a material improvement. A wire remains perfectly uniform in all seasons, and, from its superior strength, would last for many years. Cords, on the contrary, besides being contracted or relaxed by every change of the atmosphere, are very apt to rot from damp or moisture, which is very common in weaver's shops. I am aware, that the expence of mounting a loom with wires, will form a serious objection when a variety of work is wanted, and the mounting, of course, frequently changed. But, when there is a rational prospect of a loom being employed for a length of time upon the same pattern, I am convinced that it will be found not only the best, but eventually the cheapest plan. When a mounting is extensive, and much cordage required, great pains are frequently necessary to keep the whole regular, and much time is lost in regulating and repairing the cords. If wires are used, the leaves must be raised by levers; for wire, however much softened, does not possess sufficient flexibility to bend over a pully. The wires should be lackered or painted, to preserve them from rusting, and their lengths may be regulated with great accuracy, by means of temper screws. The above, however, is given merely as an opinion, for I have never known the experiment tried; but I do not entertain a doubt, that it would be found a material improvement.

But in actual practice, carpets are generally, if not always, woven in the

#### DRAW LOOM.

1 shall, therefore, before proceeding, endeavour to describe and illustrate the principle and construction of this extensive and useful machine, and to trace the difference which generally subsists between those which are used for double cloths or carpets, and those employed for the manufacture of damasks, which are fancy tweels of the most extensive range of pattern. Draw looms, as noticed in the Essay on tweeling, are also used for spot weaving, when the pattern is extensive; but the construction of these differs very little from the others, and the small deviations shall be noticed in the proper place. I preferred postponing the description of the damask draw loom, until I could also introduce that for carpets; both for the sake of tracing the analogy between them, and to afford further opportunities of extending my inquiries and examinations, respecting these machines, which are, by much, the most complicated used by weavers. I offer this apology for inserting the observations upon damask, which properly form a part of the Essay upon tweeling, in this place.

It would be difficult, if not impossible, to give representations of the full mounting of an extensive draw loom, for the number of cords is so immense, and they are, necessarily placed so close together to save room, that it would only create unnecessary confusion to attempt to delineate the whole. I have lately seen a damask draw loom at Dunfermline, where that manufacture is carried to great extent and perfection. This loom, which I was

assured was not the most extensive in the place, contained 120 designs of 10 spaces each, and, consequently, was adapted to work a pattern as extensive as could have been effected by 1200 leaves, upon the plan of the back harness formerly described. I have, therefore, represented specimens of the working parts upon a limited plan, for the most extensive are only continuations of the most limited, in the same-regular succession.

These plans will be found in Plate 9.

The use of the draw loom is to combine much mounting in a small space; consequently, the shafts, and every other part which is composed of wood, are avoided, and the moving apparatus consists entirely of cordage. That part of the apparatus which serves as a substitute for the heddles of other looms, is called the harness, and passes through a flat board containing a number of holes or other divisions. In Fig. 1. the edge of the board is represented at C, and the harness passing through it at H. The figure is a transverse elevation of that part which is peculiar to the draw loom, the front leaves, which are worked by treddles; and all other parts in front being taken away for the purpose of showing these parts. In the draw loom, the draught of the warp through the mails of the harness is always in uniform succession, as in tweeling; but it is customary to draw a number of threads through the same mail, as in the back harness used for the diaper. Indeed, the draw loom harness is merely an extension of the former, effecting the same end by different means. Fig. 2. is a representation of the flat side of the board, the edge of which is seen in Fig. 1. to show the way in which the holes, or divisions, through which the harness passes, are placed. Near the centre of each twine of the harness, is the copper or pewter

mail, which serves as the eye, and each is kept tight by a small weight (generally of lead) hung to the bottom. Now, if we are to suppose that the range of the pattern is 100 spaces of the design, for 1000 or any number is only an extension of the same principle, then the 1st, 101st, 201st, &c. twines, after passing through the board are to be knotted together, because all rise at once, each being the first of a new design. In like manner, the 2d, 102d, &c. are knotted, and so on until the whole succession of 100 is completed. To each of these a cord is then tied, which after passing over a pully in the box A (containing in this case 100 pullies) is fastened, in a horizontal direction, to a fixture on one side of the loom, and nearly level with the box A. The horizontal part of these cords is marked B, and this part of the mounting is called the tail. To each cord in the tail, another cord is tied at a convenient distance on one side of the loom, and passes perpendicularly towards the floor, near which they are all made fast to a cross piece of wood. These cords are called simples, and are distinguished by the letter D. Another stout cord F is then stretched from the roof to the floor, parallel to, and at a small distance from the simples. These operations being performed, the whole must be made uniformly tight, and care must be taken that all the mails are level and of a proper height. The warp is then to be drawn through the mails and front mounting, successively, as before mentioned, and the remaining parts for lifting the harness to form the design are to be applied,

If the connection from the harness to the simples is traced, it will be evident that when any simple is either pulled down, or strongly to one side, it will raise all the twines and mails with which it is connected; and, when

relieved, they will be pulled back to their former places, by the weights which are fastened to each. As the simples are very numerous and close to each other, it would be impossible, in a heavy design, to select those which should be successively pulled, without a great waste of time, unless means of regular and speedy selection are employed. This is effected by means of another set of cords called lashes, represented at E, and connecting the simples with the cord F, upon both of which the lashes slide easily up and down. The application of the lashes to the simples must be regulated by the pattern to be produced, and this is called

#### READING ON THE DESIGN.

This operation, from the complexity of the patterns, and the necessity of accuracy, is generally performed by two persons. The pattern, being drawn upon design paper, points out what mails are to be raised, or which is the same, what simples are to be pulled at every change of the harness. It is the business, therefore, of one person to read, or rather to select, from the paper what simples are to have lashes applied to them at every change. The other person, following the instructions which he receives, passes a lash round every simple which is pointed out. He then knots the lashes together, and connects the other end with the cord F by a loop round it, so that the lashes may slide freely upon it. The other end passing loosely round each simple, also slides freely upon them. The lashes must be uniformly tied, that the simples may be pulled equally. A single instance will be sufficient, to illustrate how the design is taken from the design paper.

Let Fig. 14. Plate 4. represent the design of a flower, any number of which are to be woven, at certain intervals, by the draw loom. By counting the spaces upon the design paper, it will appear that this flower covers 45 by the breadth, and 35 by the length. The former gives the number of mails in one flower; and the latter, the number of changes which the harness must undergo while it is working. When the warp has been regularly drawn, and the simples applied, the lashes are to be placed according to the design. In this case, every square which is black, represents a simple to be raised. Beginning at the bottom, it appears that only two mails are to be raised for the stem of the flower, and counting from the right hand, these will be raised by the 31st and 32d simple. The instruction, therefore, given to the person who applies the lashes is; Pass thirty and take two. On the second row of squares, part of the flower as well as the stem, must be raised, and by counting as before from the right, passing the white, and taking the black, the direction will be; Pass 18, take 3; pass 8 and take 2. On the third, two other parts come in: therefore, pass 10, take 3; pass 5, take 5; pass 7, take 2; pass 7 and take 4. In the same way, the operations are continued until the whole 35 are completed, always passing the white, and taking the black.

I shall add the whole instructions for this flower, by comparing which with the design, the principle may be sufficiently understood, and all damask patterns, however extensive, are done exactly on the same plan.

1st, Pass 30 and take 2.

2d, Pass 18, take 3; pass 8 and take 2.

3d, Pass 10, take 3; pass 5, take 5; pass 7, take 2; pass 7 and take 4.

4th, Pass 9, take 5; pass 4, take 5; pass 6, take 3; pass 6 and take 6.

5th, Pass 8, take 7; pass 3, take 5; pass 6, take 4; pass 4 and take 7.

6th, Pass 8, take 7; pass 4, take 3; pass 6, take 2; pass 2, take 2; pass 2 and take 8.

7th, Pass 8, take 7; pass 4, take 2; pass 6, take 3; pass 2 and take 11.

8th, Pass 9, take 5; pass 5, take 2; pass 5, take 4; pass 2, take 2; pass 3 and take 4.

9th, Pass 10, take 3; pass 8, take 2; pass 2, take 4; pass 4 and take 2.

10th, Pass 11, take 2; pass 10, take 2; pass 2, take 2; pass 4 and take 2.

11th, Pass 11, take 2; pass 10, take 3; pass 2, take 2; pass 6 and take 2.

12th, Pass 13, take 3; pass 3, take 3; pass 4, take 2; pass 6 and take 5.

13th, Pass 16, take 4; pass 5, take 2; pass 8 and take 8.

14th, Pass 25, take 2; pass 8 and take 9.

15th, Pass 24, take 2; pass 10 and take 9.

16th, Pass 8, take 3; pass 13, take 2; pass 11 and take 8.

17th, Pass 7, take 5; pass 11, take 2; pass 14 and take 6.

18th, Pass 7, take 6; pass 9, take 3; pass 16 and take 3.

19th, Pass 7, take 6; pass 8, take 4.

20th, Pass 7, take 6; pass 7, take 5; pass 7, take 4.

21st, Pass 1, take 3; pass 4, take 5; pass 6, take 2; pass 2, take 3; pass 5, take 6.

22d, Take 6, pass 3; take 4, pass 4; take 3, pass 3, take 14.

23d, Take 7, pass 8; take 2, pass 5; take 2, pass 3; take 9.

24th, Take 8, pass 2; take 2, pass 2; take 2, pass 8; take 2, pass 3; take 7.

25th, Pass 1, take 19; pass 10, take 2; pass 5, take 4. 26th, Pass 2, take 5; pass 3, take 4; pass 10, take 2. 27th, Pass 10, take 2; pass 2, take 4; pass 7, take 2. 28th, Pass 8, take 4; pass 2, take 6; pass 5, take 2. 29th, Pass 7, take 5; pass 3, take 6; pass 5, take 6. 30th, Pass 7, take 5; pass 3, take 6; pass 5, take 8. 31st, Pass 6, take 6; pass 3, take 6; pass 6, take 8. 32d, Pass 6, take 5; pass 5, take 5; pass 6, take 8. 33d, Pass 6, take 5; pass 6, take 3; pass 8, take 7. 34th, Pass 6, take 5; pass 19, take 3.

From this it will appear, that the shape of every pattern wrought in the draw loom, depends entirely upon the mode of connecting the lashes and the simples. course, the pattern may be altered at pleasure, to any other which does not exceed the range of the mounting, merely by changing the order of this connection. will also be obvious, that in ascertaining the order from the design paper, the connection of the lashes with the simples, is denoted by counting from right to left, or vice versa, and that the number of changes, and consequently the number and arrangement of sets of lashes on the cord F, is, in like manner, ascertained by counting the design from the bottom to the top. The first set is generally placed lowest upon the cord, and the rest in regular succession above it. The sets are connected with each other, at convenient distances, by pieces of twine; so that by a slight pull, they will follow each other in regular order. When the connections are completed, all the sets are pushed up nearly to the top of the cord F. The loom is then to be worked by two persons, one of whom pulls the draught, and the other manages the treddles, shuttle, and lay. The fore mounting is exactly the same, in every respect, as the diaper harness, and the number of leaves equal to one set of the tweel. For the ordinary qualities of damasks, five leaves are commonly used, but many of the finest are wrought with eight.

When the operators are ready to begin, the person who draws, pulls the first set of lashes down, and then by drawing the simples, and consequently the tail, raises that part of the harness attached to the part which is pulled. The weaver then works until a change of the harness becomes necessary. The person who draws, then slacks the simples which had been drawn, pulls down the second set of lashes and draws the simples as before; the weaver proceeds to work until another change is required, and so on until the whole pattern is completed. In the design given, the weaver is to work once over his treddles between every change, and this is generally the case in damask weaving.

When the mounting of the draw loom is very extensive, it is found convenient to have two, and sometimes three boxes of pullies; for were the whole number of pullies placed in one box or frame, it must be extended to a very inconvenient size. These are placed parallel to each other, as represented by the dotted lines Fig. 1. and an equal portion of the cordage is conducted over each. It is also common, to have three or four different sets of simples, and lashes. One set of these is stretched, and

the others are loose; and each set is stretched in turn, when a different part of the pattern is to be wrought.

Many different attempts have been made, at various times, and with various success, to supersede the necessity of employing an additional person to draw the lashes, by constructing the apparatus so, that the weaver may draw the harness, as well as work the treddles. The most recent, and probably the most generally adopted of these plans, is one which has been lately invented and introduced at Dunfermline, where it is now very common. It is known there, by the name of the

#### PATENT DRAW LOOM.

In this loom, the tail of the harness, instead of being carried over pullies to one side, extends perpendicularly upward, and is fastened to the roof of the shop. Upon each cord is a knot, at a convenient distance from the roof, and all the knots must be at an equal heighth. The simples extend horizontally over the weavers' head, where they are made fast; and the lashes hang down from these, and have generally a small handle, or bob, as it is frequently called, attached to each. An instrument, called the comb, from its figure, is hung in a horizontal position, and moveable on its centres. The appearance and shape of the comb will be found in Fig. 4. which represents it as it appears when viewed from above or below. In Fig. 5. it appears as viewed on one side. In both these figures, a represents the centres, b the teeth, c the pull, d a few cords representing the relative situation of the tail of the harness to the comb, e cords representing simples, and f-Fig. 5. the situation of the lashes. In Fig. 5. the operation is represented by two cords of the

tail d, one of which has the knot drawn into the teetle be and the other is disengaged. When the weaver pulls down any particular set of lashes, those simples to which they are attached, are drawn into the oblique direction, as at e, and, consequently, pull those cords of the tail to which they are tied between the teeth of the comb. The end of the lever projecting at c, being then pulled down, and secured by a knot in a notch, in the same way as the diaper harness mounting, the teeth rise, and by means of the knots, carry up that part of the harness which is drawn betwixt the teeth, whilst all the rest remains free. When a change is wanted, the comb is let down, and the simples being slacked, the cords of the tail quit the comb; another set is drawn in by pulling another set of lashes, the comb is again raised and secured as before, and the operation proceeds. The weaver pulls the lashes with one hand, and raises the comb with the other, so that very little time is consumed in changing the harness.

The patent draw loom seems to possess some very obvious advantages, which are not to be found in the old loom. It saves the labour of an additional person, and the operation seems to be conducted altogether, or nearly, as quick. 2dly, Both the tail and simples are much shorter, and, consequently, require less cordage; the boxes or frames of pullies are unnecessary, and the space occupied by the simples at the side of the loom is saved: and 3dly, The mechanical apparatus is so applied, that much less power is required to raise the harness, which must be of considerable advantage in heavy mounted looms, where the strength required is very considerable.

By reducing the way in which the power is applied in both cases, to the elementary principles, the difference will be found to be very great. In the first case, one end of the tail is made fast, and the other sustains all the weights attached to the harness. The simples which are pulled down to raise the harness are connected to the tail, between the end which is fast and the pullies. Consequently, the simples act in the same ratio, as a weight fixed to a moving pully, suspended by a rope passing through the pully, and of which rope one end is made fast. It has been often demonstrated, that a weight, say of 2 lbs. in this situation, will be balanced by another of only 1 lb. suspended from the other end of the rope, after passing over a fixed pully. Hence the weight, or the power, which is the same thing, applied to the simples to pull them down, must be somewhat more than double the sum of all the weights, attached to that part of the harness which is to be raised. See Emerson's Mechanics, Prop. 27, or almost any elementary treatise.

But in the case of the patent loom, the harness is raised perpendicularly by the comb; consequently, no more power is required than will overcome the sum of the weights to be raised; and if the lever, at the end of which the comb is fixed, be divided into three equal parts, and the centres, or pivots, placed at the distance of one of these parts from the comb, the power will be again doubled: Emerson, Prop. 19. From these calculations, we may deduce, that the power required to raise the harness of the patent loom, will be only about one fourth of that required for the other.

But in every species of complicated mechanism, many deficiencies and objections, which may not be obvious to the eye of a transient spectator, frequently become apparent upon practical experience. For this reason, I was at pains to collect from those who were daily employed in working them, their opinions of the comparative merits of the two plans.

When the range of pattern was not very great, I found both the general opinion and practice, which is still more conclusive, decidedly in favour of the patent loom. It was only respecting the very highest mounted looms, that a difference of opinion seemed to exist. I was informed that two looms, of very extensive ranges, had been lately mounted; the first, of 120 designs, upon the old plan; the second, of 125 designs, upon the patent plan. Both looms were allowed to execute their work in a very sufficient manner, but it was stated, that the mounting of the patent loom, although last set to work, was already much decayed, whilst that of the other, which had produced more cloth, was impaired in no perceptible degree.

Should this prove to be generally the case, it will form a just ground of hesitation, in preferring the new to the old plan, in looms of this description. The mounting of an extensive draw loom, is a work necessarily involving much time, labour, and expence, and the loom must therefore, be employed for a very considerable portion of time, before it will indemnify the proprietor. But it may be possible, admitting the fact to be as stated, which I have no reason to doubt, that the difference of the mounting of these two looms, in point of durability, might be produced by some incidental or contingent circumstances in their construction, independent of the general principle. The cordage of the one might be inferior to that of the other, either in the quality of the stuff, in the spinning, or in both. Some part of the machinery might have been imperfect in the workmanship, and caused unnecessary friction; the mounting might have deviated a little from an equal degree of tension, or from the true level, which must produce more strain on one part than another. Whether any of these causes did operate in this case, I had no means of ascertaining; but, in forming opinions respecting complicated and expensive machines, too much caution cannot be used, in investigating not only the direct principles of construction, but all the minute and collateral circumstances which may affect their operations. Want of attention to this, has been more injurious to the improvement and extension of practical mechanism, than any circumstance which has come to my knowledge upon Therefore, without offering any decided that subject. opinion upon the fact stated, it may be sufficient to remark, that speculatively and abstractedly considered, the patent loom, particularly the harness part of it, appears to possess some advantage over the other, even in point of durability. The tail, instead of being conducted over pullies to one side, rises perpendicularly to the roof; consequently, the cords deviate much less from a straight line, and the decay which must be produced, both by the friction of the pullies, and the deflection of the cords, is, almost entirely avoided. It is, however, to be allowed, that some friction will be produced by pulling the cords betwixt the teeth of the comb, and afterwards, by raising the harness, and that, in the former of these motions, the friction is almost at right angles to the staple of the hemp or lint, which is a very unfavourable direction.

In these comparisons of the old and patent draw looms, I have endeavoured impartially, to state both the opinions which I had collected, and the remarks which occurred to myself. Probably, some time may still elapse, before the superiority of either will be universally admitted, even by those who, from their practical experience, have the best opportunities of forming an accurate judgment upon the subject.

But, in whatever way a draw loom is mounted, too much attention cannot be paid, both to the quality of the materials, and accuracy of the workmanship. This, indeed, is a general rule, and will be found to apply to every description of machinery. No plan of economy can be more ruinous in its effects, than that of constructing any piece of mechanism of insufficient materials, and inaccurate workmanship, for the sake of a small reduction of the first expence. The mounting of an extensive draw loom will occupy a man, for at least four Estimating these to be lunar months, of 24 months. working days to each, and the person, employed in mounting the loom, to earn 3s. per day, the expence, for labour alone, will amount to 141. 8s. before the loom can be set to work. Let us then suppose, that the weaver who works this loom, besides paying the person who draws the harness, if he employs one, can earn ls. per day, more than he could if weaving plain cloth. In this case, it will require 288 working days of constant industry, before the price of labour in mounting is repaid, exclusive of the whole expence of the materials. It is plain, that whether a weaver mounts a loom for himself, or employs another to do it for him, the case will be precisely the same, for in both instances the price is estimated by the labour. In the first instance, labour is given; in the second, money; and, by the supposition, the value is the same. But, to make the calculation simple, let us suppose that an operative weaver mounts the draw loom, which he is afterwards to work. By the suppositions which we have made, he will expend 96 working days, in the mounting, before he begins to weave, and 288 working days in weaving, before he recovers common wages for the time which he has expended. These,

taken together, amount to 384 working days, to which adding the intervening Sundays (without any allowance for holidays, sickness, or other causes of impediment), he will at the end of one year and 83 days, or nearly 15 months, be merely paid for his labour. Now let us again suppose that the money expended for materials of the best quality, in mounting a draw loom, amounts to 101. and, that those of inferior quality, might be purchased for 61. Let us suppose also, that these two mountings will last in proportion to their prices, which, in practice, is never the case, for the vulgar adage "the best is always the best penny-worth," will here be found invariably true. In this case, the former will last ten months for every six that the latter will. Let us then suppose, that the worst mounting will last for two years, and the best for three years and four months; the calculation will then be

## FOR THE WORST.

For labour, as b	efore	•		•		•		L.14	8
For materials	•		•		•		•	6	0
								20	g

#### RÉTURN.

1s. per day for 626 working days . . . 31 6
The profit, therefore, to the weaver will be 10s. 18s. excluding interest.

#### FOR THE BEST.

For labour	•	•	•		•		L. 14	8
For materials	. •		•	•		•	10	0
. •							24	8
• •		RET	URN.					
1s. per day for 1043 working days						•	52	3
Or of profit, excluding interest							. 28	15

In both cases, it is supposed, that each kind of material has been laid in at the fair market price, and that no imposition has been practised on the buyer.

The grounds upon which these calculations are made, have been taken entirely at random, to illustrate and prove the position advanced. Whether the price of wages, the cost of materials, or the durability of the apparatus, be taken high or low, the inference will be nearly the same. In every state of the price of labour, if good materials only repay a weaver, bad will ruin him; and, if bad materials yield him a profit, good ones would yield him much more. Simple as this principle is, and easily demonstrable, there are few from which there are more deviations in common practice. I have known incalculable loss, in many instances, arise from this deviation, and have, therefore, entered more into the consideration of it, than I should have done, were it more generally understood, and practised in the affairs of common life.

We now proceed to consider the application of the draw loom to the weaving double cloth, and to explain the difference which exists between the Damask, and

### CARPET DRAW LOOM.

CARPETS, being generally composed of coarse and bulky materials, there are, of course, much fewer splits, or threads, in the warp, than in that of a damask; and, consequently, the drawing apparatus is much less extensive. The common run of carpets do not exceed 10 porters of warp, 4 threads in the split, in the breadth of 37 inches, which is equal to a 500, wrought two in the split or 1000 threads. The harness and mails of the

carpet draw loom, are perfectly similar to those of the damask, excepting that they are larger and coarser. In drawing a carpet through the harness, only one thread passes through each mail, and one thread of each of the two warps is drawn alternately. The draught, through the harness, proceeds in regular succession as in the damask, and two threads of each warp pass between the same splits of the reed, which is, generally, of steel. It is found, in general, unnecessary to use simples in the carpet draw loom; the lashes, therefore, are attached directly to the cords of the tail, from which they hang down perpendicularly at one side of the loom. To the lower end of each set of lashes is tied a cord, and to the other end of this cord, is suspended a small handle, or bob.

Fig. 6. is a transverse elevation of part of a carpet draw loom, showing how the lashes and bobs are attached to the tail. A is the box or frame of pullies, B the tail, C the lashes, G the board through which the cords pass, H the bobs. The bobs are suspended in two rows, as represented in Fig. 7. which is a section of the board G, showing two of the bobs. Of these bobs, one lifts that portion of the black warp which is to be uppermost; the other lifts the white in the same manner, supposing still that these are the two colours of which the carpet is composed. The four front leaves open the sheds, two being set apart for the black warp, and two for the white.

The front leaves of the carpet draw loom are exactly similar to those of the diaper, the eyes being of a length rather more than the depth of the shed, so that they may not interrupt the harness in rising. In some looms, the whole is mounted as a harness, and the treddles are connected with certain of the tail cords. Upon inquiring

of persons, who had been long in the habit of working both, I could not ascertain that any decided preference was to be given to either plan. Both are found to do very well, and both are generally used in different manufactories.

Let us now suppose, that Fig. 14. Plate 4. is to be wrought as a carpet, and that the figure is black upon a white ground. In this case, when a white shot is thrown across, the figure must be raised, and the ground sunk; and when a black shot is inserted, the ground is to be raised, and the figure sunk. For the first, the instructions, in reading on, will be the same with those given for damask, and for the second, directly the reverse. As the shots of weft are thrown in alternately, the harness must be changed at every shot, and for this reason the bobs are placed in pairs, as represented by Fig. 7. The instructions, therefore, will be

1st. White shot, pass 30 and take 2. Black shot, take 30, pass 2, take 13.

and so on, whatever is passed in the one case, being taken in the other.

Different plans have been tried in carpet weaving, as well as damask, to supersede the use of the draw boy. Hitherto, none of them have come into very general practice, although there seems no reason to doubt that some saving may be effected in this way. Carpet weaving, however, does not possess the same facilities for this as damask, for in the former, as the harness must be changed at every shot, if the time of doing so should impede the weaver even very little, more will be lost than an equivalent for the wages of a draw boy. Besides this,

as the weaver must shift his shuttle at every shot, he is sufficiently occupied without being obliged to change his harness.

Carpets are seldom warped upon mills, for the yarn being very coarse, the warp is found not to be sufficiently stretched. A square frame of wood is, therefore, commonly used, with pins at certain distances, over which the warp is stretched by the warper, in a manner similar to the old practice, described in the first Essay. As the warps of carpets do not contain many threads, this practice is considered sufficiently expeditious.

When carpets consist of more than two colours, they are woven exactly as checks, and merely require additional shuttles to insert the west, the same as the warp. There is no other difference in the process. It is not yet customary to use the fly shuttle in carpet weaving, and when the webs are too broad for one man to stretch, two are employed, one at each side of the loom.

Many kinds of carpeting for rugs, passage, and stair cloths, &c. are also woven in the plain loom.

Carpets are also manufactured with flushing like velvet, which is afterwards cut. When this is the case, wires are introduced into the shed, to form the length of the flushing. In each of these wires is a groove, and when the weft has been thrown across, a sharp pointed knife is passed along the groove, which serves as a guide for it. The wire is thus relieved, and the cut warp forms the flushing. These may either be wrought plain, or in figures raised by the harness. This manufacture is chiefly carried on at Kidderminster, and has hardly been introduced at all in Scotland. From the name, it appears to have been originally imported from Turkey. Very elegant carpets are also manufactured in France.

Quiltings are also double cloths, and are manufactured exactly upon the same principle as carpets. The two webs are generally of the same colour. This manufacture is also derived from the French, and was chiefly carried on in the neighbourhood of Marseilles. Those made in England, are generally of cotton.

# ESSAY IV.

ON THE

## WEAVING OF CROSSED WARPS.

THE ornamental kinds of weaving, which form the subject of the 2d and 3d Essays, are those peculiar to stout fabrics of cloth, of various descriptions. That which we are now to investigate, is exclusively adapted to the slightest and most flimsy textures. Like the other branches of the art, we derived our first knowledge of cross weaving from the continent; but, this species of weaving has certainly been much improved, and a considerable variety of nets added, by the invention and ingenuity of weavers in this country.

The manufacture of cross woven goods is, chiefly, carried on in Glasgow, Paisley, and the neighbouring villages in the counties of Lanark and Renfrew, in the west of Scotland. Some attempts have, indeed, been made in different parts of England, to introduce this manufacture; but, whatever may have been the success of these experiments, it does not appear that they have ever been prosecuted to any considerable extent.

The first branch of cross weaving, and of which all the others are only varieties, is

#### GAUZE.

In all the species of weaving, which we have hitherto considered, the threads of the warp, whether raised and sunk alternately, or at intervals, remain always parallel to each other, and without crossing. But in gauze weaving, the two threads of warp, which pass between the same splits of the reed, are crossed over each other, and twined like a cord at every tread. They are twined to the right and left alternately, and each shot of west preserves the twine which the warp has received. Fig. 15. Plate 4. is a representation of gauze, drawn, like the other specimens of cloth in the same plate, upon a large scale, and will, by attentive observation, exhibit the crossings of the warp, and intersections of the west. To produce this appearance, it is only necessary that the warp should really be crossed at every second shot; for its return from the crossed to the open, or parallel state, gives the reversed crossing.

The whole variety in every branch of the art of weaving, consists merely in the way of forming the sheds; and, as this is effected by the heddles, and their connections with the treddles which move them; the whole knowledge of the art, consists in the arrangement of this part of the apparatus of a loom.

Representations of the mounting, peculiar to gauze weaving, will be found in Plate 10. Fig. 1. represents two threads of warp, opened to form the shed, where the warp is not crossed, and Fig. 2. the shed where it is crossed. The mounting, of a gauze loom, consists of four leaves, constructed like common clasped heddles, and of two half leaves. The leaves are raised and sunk, by means of top levers, or coupers, and marches, exactly

in the same way as in most other ornamental looms, and as represented in Fig. 1. Plate 5. The open shed of the gauze is formed by the leaves 3 and 4; the cross shed, by the leaves 1 and 2, and by the half leaves. The leaves 1 and 2 are called standards, and the half leaves pass through them, as represented in Fig. 3. It is necessary to observe, that in order to produce the twine, in forming the sheds, the threads do not rise and sink alternately, as in plain weaving, nor at intervals as in tweeling. In both sheds, the thread A is always raised, and the thread B sunk; but in the open shed Fig. 1. the threads are not crossed, and in the cross shed Fig. 2. they are. By examining these figures, the way of drawing the warp through the heddles, will become apparent, and this is an important part of every branch of cross weaving. The thread A is drawn through the third leaf, but, as it always rises, it is not taken through the clasp, or eye, of the heddle, but above it, through what the weavers usually call the upper doup. In like manner, the thread B, which always sinks, is drawn through the under doup of the fourth leaf. When this has been done, the thread A is crossed over the thread B, as will appear more plainly in Fig. 5. which is a horizontal, or ground plan. After being drawn through these two leaves, which are generally called the back mounting, and crossed, it only remains to draw the warp through the fore mounting. Of the half leaves, one is hung from above, and one rises from below. The one hung from above, passes through the lower doup of the leaf, or standard 2, and that, hanging from below, the upper doup of the standard 1. This will appear very plain in Fig. 3. Through the under half leaf, connected with the standard 1, the thread A is drawn, and through the upper half leaf, connected with

the standard 2, the thread B passes. In Figs. 1. and 2. the shaft of the upper half b, appears, as hung between the standards 1 and 2; but this is not the usual practice, for it is found more convenient, to place the two standards together; the under half leaf a, in front of the standard 1, and the upper half leaf b, behind the standard 2, as in Figs. 3. and 4. By means of the half leaves, the alternate crossing of the warp is effected; for, in the open shed Fig. 1. the half leaves work in an opposite direction to the standards, and leave room for the warp to rise and sink in the space between the leaves and standards, while, in the cross shed Fig. 2. the half leaves rise and sink with their respective standards, and force one thread of warp across the other. Thus, when the warp is direct, the half leaves are crossed, and when the mounting is direct, the warp is crossed. This will plainly appear, by carefully tracing the threads A and B, in Figs. 1. and 2. and also in Figs. 3. and 4. where sections of the threads are represented by round dots. In Fig. 3. the half leaves and standards are crossed as in Fig. 1. and in Fig. 4. if the standard 1 is sunk, and the standard 2 raised, the mounting will be direct, and the warp crossed as in Fig. 2.

It has not been the custom, among weavers, to represent the drawing or cording of gauzes or nets, upon paper. This may have arisen, in some instances, from the desire of keeping that branch of manufacture secret. But, in general, it may be traced to a different cause. From the very nature of the process, it is much more difficult to represent cross than parallel warp; and, as the crossings take place, alternately, in the warp and in the heddles, these crossings cannot be easily represented, without elevations of the machinery, as well as ground plans. This circumstance, together with the want of attention

among operative weavers, to whom the knowledge of cross weaving is chiefly confined, to acquire a knowledge of mechanical drawing, has, hitherto, prevented any attempt at representation. Their views seem never to have gone further than horizontal plans of their heddles and treddles, and the formation of their pattern upon design paper, which is not well adapted to represent crossed warp.

In my attempt to obviate this inconvenience, I have merely applied the modes of drawing described in the first Essay, and well known among engineers, architects, mill wrights, and many other artificers, for the purpose of adapting that kind of illustration to the weaving loom, which they have long practised successfully, to illustrate many other branches of mechanical study.

But, in order to render the mode of mounting a gauze loom as plain as possible, I shall enter into a more detailed description of the mounting, than has appeared necessary in those kinds of weaving, where the horizontal plans of the draught and cording have been long practised and understood by professional men. The novelty of the subject, and its evident utility, should I succeed in my explanation, will, I hope, screen me from the charge of unnecessary prolixity; and should I even fail in rendering this part of the knowledge of the art so perspicuous as I wish, I shall not think either my own or my readers' time wholly misapplied, if the practicability of representing the gauze and net mountings upon paper, shall be established to the satisfaction of those interested in the manufacture.

It has been already stated, that the gauze mounting consists of two back leaves, two standards, and two half leaves. These are moved by two treddles. The intermediate levers are five top levers, or coupers, five long, and five short marches. Tracing the heddles in regular succession from the front, the first is the under half leaf a; the second, the front standard 1; the third, the second standard 2; the fourth, the upper half leaf b; the fifth, the first back leaf 3; and the sixth, the second back leaf 4. The two back leaves and the two standards, are raised or sunk, as the case may require, by connecting cords with the marches and treddles, as in other looms. The half leaves have no connection with any treddle, but are lifted and sunk by the warp, in the open shed Fig. 1. and kept tight by weights, in the cross shed Fig. 2. These weights must, therefore, operate upon the half leaves in the cross shed, and must be relieved in the open.

It will be proper to trace the connections of the leaves with the coupers and marches, in the first place, and, then, to explain the way in which the weights are applied to operate upon the half leaves.

1st, The lower half leaf a, is attached by a cord below, to the first short march; it has no connection above. See Fig. 1. Plate 11.

2d, The first standard, by oblique cords, to the first couper above; the couper, to the first long march; the standard is connected below with the second short march.

3d, The second standard, to the second couper above, the couper, to the second long march; the standard, to the third short march below.

4th, The upper half leaf b, to the third couper about; the couper, to the third long march: no connection below.

5th, The first back leaf 3, to the fourth couper above; the couper, to the fourth long march; the leaf 1 to the fourth short march below.

6th, The second back leaf, to the fifth couper above; the couper, to the fifth long march; the leaf, to the fifth short march below.

These connections being formed, it only remains to apply the weights to their respective marches, and to connect the other marches with the treddles. The mode of applying the weights will appear in Fig. 1. Plate 11. This figure is a transverse section of the front part of the mounting of a whip net, of which it will be necessary to treat afterwards. In the mean time, as the cording of common gauze is exactly the same as that of the whip net, it will serve to illustrate that part of the mounting.

The lower half leaf a, is connected with the first short march.

The upper half leaf b, with the third couper above, and, from thence, with the third long march.

The application of the weights is, therefore, as follows: From the first short march two cords descend, one passing on each side of the first long march; and from these cords, the weight is suspended. Above the long march, the cords are attached to each end of a piece of wood (generally a piece sawed or cut from a common bobbin), by which they are kept assunder, to prevent them from rubbing on the long march which works between them. Another piece, of the same kind y, is fixed below, and from this the weight is suspended. The same apparatus is applied to the third short march, and passes upon both sides of the third long march, for the upper half leaf. The pieces of wood are distinguished by the letters v and z.

When the open shed is made, the first standard is pulled down. This raises the first long march, which, consequently, lifts the weight, and allows the under half

leaf a, to rise. At the same time, the second standard is raised. This, of course, also raises the third short march, and relieves the pressure of the weight from the third long march. The upper half leaf b, is thus allowed to sink. In forming this shed, the standards and half leaves merely yield to the warp, for the raising and sinking is entirely produced by the back leaves. In the cross shed, the back leaves have nothing to perform, and, therefore, remain stationary, while the motion of the standards being reversed, the weights act with their full power, and keep the half leaves tightly drawn to that part of the standards through which they pass.

From these explanations, and from a careful examination of the Plates 10. and 11. the general principle of weaving gauze may be pretty well understood. The connections of the back leaves, standards, and half leaves, with the long and short marches, have been already stated.

The connections with the treddles, will be found by examining Fig. 5. Plate 10. which is a horizontal plan, similar to those employed, to illustrate other branches of weaving. In order to bring this as nearly as possible to the same plan, as other plans of draughts and cordings, similar marks have been used. The warp thread A, which is drawn through the upper doup of the first back leaf 3, is distinguished by a black mark. The thread B, which is drawn through the under doup of the leaf 4, by a white mark. The draught of the warp, through the upper half leaf b, is also denoted by a white, and that through a, by a black mark. The connections for raising the back leaves and standards, are also marked black; and those for sinking them, white. Where no connection from the marches to the treddles is necessary, the mark × is used.

As the half leaves are raised and sunk by the warp, no mark is used for the cording of them. The open shed is formed by pressing down the treddle 1; the cross shed, by the treddle 2. The treddle 3, merely reverses the motion of the treddle 2, to enable the weaver to work plain cloth as well as gauze, when he finds it convenient. The alternate motion, necessary for plain cloth, is entirely performed by the standards and half leaves, the back leaves remaining stationary, in this as well as the cross shed. But, in this shed, it is necessary to connect the marches with the plain treddle, to keep the half leaves tight when the weights are raised, the fore mounting in the plain shed, being exactly in the same situation as in the open shed.

It does not appear necessary to add more to these explanations; but, although it involves a recapitulation, I trust it will not be deemed improper, to give the whole connection of a gauze loom, for the use of those, who may be neither fully acquainted with the subject, nor conversant with the modes of drawing mechanical designs.

#### HEDDLES.

## Front Mounting.

a, a half leaf; the shaft below.

1, a full leaf; the first standard.

2, a full leaf; the second standard.

b, a half leaf; the shaft above.

## Back Mounting.

3, a full leaf; warp through upper doup.

4, a full leaf; warp through under doup.

#### CONNECTIONS WITH THE COUPERS.

First standard, 1; first couper.
Second standard, 2; second couper.
Upper half leaf, b; third couper.
First back leaf, 3; fourth couper.
Second back leaf, 4; fifth couper.

## COUPERS TO LONG MARCHES.

First couper; first long march.
Second couper; second long march.
Third couper; third long march.
Fourth couper; fourth long march.
Fifth couper; fifth long march.

## HEDDLES TO SHORT MARCHES.

Under half leaf, a; first short march. First standard, 1; second short march. Second standard, 2; third short march. First back leaf, 3; fourth short march. Second back leaf, 4; fifth short march.

## WEIGHTS FROM MARCHES,

First weight, from first short march; over first long march.

Second weight, from third short march; over third long march.

## OPEN SHED TREDDLE 1.

Lower half leaf, a; raised and slack. First standard, 1; sunk.
Second standard, 2; raised.
Upper half leaf, b; sunk and slack.
First back leaf, 3; raised.
Second back leaf, 4; sunk.

## CROSS SHED TREDDLE 2.

Lower half leaf, a; raised and tight. First standard, 1; raised. Second standard, 2; sunk. Upper half leaf, b; sunk and tight. Both back leaves, stationary.

## PLAIN SHED TREDDLE 3.

Lower half leaf, a; sunk and tight. First standard, 1; sunk. Second standard, 2; raised. Upper half leaf, b; raised and tight. Back leaves, stationary.

To form these sheds, the following connections between the marches and treddles are necessary:

#### LONG MARCHES.

Treddle 1; second and fourth long march.

Treddle 2; first long march.

Treddle 3; second and third long march.

#### SHORT MARCHES.

Treddle 1; second and fifth short march.

Treddle 2; third short march.

Treddle 3; first and second short march.

From the drawings, and descriptions, I hope, that any person, who possesses an ordinary knowledge of common weaving, and who will study them with care and attention, will find little difficulty in mounting a gauze loom. When the principle of gauze weaving is thoroughly understood, its application to the weaving of fancy nets, may be easily acquired. Many varieties of net work are used; but a few, which form the ground work upon which the rest are formed, will be sufficient to elucidate the general principle, and the limits, to which it is necessary to restrict this work, will not admit of more particular details. The most simple of these is known by the name of the

#### WHIP NET.

THE term whip is used by weavers, to denote a species of warp rolled upon a separate beam, and slackened, as may be required, to form fanciful patterns. In this net, the whole warp is of this description, and, therefore, only one beam, or roll, is required. The mounting of the whip net is, in every respect, the same as common gauze, and the connections are formed exactly in the same way. Fig. 16. Plate 4. is a representation of this net, upon a large scale like the others. In every species of net weaving, it is found proper to use glass beads, in place of the eyes of common heddles, or the metal mails

of the tweeling and carpet harness. This arises from the great friction, occasioned by alternately slackening and tightening the whip, to form the crossings. Those parts of net mountings which pass through the standards, and perform the same operation as the half leaves used for gauze, are called bead lams.

The two back leaves in the whip net, are placed behind the reed; the standards and bead lams, in front of it. This is a way of placing heddles peculiar to net weaving, and used in no other species of cloth. The mounting in front passes between the reed, and the race rod upon which the shuttle runs, so that the standard and bead lams are moved, backward and forward, by the lay at every shot. The principal difference of the whip net from common gauze, consists in this way of disposing the mounting, and in the way of drawing, or leading in the warp. The way in which the bead lams cross each other, will be seen, by inspecting the transverse elevation Fig. 1. Plate 11. which represents the two standards and bead lams before the reed. Fig. 2. is a horizontal The crossings of two plan of the whole mounting. splitfuls are there shown; a, is the lower bead lam in front, passing through the upper doup of the standard 1; b, is the upper bead lam, passing through the under doup of the standard 2. Both bead lams are crossed in front of the standards, as represented in Fig. 1. The threads of warp, or whip, A and B, are crossed, as will appear in Fig. 2. B, after being drawn through the back leaf 4, is crossed over A, which is drawn through the leaf 3, as in common gauze. These two threads are then drawn through the reed together. The next crossing is in the front mounting, where the threads, A and A, in different splits, and the threads, B and B, are crossed by the bead

Let the dots upon the standards 1 and 2, Fig. 2. represent sections of the heddle twine of the standards, and let the bead lams, a and b, be supposed to be quite slack. The first crossing of the threads in the same split will then be shown by the threads A and B, and the front crossing by the bead lams a and b; for when these bead lams are pulled tight, and the whip slackened, the crossing of the threads will take place, and the bead lams will be direct. Thus one crossing is effected by the back, and another by the front mounting, and these are wrought alternately as in gauze. It is unnecessary either to represent or describe the connections of the heddles with the treddles, marches, and coupers, for they are exactly the same as in gauze. The apparatus by which the whip or warp is slackened, is represented Upon the end of the roll d is a ratchet wheel and catch, above which the lever c is placed. From one end of this lever a cord descends, from which, after passing twice round the roll, the pace weight is suspended. The other end of the lever c is connected with a long march, the end of which appears at e. This long march is connected with the treddle 2. The catch is lifted out of the ratchet by another cord, when the whip is to be slackened. Thus, when the treddle 1 is pressed down, the whip is tight and direct, and the bead lams slack and crossed. When the treddle 2 is pressed, the whip is slack and the lams tight. The range of the lever c may be increased or diminished at pleasure, by shifting the centre or fulcrum f, and, consequently, the whip may be more or less slacked, as occasion may require. The bead lam shafts are connected to the standards by cords gg, Fig. 1. which are called bridles, to keep the bead lams from being more tightened when forming the

cross shed than is necessary. The tempering of these cords is considered of essential importance; for if they are too short, the shed will not be properly formed, and if too long, the friction of the beads will very soon cut the heddle twine of the standards. A very useful knot is employed for those parts of the cordage of looms which require nicety in the lengths. Weavers call it a snitch knot, and under Fig. 1. is shown the way of tying it.

The next species of net, which comes under our notice, is that which is known by the name of the

#### MAIL NET.

This net, a representation of which is given in Fig. 17. Plate 4. is merely a combination of the common gauze and the whip net, drawn through the reed in alternate splitfuls. The gauze part passes through one interval, the whip part through the next, and so on The two warps, namely, the gauze, or ground, and the whip, are, therefore, on different rolls; for the whip requires to be slackened to cross the gauze, which, in order to stretch the whip, must remain tight. The mounting is exactly that of a gauze and whip net combined; but, as it may be useful in practice, I have thought it best, again, to represent the whole leaves and bead lams, and to recapitulate the connections. gauze part of the mounting of the mail net is sometimes made to consist of only two back leaves, and a single set of bead lams without any standards. When this is the case, the open shed is effected by the back leaves, the bead lams are sunk, and crossing the under part of the shed rise again to the upper, Where the cross shed is

to be formed, the back leaves, instead of remaining stationary, must be sunk to bring half of the gauze down to the race rod, while the other half is raised, and the crossing effected, merely by raising the bead lam shaft. This apparatus is represented in Fig. 4. with the sinking connections, which are effected by two short marches h and i, with their centres reversed. The reason of applying two marches, is to give the bead lam shaft about double the range of the other mounting, by the same sinking of the treddle. The nearer to the point, or right hand end, of the lower march i, that the cord which connects it with h is placed, the greater will be the range of the sinking motion communicated to the bead lam shaft k. The effect of this bead lam, to form the crossing, will appear in the small sections of sheds Figs. 6. and 7. Fig. 6. is the cross shed, where the bead lam is raised, and tight; Fig. 7. the open shed, where it is sunk, crossed, and slack. Fig. 5. is a ground plan of all the leaves of a mail net of this construction,

## Before the Reed.

- a, is the under bead lam shaft.
- 1, the first standard.
- 2, the second standard.
- b, the upper bead lam shaft.

## Next is the Reed, behind which

- k, is the bead lam shaft without standards.
- 3, is the first back leaf for the whip.
- 4, the second back leaf for do.
- 5, first back leaf for the gauze.
- 6, second back leaf for do.

#### SHEDS OF THE MAIL NET.

Open whip shed, treddle 2.
Under lam shaft, a; raised and slack.
First standard, 1; sunk.
Second standard, 2; raised.
Upper lam shaft, b; sunk and slack.
Bead lam, k; raised.
First net leaf, 3; raised.
Second net leaf, 4; sunk.
First gauze leaf, 5; stationary.
Second gauze leaf, 6; stationary.

Note. In this shed, it is of advantage, as before stated, to sink the two gauze leaves, in order that the gauze shed may be fully opened. Two cords are, therefore, applied between the short marches below and the treddle, for this purpose. It will also appear that in this shed, the whip part of the mounting forms the open shed, and the gauze part the cross,

Cross whip shed, treddle 3.
Under lam shaft, a; raised and tight.
First standard, 1; raised.
Second standard, 2; sunk.
Upper lam shaft, b; sunk and tight.
Bead lams, k; sunk and slack.
First net leaf, 3; stationary.
Second net leaf, 4; stationary.
First gauze leaf, 5; sunk.
Second gauze leaf, 6; raised.

Plain shed, treddle 1.

Under lam shaft, a; sunk and tight. First standard, 1; sunk. Second standard, 2; raised. Upper lam shaft, b; raised and tight. Bead lams, k; sunk and slack. First net leaf, 3; stationary. Second net leaf, 4; stationary. First gauze leaf, 5; raised. Second gauze leaf, 6; sunk.

#### TREDDLE CONNECTIONS.

Long Marches.

First, or plain treddle; 2, 3, and 7. Second, or open treddle; 2, 4, and 5. Third, or cross treddle; 1 and 8.

Short Marches.

First, or plain treddle; 1, 2, 4, and 8, Second, or open treddle; 2, and 6. Third, or cross treddle; 3, 4, and 7.

Note. In counting these short marches from the front, the upper reversed march h, for working the bead lams of the gauze mounting, is not taken into account; for its motion is taken from the march below i, which, in this case, is the fourth from the front.

IT may be proper to remark, that, although the fabric of nets is very flimsy, considerable power is required to move the treddles, on account of the friction produced by the crossings of the warp. For this reason, the centres of the treddles are placed behind, and the weaver works upon the ends furthest from the centres, as in every other case in weaving, where mechanical means are necessary to increase the power exerted.

When the mail net is mounted with the bead lams, it is usual to employ three beams. Upon the first of these, the whip is rolled. One half of the gauze warp upon the second, and the other half upon the third. By this arrangement, the whip may be slackened independently of the other parts, and, at the same time, as the gauze is crossed when the whip is open, it is found convenient to slacken one half a little, that it may yield to the bead lams, when pulled up to form the crossing.

In general, however, the bead lams are apt very soon to decay from friction. It is also found that, when slack, they frequently get entangled with each other, and either break the warp or obstruct the operation. For these reasons, although more mounting is required, mail nets are generally wrought with two half leaves, or bead lams, and two standards for the gauze part, as in common gauze. It seems only necessary to add, that weavers, when mounting or working this species of net, ought always to keep in mind its general principle, namely, that it consists of gauze and whip net, drawn through the reed alternately. It, therefore, requires exactly two gauze mountings. The gauze part must be corded to form the cross shed, while the whip forms the open. The whole gauze mounting, and the two back leaves of the whip, are behind the reed. The whip standards and bead lams, in front, form the crossing of the whip, over and under the gauze, and the gauze passes between the standards and bead lams, Fig. 1. Plate 11. where the plate is shaded black.

Of the other species of nets, it will not be necessary to say much. The varieties are chiefly in the crossings of the bead lams. One of these, invented at Paisley, and generally called the night thought, probably from its having occurred to the inventor when in bed, has been much admired. It is also distinguished, for what reason I am at a loss to account, for I cannot find that any patent was ever granted for it, by the name of the

#### PATENT NET.

A representation of this net is given in Fig. 18. Plate 4. Its difference from the mail net is, chiefly, in the crossing of the bead lams, the leading in, or drawing of the warp, and the application of two additional treddles. Like the mail net, it is a combination of gauze and whip; it is wrought with the same number of leaves, and these leaves are disposed exactly in the same way. The mail net is drawn alternately gauze and whip; and, at one tread, the whip crosses the gauze; while, at the next, the two whip threads cross each other between the two splits of gauze. But, in the night thought, or patent net, half of the whip crosses two splitfuls of gauze, while the other half has no crossing whatever. The two halves are crossed alternately, and this gives the appearance of the net, as will be obvious by inspecting the Fig. Plate 4. The draught of the warp, cording of the treddles, and crossing of the bead lams, are represented in the horizontal plan, Fig. 8. Plate 11. similar to the common way of exhibiting a draught and cording. In this plan, the whole crossing is represented by the bead lams, for the warp is laid down perfectly direct, as in other kinds of weaving. The whip part of the warp is shaded darker

than the gauze, to distinguish them from each other, and to show the way in which both are led in, or drawn. The under shaft of the bead lams is supposed to be raised, and the upper shaft sunk, so that the lams may be perfectly slack. The lams belonging to the upper shaft, which cross above the warp, are represented by double lines to make the crossings distinct. Those belonging to the under shaft, which cross below the warp, are single black lines. The way in which these lines are drawn, will show that the upper lams cross in front, both of the standards and under lams.

The connections of the heddles with the treddles, are shown in the same way as before, the black marks denoting raising, or long march, connections; the white, sinking, or short march, connections; and the mark x, stationary leaves, or no connection. In the gauze part of this, as in the mail net, the back gauze leaves must be sunk, when the gauze bead lams are raised to form the cross shed; but if the full gauze mounting is used, they remain stationary, as represented in the plan. Fig. 9. is a transverse elevation of the part before the reed, used for the patent net. The bead lams, and part of the standards, are drawn to show the crossings as they appear when viewed in front. The shafts are omitted, being exactly the same as those of the mail net. The threads of warp, being shown in section, are represented by round dots; those of the gauze, white; and of the whip, ILL. In both of the Figs. 8. and 9. one set of the pattern is given; and this is to be repeated until the whole warp is drawn. The patent net is wrought either with three, or four beams. If the single bead lam without mandards is used, two beams are required for the gauze part; if the full gauze mounting is adopted, only one

beam is necessary. In both cases, two are requisite for the whip, in order that each half should be slackened in its turn, for the alternate crossing. As in the mail net, it is most common to use the full mounting for the gauze.

For practical use, I shall give the sheds of the patent net, in the same way as the others.

SHEDS OF THE PATENT NET, OR NIGHT THOUGHT.

## FIRST SHED, TREDDLE 1.

Under lams, a; raised and slack. First standard, 1; sunk.
Second standard, 2; sunk.
Upper lams, b; sunk and tight.
Gauze lams, k; sunk and slack.
First whip leaf, 3; raised.
Second whip leaf, 4; stationary.
First gauze leaf, 5; sunk.
Second gauze leaf, 6; raised.

## SECOND SHED, TREDDLE 2.

Under lams, a; raised and slack.

First standard, 1; sunk.

Second standard, 2; raised.

Upper lams, b; sunk and slack.

Gauze lams, k; raised and tight.

First whip leaf, 3; raised.

Second whip loaf, 4; sunk.

First gauze leaf, 5; sunk.

Second gauze leaf, 6; sunk.

The gauze leaves, stationary, with full mounting.

## THIRD SHED, TREDDLE 3.

Under lams, a; raised and tight. First standard, 1; raised, Second standard, 2; raised. Upper lams, b; sunk and slack. Gauze lams, k; sunk and slack. First whip leaf, 3; stationary. Second whip leaf, 4; sunk. First gauze leaf, 5; sunk. Second gauze leaf, 6; raised.

## FOURTH SHED, TREDDLE 4,

Under lams, a; raised and tight.

First standard, 1; raised.

Second standard, 2; sunk.

Upper lams, b; sunk and tight.

Gauze lams, k; raised and tight.

First whip leaf, 3; stationary.

Second whip leaf, 4; stationary.

First gauze leaf, 5; sunk.

Second gauze leaf, 6; sunk.

The gauze leaves, stationary, with full mounting.

There are many varieties of these nets, but they depend more upon difference in treading, than any variation of the general principle. To give plates representing these varieties, would enhance the price of this work too much to render it susceptible of that circulation which is my chief object. Some descriptions of these varieties will be given, as miscellaneous observations, before the conclusion of this Essay. In the mean time, we proceed to give a short description of a species of gauze, generally called

#### CATGUT.

To those who are previously acquainted with the manner of weaving gauze, that of producing catgut will be a very simple operation. The principle of both is exactly the same. The gauze, as already explained, is crossed and twined at one treading. It is there kept fast by the intersection of the west; and, at the next tread, by returning to the open state, the twine is reversed, and the warp again locked by the weft. Consequently, the same threads of warp always rise and sink, being crossed and open alternately. The catgut carries the twine a little further; for, in this species of cross weaving, half a turn more is produced than in the gauze. The most simple way of weaving catgut, will appear in Figs. 10. and 11. Plate 11. Fig. 10. represents the open, and Fig. 11. the cross shed, as they appear when opened. The whole mounting consists of two back leaves, and a set of bead lams, similar to those already described for the gauze part of the mail and patent nets. The open shed is formed by the back leaves, the lams yielding a turn and a half, as represented in Fig. 10. At the next tread, the cross shed is formed by raising the lams, and leaving the back leaves stationary, or sunk, as in gauze, see Fig. 11. Here the threads, A and B, rise and sink alternately, as in direct weaving, but with the gauze crossing added to the plain shed. Catgut, therefore, combines the principles of plain and cross weaving. In the finer kinds of catgut, it is found useful to work the lams through a standard, as represented by Fig. 12. It will appear by this figure, where the threads of warp are in section, and represented by dots, that the whole gauze cross is effected by the lam; and the additional half turn is produced by sinking the standard, when the lam is pulled tight.

Having stated what appeared most essential of the principles upon which cross weaving depends, and their application to common practice, I shall conclude this Essay, with a few

#### MISCELLANEOUS OBSERVATIONS.

In the net, as in every other species of fancy weaving, a boundless variety may be introduced. As it would be impossible to enumerate and describe all the varieties, I shall only briefly mention a few which are in most common use.

A kind of fancy nets are very common, which are figured by omitting the crossing in particular places, and which leaves a wider interval than in the other parts. These are called, by weavers,

## DROPPED NETS.

To effect this, it is necessary to mount the loom with additional back leaves, and treddles for moving them. By this apparatus, the crossing of the warp which is drawn through any of these leaves, may be omitted for a shot, while the other parts of the web are crossed like a common net. The way in which these omissions are disposed, forms the pattern. This is so very similar to the way of disposing the leaves in spot weaving, which will form the subject of the next Essay, that it seems unnecessary to go more into detail in this place.

A net, very simple in the mounting, but which produces a very pleasing effect, is much used, and is called the

#### SPIDER NET.

Titis net has merely a common gauze mounting behind the reed, and the gauze is drawn through every second interval. The whip part is, usually, composed of coarser yarn than the gauze. It passes through a bead, to which two lams are attached. These lams pass through the reed, and are attached to separate shafts, so that each may be raised alternately. By these means, the whip, or spidering, is alternately pulled to the right and left in a zig zag direction, but the whip threads do not cross each other. On whatever side the whip is lifted, it is secured by the weft shot.

Another net is known by the name of the

#### DOUBLE PARIS NET.

This net is, in every respect, both of drawing and cording, the same as the patent net, or night thought. It is wrought entirely by the first and fourth treddles, omitting the second and third.

There is also a species of nets called

#### BALLOON NETS.

THESE are also mounted like the patent net. The cording is so disposed, that the crossing of the gauze may be continued regularly, while every crossing of the whip part is twice repeated. In this net, the gauze part is slackened, and the whip part kept always tight. By these means the gauze, being drawn alternately to the right and left, forms a waving, or serpentine appearance, instead of being perfectly straight. There are many varieties of these nets.

It is not easy to give practical instructions for the weaving of nets; for the knowledge and dexterity necessary for this, like all other mechanical arts, can only be attained by assiduous practice. Much depends upon having all the cords of the mounting nicely tempered. This may be easily accomplished, by means of the snitch knot formerly described. It is also essential, that the warp and the lams should be equally slackened at the alternate treadings. If this is not the case, the lams when slack, are very apt to be entangled, which produces much inconvenience and trouble. The way of treading is also material, especially in the cross shed. It is very important that the shed should be gradually opened, while the lay is going back, and, after throwing the shot, that the west should be driven home in the same gradual way, while the treddle is relieved. The crossing of the warp, both before and behind the reed, necessarily creates an obstruction in the moving of the lay, which exists in no species of direct weaving.

In gauze mountings, where beads are not used, the twine of the half leaves is made of silk. This is proper, both on account of strength, and to diminish the friction.

In weaving catgut, it is common to add a treddle for weaving the cloth plain, as in gauze. When the bead lams, without standards, are used, the open shed and plain shed are wrought alternately, by the two back leaves; the bead lams, in both instances, being sunk and slack. When the bead lam is used with a standard, the open shed, as formerly described, is formed by the back leaves, one being raised, the other sunk, and the lams slack. The cross shed, by raising both back leaves, sinking the standard, and keeping the lams tight. The plain shed is formed, by reversing the latter motion, that

is to say, by raising the standard, and sinking both back leaves, the lams being still kept tight. In forming the plain shed in cross weaving, the weights suspended from the marches are relieved; but, as the back leaves remain stationary, the half leaves, or bead lams, generally remain tight by their own weight. If, however, they have any tendency to slacken, they may be easily secured, by taking a cord from the short march of the under half leaf a, and from the long march of the upper half leaf b, to the plain treddle.

# ESSAY V.

ON THE

# WEAVING OF SPOTS, BROCADES, AND LAPPETS,

HAVING now finished our descriptions of the grounds, or fabrics, in common use, we proceed to investigate the mode of adding flowers, and other ornamental figures, to these grounds. These ornaments are, frequently, interwoven either with plain, tweeled, or gauze grounds; and form a very extensive branch of fanciful weaving.

The most simple of these figures, are the

## COMMON SPOTS.

THE weaving of spots is effected by additional leaves and treddles, as in tweeling, and the manner of mounting is, in every respect, similar to that used for other kinds of ornamental work. The apparatus consists of coupers, long and short marches, and treddles, as represented in Fig. 1. Plate 5. already frequently referred to. For the sake of reference, and to ascertain the exact range of the pattern, it is customary in this, as in other branches of

ornamental weaving, to draw the spots upon design paper, each interval generally denoting one splitful, or two threads of warp. The most simple figure of a spot, is that represented in Fig. 1. Plate 12. being what is called a common barley-corn spot, covering three splits, with an interval of nine splits between every spot. To weave this, only three leaves would be required, namely, two for the ground, and one for the spot; but, as one row of spots is thrown into the bosom of the other, forming a kind of diamond figure, four leaves are necessary. A, B, 1, 2, represent a ground plan of the heddles, the same as formerly described. The cross lines, 1 to 12, show a portion of the warp, as it passes through the heddles, every two lines being joined, to denote that these pass through the same interval in the reed. The black marks on each leaf of the heddles, show that the thread, to which the mark is attached, passes through the eye of the heddle in that leaf, and no other. Opposite to the plan, the spot appears upon the design paper. The lest hand thread between every split, forming one half of the whole warp, is drawn through the front leaf A; and the other half is divided between the remaining three leaves, as represented. From this way of disposing the warp, it will be obvious, that when the front leaf is raised, and the other three sunk, and these leaves reversed alternately, plain cloth will be produced. When the third leaf, 1 alone is raised, and all the rest sunk, the left hand row of spots is formed, by throwing across coarser west, by means of a separate shuttle. As this leaf raises only one half of three splits, while the whole of the next nine splits are sunk, only the portion of the coarse west passing under those threads which are raised, is interwoven in the cloth, the remainder passing loosely over

the interval unto the next spot. When the weaving is completed, and the cloth taken out of the loom, these loose intervals are clipped away, when the spots appear as in the design. The back leaf 2, works exactly in the same way; but it will appear, that the threads to be raised are exactly in the centre betwixt the former, and this places the alternate rows of spots in the diamond The leaf B, contains the remaining portion of warp, to complete that part of the plain cloth which lies in the interval between the spots. The portion of warp represented, consisting of twelve splits, is called one set of the figure, and along the whole breadth of the web the same is exactly repeated. The leaf A, containing half the warp, is generally called the ground leaf; B, containing the intervals, the plain leaf; and the two others, the spot leaves. From the design, it will appear, that the set of twelve splits is thus divided—1, 2, and 3, form the left hand spot; 4, 5, and 6, the first interval; 7, 8, and 9, the right hand spot; and 10, 11, and 12, the second interval. The cross bars a, b, 1, 2, as usual, show a plan of the treddles. Each of the four treddles is connected with all the four leaves. The squares formed by the crossings, are distinguished by black marks, when the leaf which forms that crossing is to be raised; or, in other words, that leaf is to be connected with the treddle by the long marches, as formerly described. Where the square at the crossing is not blackened, the connection is made by the short marches, that the treddle may sink the leaf. To work this pattern, beginning with the left hand spots, the leaf 1 is raised, and one shot of the coarse spotting west thrown across; then, two shots of plain west are interwoven; again, one of spotting; and so on, until the spot is

sufficiently large. Six shots of plain are then wrought to form an interval by the west, equal to the three splits in the warp; after which the leaf 2 is to be raised, and the right hand spots formed in the same way as the former. Another interval of plain is then wrought, and so on.

Upon this principle, a boundless variety of figures may be formed upon cloth, if a sufficient number of leaves be employed. It would very far exceed any moderate limits, to investigate the whole range of patterns which may be produced; nor, indeed, is it practicable. The general principle being studied and understood, all the rest may be accomplished at the fancy of the operator. The spot described, is called a common spot, and is the most simple, because one half of the whole warp being included in the ground leaf, the whole of the spotting is thrown upon the other half. But, in this case, the spots will only appear to advantage on one side of the cloth, and scarcely at all upon the other. The texture of the cloth is also inferior, as the spotting is not fully incorporated into the fabric. For this reason, recourse has been had to another mode of forming spots, which appear equally on both sides, and which are much superior in point of effect to the former. These are usually called

## PAPER SPOTS.

These spots not only require nearly double the mounting, or apparatus, on the loom, but are much more tedious in the process of weaving. This increases the expence so greatly, as to prevent them from being manufactured to any great extent, although large quantities have been made at different times.

Fig. 2. is a plan of drawing, and cording a paper spot, such as the pattern opposite to it upon the design paper. But it will also work any other spot pattern, standing upon the same, or a smaller number of splits, and of which the two sides are similar to each other. This pattern stands upon ten splits, for each spot, with an interval of twenty splits between those on the same row; and, of course, one set of the pattern is thirty splits. Like the former, and, indeed, like most spot patterns, the second row is thrown into the bosom of the first; and, of course, is wrought by additional leaves. The mounting of this spot consists of twenty-two leaves, of which the leaves A and B, are, for the intervals of plain cloth, between the spots, and the remaining twenty, are spot leaves. The eleven leaves, from A to 10, contain one half of the warp, and those from B to 20, the other half. Of course, when these two sets of leaves are raised, or sunk, alternately, plain cloth is produced. The leaves from 1 to 5, on the front set, and from 11 to 15, on the back set, work the left hand spot; and those from 6 to 10, and from 16 to 20, the right hand spot. The cording is represented at the left hand; the black squares, at the crossings, denoting rising, or long march connections, and all the others the reverse. By examining the figure upon the design paper, it will appear, that the lower part of it contains ten splits by the warp, and five splits, or ten spots, by the weft; and a comparison of this with the draught will show, that if the ten treddles on the left hand are pressed down in succession, they will raise the leaves so as to produce a spot similar to the figure. The second part of the spot is merely a repetition of the first, and the small spot is made by the treddles 1, 2, 3, and 4. The right hand treddles, wrought in the same

way, produce the second spot, standing in the bosom of the first. In weaving paper spots, one shot of plain, and one of spotting, are thrown in alternately. The paper spot, here represented, may be reduced to a common spot of the same figure, by taking away all the leaves from A to 10, and drawing the warp contained in them through one ground leaf. Twelve leaves then, instead of twenty-two, will be sufficient. If a solid spot is wanted, like the lowest one in the figure, those crossings marked by small black dots, must be changed from sinking to raising connections. Having thus shown a specimen, both of common and paper spots, what other examples may be necessary, for the further illustration of the nature of spot weaving, will be given as common spots. As above mentioned, the only difference is, that in the former, half of the warp is drawn through the ground leaf, and the other half through the spot leaves and the plain leaf; while, in the latter, the number of spot leaves is doubled, the intervals only being plain leaves.

## ALLOVER SPOTS.

Fig. 3. represents the figure and plan of an allover spot, set upon twenty splits, with a small round spot in the bosom of each diamond. In this, the leaf A, as formerly, forms the ground containing half the warp; the leaf B, contains only a few plain heddles at each side of the web, to form the selvage: all the bosom of the web being covered with spotting, in the form represented in the design, from which it is called an allover pattern. The splits of warp, one to twenty, form one set of the pattern; and, at the left side, two splits of the next set,

nineteen and twenty, are added, to show that the spotting is to be continued in sets exactly the same all over the web, without any intervals of plain.

Any allover spot pattern, not exceeding twenty splits, and whose sides are similar, may be wrought by this mounting, only some variation in the cording, or in the succession of treading, may be required. To work the pattern represented, the spot treddles, from one to eleven, are to be pressed in succession, and then from eleven back to one. The black spots, denoting, as usual, the taising cords, which extend in the diagonal direction from corner to corner of the treddle plan, form the diamond, or allover part of the pattern. Those at the other corners, form the round spot. A careful inspection of the figure, will render this apparent. . If the last mentioned raising cords are taken away, and sinking cords substituted, the allover part will remain the same; but there will be no spot in the bosom. Or a spot of any other shape, within the range of the mounting, may be substituted, by adapting the raising cords to lift the leaves required. Upon principles the same as the above, all spot patterns may be formed, where the two sides of the · ligure are similar to each other; but, where this is not the case, a different and more extensive mounting becomes necessary.

Fig. 1. Plate 13. is an example of this. The spot drawn upon the design, it will evidently appear, does not correspond in the two sides. It becomes, therefore, necessary to allow a leaf of heddles for every thread contained in the range of the spot, which is ten splits. The other thread of the split is, as usual, drawn through the ground leaf A; and the warp, to form the intervals, through the plain leaf B. The remaining leaves are for

the spot, ten being allowed for each, and forming, in all, twenty-two leaves; that is, twenty for the two spots, and two for the plain work. This mode of drawing, is equally well calculated for any figure, regular or irregular, not exceeding ten splits; and the alteration, whether the figure is solid like that represented, or hollow, will depend entirely upon the cording, or way of forming the connections.

A careful and attentive consideration of the different designs, and modes of mounting them, which have been given, will evince that figures may be wrought upon cloth in immense variety, upon principles perfectly similar. When the spot is regular, or when the two sides of it are similar, two threads, in every figure, are drawn through the same leaf, because these threads are uniformly raised at the same time in working. But where the figure is irregular, or when no two parts of it correspond, only one thread, in each, can be drawn through the same leaf, because every thread must be raised independent of the others. Figs. 1. 2. and 3. Plate 12. are examples of the first. In Fig. 2. Plate 12. it will be obvious, that the spot extending to ten splits, the fifth and sixth form the centre; and that the two sides, from five to one, and from six to ten, are exactly similar, diverging equally from the centre. Five leaves, therefore, are sufficient for ten splits, for numbers five and six pass through one leaf, numbers four and seven through one; and, in the same way, numbers three and eight, numbers two and nine, and numbers one and ten, pass respectively through the same leaves. In Fig. 1. Plate 13. however, the case is different. The two sides of this flower are totally different. Like the former, it covers ten splits, and because every thread must be independent of all the others, requires ten leaves. The particular form of the spot, is then ascertained by the manner of cording.

To fix the plan of the cording, it is only necessary to number the divisions on the design paper, which represent splits of warp, and to place corresponding numbers also to distinguish the leaves and treddles; as, for example, in Fig. 1. Plate 13. Let the warp splits on the design be supposed to be numbered from one to ten, beginning at the right. Let the spot leaves on the plan be also numbered from one to ten, beginning at the front, and then let the spotting treddles be numbered in the same way, beginning at the centre, or plain treddles. First, then, mark the black spots, or raising connections, for the plain work. One half of the whole warp is drawn through the front leaf A, and the other half through the remaining leaves. Therefore, where the plain treddle a, crosses the leaf A, the raising mark is placed; and where the other plain treddle b, crosses each of the others, a similar mark is also placed. Then, when the leaf A is raised, all the others will sink, and when A is sunk, all the others will tise. This will form the ground, or plain work. Proceed next to the left hand spot. The first threads to be raised in this spot, are numbers four and five: Two raising marks, are, therefore, placed where the treddle number one crosses the leaves numbers four and five. second threads to be raised, are three and four; and the marks are placed where the treddle number two crosses the leaves numbers three and four. In the same way, proceed until the spot is finished, observing only that it often occurs, that a number of lifts upon the same threads may be in the design, and when a connection for raising these is once formed, it is unnecessary to repeat it, because pressing down the same treddle will produce the effect as

often as may be required. In Fig. 1. Plate 13. the tenth, eleventh, and twelfth lift, are all the same, and, therefore, require only one treddle. The right hand spot is merely the left hand one reversed, and the manner of placing the marks exactly the same.

When the plan of cording is completed, it will always appear that the black, or raising marks, form exactly a copy of the design, only that it appears across the drawing, instead of being from top to bottom as in the design. When the two sides of the figure are similar, as in Figs. 2. and 3. Plate 12. the cording will represent only one half of the design. This appears very plainly in Fig. 3. Plate 13. where the leaves and treddles are represented as being placed close together, and the intervals omitted. When this has become familiar, from study or practice, it will be unnecessary to draw plans of the cording, as it can be taken equally well from the design.

## BROCADES, OR FINGER SPOTS.

In the spots, hitherto described, as the figure is formed by coarser weft thrown across by a shuttle, when the yarn crossing the intervals is clipped away, a certain degree of roughness always appears, and, besides, all which is clipped is totally lost. To remedy these inconveniences, another mode of spotting has been practised, and goods of this description, are called brocades, or finger spots. The mounting of these is very similar to that of common spots, but the yarn, which forms the spotting, instead of being thrown across the whole fabric, consists of a separate thread for every flower, which is generally interwoven into the fabric by the hand, or finger, whence they receive the name of finger spots.

In mounting brocade looms, it is not necessary that there should be an additional set of spot leaves to place the one flower in the bosom of the other; for, as the spotting is interwoven by the hand, and as every spot is formed by a thread totally independent of all the others, every second flower may be omitted in the fingering, which will exactly produce the effect.

A specimen of the draught and cording of a finger spot, will be found in Fig. 2. Plate 13. The draught comprehends every figure which does not exceed twenty splits in breadth, and the pattern may be varied to any figure of that extent, by adapting the cording to the figure required. That upon the design is only seventeen splits in breadth, and, of course, the interval is twenty-three splits. The treddles and cording are double, for the purpose of reversing the flower, and every second flower, only, is to be fingered in working. The plain leaf b, is only for the selvage, as in the allover pattern, Fig. 3. Plate 12.

In working brocades, one half of the fingering is generally performed by the weaver, and the other half by a boy or girl, employed for the purpose. To reduce the expence, by rendering the labour of fingering unnecessary, various plans have been devised. In one, the spotting is passed through the spot sheds, by a number of small shuttles, in a way nearly similar to the tape, or incle loom. In another, the spotting is carried through by circular pieces of metal, generally brass, which are moved by a rack, and have a segment of each circle cut out. The number of plates, which it has already been tound necessary to give, necessarily prevent us from representing these kinds of apparatus, and without figures

it would be difficult, if not impossible, to render any description, however minute, sufficiently perspicuous. The want will be the less regretted, that brocades have not been for some years manufactured to any considerable extent. In the specimen, it will appear that the spotting of the brocade is not woven plain like the other spots, but flushed somewhat like tweeling. This is generally the case, because the flushing renders the effect more brilliant. When spotting patterns are too extensive to be wrought with leaves and treddles, recourse is had, as in the damask, and carpet weaving, to the

## . SPOT DRAW LOOM.

THE principle and construction of the draw loom, have been so fully investigated in the third Essay, that very little remains to be added. The spot draw loom, besides the harness, consists of four leaves for working plain cloth, two of which are raised and sunk alternately, as in common weaving. The spotting is effected by the harness, and the plain, by the leaves in front. The heddles, as in the other draw looms, have long eyes, to allow the spotting to rise freely. In the spot harness, mails are not used, but merely eyes like those of heddles. Various contrivances, for raising the harness, and superseding the necessity of employing a draw boy, have been adopted in this mounting. Of these, the principal are the barrel, and saw. Neither of them have been brought to such perfection as to save much labour, and, indeed, the spot draw loom is, in general, very little used. The reading on of the design, is exactly the same as in damask, the spot part being corded, and the plain omitted. Only one thread passes through each eye of the harness. The draw loom may be mounted, either for common, or paper spots. The principle, being the same as in mounting with leaves, does not require to be repeated.

The next species of ornamental weaving, and which, from its cheapness, is very extensively used, is the

#### LAPPET.

THE lappet is a species of flushing done with whip, which is generally considerably coarser than the yarn which forms the fabric of the web. In most instances, the whip consists of two threads twined together. It is not interwoven with the fabric, but crossing over a certain number of splits of warp, rises through the shed, and is tacked to the cloth by the weft shot passing under it. Until within these few years, lappets were generally wrought by bead lams, without standards, passing through the recd, and raised by shafts above. When either of these shafts was raised, the whip, traversing over the under surface of the cloth, was lifted through the shed. and intersected by the weft. But, a much more simple, and sufficiently accurate apparatus, has lately been brought into practice, and has completely superseded the bead lams. This consists of a shaft of well seasoned wood, into which a number of lappet needles, as they are called, are driven at equal lengths. The lappet needle is formed of a piece of brass wire, one end of which is flattened by hammering. A small hole is then drilled through it to receive the whip. The hole is countersunk on each side, and the needle being polished and pointed, the other end, after being sharpened, is driven into the shaft. This shaft

is suspended under the warp, the points of the needles being up. It is susceptible of two motions, the first, from right to left, and vice versa, produces the traversing of the whip upon the under surface of the cloth, to form the pattern. The second is a vertical motion, by which the needles rise through the shed, and raise the whip above the shuttle that it may be intersected by the weft. This motion is communicated by the lay, for whenever the lay is pushed back to form the shed, the lappet frame is pulled up, and when the lay is brought to the fell, to strike home the weft, the frame again sinks by its own weight. When a greater variety of pattern is wanted, more frames are used. When two are employed, the fabric is called a

## DOUBLE FRAME LAPPET.

This apparatus consists of two frames of needles, which move in an opposite direction to each other, when the pattern is forming; for, while one goes to the left, the other comes to the right, and the contrary. Sometimes, the frames are only made to approach each other, or to meet, and, sometimes, they cross each other and return. When the pattern is uniform, that is to say, when the same number of splits are to be crossed, the horizontal, or pattern motion, is communicated by the weaver's left hand, and the length of the traverse, regulated by a rack and spring, fixed upon the upper shell of the lay. But, when it is necessary that the length of the traverse should vary, to form any particular flower or figure, a wheel of a particular construction is used, and the goods fabricated in this way are called

## WHEEL LAPPETS.

THE construction of these wheels is very ingenious, although very simple. In no part of this work, have I had more occasion to regret, that, without additional drawings, it will not be in my power to elucidate my descriptions so perfectly as I wish, than in the present instance. But, after mature consideration, I have thought it of less disadvantage to forfeit, at least for the present, the ample details which it would be necessary to give upon this and many other branches of the art of weaving, than to create an expence upon this work, which might preclude many of the operative part of the community, from the means of access even to those parts, which have been pretty fully discussed.

The wheels are made of wood, and placed at one side of the loom. The circumference is formed like a ratchet wheel, having as many teeth as there are shots of weft in the pattern, and one tooth is moved between every shot, the wheel revolving in centres. To lay down the pattern, upon a wheel of this kind, from design paper, the following instructions are necessary, which, indeed, bear a strong analogy to the way of reading on a pattern for the draw loom. The pattern being drawn, the number of squares from the bottom to the top, gives the number of teeth, whether the wheel is to work one flower, two flowers bosomed, or an allover pattern. The teeth being cut, the flat side of the wheel has a line drawn from the centre, to every division between the teeth. A number of concentric circles are then described, equal to the number of squares from right to left upon the design paper. By marking these, as the pattern increases or diminishes in breadth, a rule is found for forming a groove in the flat

side of the wheel, to regulate the traverse, or shift of the lappet frame, at every shot. An iron pin is fixed in the frame, which works in this groove, and the frame being, as formerly, traversed by the weaver's hand, the two sides of the groove stop the frame at the places proper to form the pattern required. The diameter of the pin must be added to the range of the pattern, in cutting this groove. A mode of spotting, by the application of a wheel of this kind, has been lately introduced, which supersedes the use of spot leaves, and is called

## PRESSED SPOTTING.

THE looms of this description, which I have seen, produce a spot upon a tweeled ground; but, it is, evidently, equally applicable to plain, as to tweeled The fabric is of cotton, and the spotting coloured in imitation of the Norwich shawls. The loom has merely a plain tweel mounting. Two frames, or shafts, are suspended below the warp, like a double frame lappet. Instead of lappet needles, these frames have pressers of brass, flat on the upper edge, driven into them. These pressers, when raised, force up that portion of warp which is to form the interval between the spots, while that part which is to be interwoven, being between the pressers, is not forced, and leaves the shed open to receive the spotting. As the pressers recede, or advance to each other, the breadth of the flower is increased or diminished. The pressers are raised by an additional treddle, placed close to each of the working treddles These treddles are called tongues, and are about six inches shorter than the other treddles, so that the weaver, by shifting his foot, can either press down the tongue along with the treddle, to form the spot, or leave the tongue unpressed, to form the interval. In this case, the centres of the treddles and tongues are behind, and the weaver works upon the ends of them. The same apparatus is used for lappets, where there are intervals. One of the presser frames is wrought by each side of the groove in the wheel, and these sides are cut to form the pattern.

This apparatus is simple, and seems very well adapted for fabrics where the warp is sufficiently strong to bear the pressing, and where the spots are broad; but, when the warp is weak, and the spot terminates in a sharp point, requiring, perhaps, only a single splitful of warp to be open, it will be better to work with leaves. For, the pressed warp must be always more strained than the rest; and it may frequently happen, that the presser may pass a thread which ought to be pressed, and render the spot irregular where much accuracy is required.

The principle of the wheel, carried a good deal further, was that which I adopted to form the patterns of the Patent Tambouring Machinery; and the very ingenious machinery, exhibited by Monsieur Maillardet, at Spring Gardens, is, in general, merely a combination of wheels upon the same principle as that which forms the lappet. Some further account of the construction of wheels of this kind, will be given in describing the mode of weaving by power.

When spots are formed upon nets, they are only interwoven with the gauze part, the whip, or net part, being left perfectly free.

In the Essay upon cross weaving, it ought to have been stated, that the selvages of nets, are wrought plain. I think it better to mention this here, than not to notice it at all. Indeed, it is not much out of place, for, as has been already observed, the selvages of allover spots, are woven in the same way. In common spots of this description, half of the warp of the selvages is included in the ground leaf, as in Fig. 3. Plate 12. and Fig. 2. Plate 13. In those paper spots, which are allovers, the selvages only are on the two plain leaves, as in the intervals Fig. 2. Plate 12. The case is the same in net weaving. Two plain leaves, which only contain a few heddles at either side for the selvages, are added to each of the mountings, shown in Plate 11. They are, generally, placed behind the net leaves, and are corded to the treddles by the same means used in other fancy weaving, namely, coupers, long and short marches, so as always to produce plain cloth.

# ESSAY VI.

ON THE

ECONOMY OF WEAVING, SIMPLIFICATION, OR OMISSION OF PROCESSES, DIVISION OF LABOUR, AND APPLICATION OF POWER.

IN the five preceding Essays, we have endeavoured to I investigate the common manual processes, most frequently used in the art of weaving, and gone as much into detail upon the various branches, as the plan and limits of this work would admit. As already noticed in the introduction to the first part of the work, the knowledge of weaving all the varieties of cloth, has been imported, and, although undoubtedly, many important improvements have been made, both in the construction of the looms, and economy of the manufactures, nothing entirely original has been invented in the business. The woollen trade, introduced by Edward the third, was the original staple of England; and, although considerable quantities both of linen and silken goods, have long been manufactured in that country, they have been by no means nearly equal in value to the woollen goods. The

cotton manufacture, which has been much more recently introduced, has rapidly arrived at an amazing extent and improvement. Still, however, in so far as the greatest branch of the cloth trade, and the raw material of which is chiefly the growth of the country, may be considered as its staple, the woollen remains in the same comparative situation as formerly. The manufacture of linens has been long the staple trade of Ireland, and, previous to the introduction of the cotton manufacture, many attempts were made for its extension and improvement in Scotland. An anonymous publication was printed at Edinburgh, in the year 1733, entitled, "The Interest of Scotland considered, with regard to its police, in employing the poor, its Agriculture, its Trade, its Manufactures, and "Fisheries."

As no name appears in the title, I have not been able to ascertain who was the author of this work. But, it is evidently the production of a man of talent and education. The sentiments contained in it, are liberal and benevolent, and, when a reasonable allowance is made for the prevalent opinions of the age in which it was written, it appears a work of uncommon merit. Many of the author's opinions, indeed, have been either exploded, or at least rendered very doubtful, by the experience, which the prosecution of a more extended trade, since the period at which he wrote, has produced; and, by the able and satisfactory reasonings of Dr. Adam Smith, and other modern economists. In general, he reasons very justly on the state of the manufactures at the time, and gives many hints for their extension and improvement, some of which appear to be very judicious, and others have been proved, by experience, to be fallacious. He admits, that the industry of the inhabitants, properly directed and exerted, is the solid and efficient cause which produces national wealth and prosperity; and strenuously contends, that a fair and liberal commercial intercourse between nations, which produce commodities desirable to each other, must be more advantageous to both, than the vain attempt to monopolize the manufacture of every article, used for internal consumption, to the exclusion or supersession of all foreign traffic. Upon this principle, which seems perfectly just, he censures a number of injudicious experiments, which had been made to establish manufactures of silk, woollen, gloves, earthen ware, and many other articles, by subscriptions, resolutions against using articles manufactured out of Scotland, bounties, and other expedients of a similar nature. He alleges that the capital lost in these speculations, all of which proved abortive, would have been, if judiciously applied, more than sufficient to establish and promote a staple manufacture, congenial to the situation of the country and habits of the people, and sufficiently extensive to exchange for other articles, better and more cheaply manufactured in other countries. This staple he assumes to be flax, but seems to admit that the climate and soil of Scotland, are not the most favourable for its culture, and that the management, in every stage of the process, was much inferior to that of the Dutch and Flemish artizans. To remedy the first, he proposes, that bounties shall be given for raising flax in the American colonies, which have since been severed from this country, most probably for ever. For the next, he wishes, that foreign artists should be invited, by premiums, to settle in this country, for the purpose of instructing the inhabitants. He then proposes his plans for inciting the people to industry, the prevention of theft and begging, and encouragement of manufactures.

The machinery, by which he means to effect these objects, seems very complicated. Indeed, it appears singular, that a person who had seen so clearly the inefficiency of the projects which he reprobates, should immediately propose regulations nearly similar, for the improvement of what he considers the staple manufacture. He conceives the erection of work-houses in every parish, the compulsory confinement of all idle persons in these places, and the flogging them until they become good and industrious weavers, to be expedients admirably calculated to promote industry and emulation. He also proposes the establishment of hospitals for the reception of orphan and destitute children, where, at a proper age, they may be taught to weave and spin. He considers the only way of saving the weavers from idleness and other vices, into which young and unexperienced persons are apt to fall, will be to confine them to the hospital, until they arrive at twenty-five years of age, when, he says, they may enter the world without danger.

He considers that the manufacture might be greatly promoted by Acts of Parliament, requiring at least seven years apprenticeship before any person should be allowed to weave upon his own account; security found by him for his performance of every piece of work in the best manner; the trade made liable to the constant inspection of overseers; these overseers amenable to the magistrates of the royal boroughs, and justices of the peace; and those magistrates directed to enforce, with the utmost riguer, severe penalties for every defect in the cloth, or malversation in the weaver. In short, the trade is to be thrown entirely under the control of justices and magistrates, and the whole funds for his hospitals and bridewells, raised by collections at church doors, and voluntary contributions.

The work appeared soon after the formation of the Board of Trustees for Manufactures and Fisheries, and the author appears, either to have been a member of that board at the time, or, at least, to have had access to all their minutes. As I have only met with a single copy of the book, and, therefore, suppose that it cannot be generally known, and as the preface contains an account of the prevalent opinions, respecting the state of manufactures and trade in Scotland at that period, and of the means by which their improvement was expected, I shall insert it entire.

## · THE PREFACE.

'MANY and just Complaints have been made of our Poverty, and the Decay of our Trade; and of the Decrease of our People for want of Business to imploy and subsist them. This is imputed, and justly, to the great Use of foreign Manufactures for wearing Apparel, Furniture, &c. whereby the poor of other Countries are partly imployed at our Expence. The manufactured Goods we export bear no Proportion in Value to those we bring in; we must therefore send out our Product to purchase Clothing for the Rich, while the Poor must either starve at home, or go abroad to seek their Bread, where it is to be earned by Labour and Industry.

'Many Schemes have been framed to cure these Evils, but in vain. Numbers of Gentlemen have, at different Times, entred into Resolutions, to use no foreign Manufactures: But these could have no Effect, because we had no Manufactures of our own to serve them; nor indeed can any Nation, where the Poor are imployed in Manufacture, serve itself with every Thing. It is

enough to have one Staple which sells to Advantage in foreign Parts, and to be capable to export it in such Ouantities, as may be equal in Value to all the foreign Goods we consume at home. An Attempt of this Kind would be to hurt and ruine our Staple. Where too many Irons are in the Fire at once, some of them must cool, and where the Staple-manufacture of a Country is neglected, and no other Branches of Business brought to Perfection, the whole will run a Risk of being lost; for Mankind, generally speaking, prefer their own private Interest to that of the Publick, and will hardly be prevailed on to buy the Manufactures of their own Country, if foreign Goods of the same Kind, and of the same, or of a better Quality, are to be purchased at a lower Rate. Every one buys where he finds his Commodity best and cheapest; and unless our own Manufactures are as good of their Kinds, and s as low in their Prices as the same Goods of other · Nations are, they will not sell either abroad or at home. Trade cannot be forced, but Manufacture may be 'improven.

Linen Cloth is our Staple-commodity, and a Manufacture we have been possest of now Time out of Mind: It is carried on by private Hands, the only Way in which a Manufacture can thrive or prosper; it is a Commodity of universal Use at home, and of great Demand at those Markets abroad, where we purchase foreign Goods of divers Kinds, which we neither can want, nor can we make them our selves without Lossy it is a Manufacture capable of employing all our spare Hands, and, was it fully improven and extended, it would be sufficient to answer our all Demands for foreign Commodities. But it has been miserably neglected and

discouraged; it has suffered from many Causes, and from none more, than the indiscreet and fruitless. Attempts that have been made to introduce other. Manufactures, which are already brought to Perfection, and carried on with all possible Advantages by other. Nations, and by these inconsiderate Resolutions to furnish our selves with every Thing, without the Aid of foreign Trade.

'Had all the Money that has been sunk and lost by publick and private Companies, and private Persons, upon these Projects, been imployed in the Improvement and Extension of the Linen Trade, those Evils we have so long complained of, had been long ere now cured and prevented; but our Thoughts were, from Time to 'Time, turned upon new Projects, which we pusht up 'Hill with great Eagerness, until they became too heavy ' for us, while our Linen Trade, which we could have carried on with Profit and Success, was intirely neglected. Ever since the Beginning of the Confusions in the Reign of King Charles I. it has been upon the Decay, and our Manufactures of Silk Goods, fine broad Cloths, and 'several others of less Moment, which were introduced at a great Expence, and too long carried on with Loss to the Nation, have nevertheless, in a great Measure, totally failed. We have been long sensible of this, and the present Generation saw the Linen-manufacture 'reduced to a very low Ebb, but saw an evident Possibility of retrieving it, if we bent all our Thoughts that This was our Condition when the Royal Boroughs, who are the Guardians of our Trade, took under their serious Consideration the State of our 'Trade and Manufactures in their general annual Conevention held at Edinburgh in July, in the Year 1725.

and in several subsequent Meetings, of their grand annual Committee in that Year.

The Society for the Improvement of Agriculture, and several private Persons, who understood Trade and Manufactures of different Sorts, gave in Proposals and Schemes, for the retrieving our Manufactures and Fisheries, to these Meetings; and Committees of that Society, and other Gentlemen, from several Parts of the Country, likewise attended and assisted at these Meetings: The Result of all which, was, that in their Meeting the Seventeenth of February 172% they unanimously resolved to address his Majesty, and to make a oproper Application, by their Representatives in Parliament, and other Persons of Distinction then at London, who were capable to serve their Country, to have the Monies (settled by Law for the encouraging of our Manufactures) effectually applied for that Purpose, in such a Manner, as that all Misapplication of them might be absolutely prevented; and the Royal Boroughs appointed one of their Number to repair to London, at their Expence, to make this Application effectual.

The effect of this was, that his late Majesty was graciously pleased to write the following Letter to the Royal Boroughs, which was presented to the Convention by his Majesty's Advocate, one of their Number, upon the Sixth of July 1726.

## Superscribed George R.

"Trusty and well beloved, We greet you well. We having observed, that the several Sums of Moncy reserved and provided by the Treaty of Union, and by divers Acts of Parliament, to be imployed for the Improvement of Fisheries and Manufactures in Scotland,

" have not hitherto been applied to the Uses for which "they were intended principally, because no particular "Plan or Method hath been concerted, directing the " Manner in which those Sums should be applied for the And being desirous to remove that " said Purposes. "Hindrance, as speedily as may be, We have thought " good to recommend it to you, that, at your first general "Meeting in the Month of July next, you do take into "your Consideration the State of the said Fisheries and " Manufactures, and of the Monies provided for encour-"aging the same, and that, by yourselves, or by Com-" mittees of your Number, you do devise and propose "the particular Methods, Rules and Regulations, which " to you shall seem the most proper, for the Application " of the said Sums towards the encouraging and pro-" moting Fisheries, and such other Manufactures and "Improvements in Scotland, as shall most conduce to the "general Good of the united Kingdom; and that you "do return to Us the Propositions in which you shall "have agreed, to the end, that, upon due Consideration "thereof, a certain Method may be settled for the Appli-"cation and Management of those Sums for the future. "The Welfare of our loving People of Scotland, and the " Prosperity of the Royal Boroughs, is so much concerned "in what We recommend to you, that We doubt not "you will go on in the Execution of what is expected " from you, with the utmost Diligence, Unanimity, and " Impartiality: And, on Our Part, We assure you of Our "Countenance and Encouragement in what you shall " propose for the real Good of your Country, consistent "with the general Interest of Our united Kingdom. " And so We bid you heartily farewel. Given at our "Court of Kensington the seventh Day of June 1726. in "the twelfth Year of Our Reign. Counter-signed by his Majesty's Command. Holles Newcastle."

tion prepared and agreed upon an Answer, wherein they exprest their great Joy and Gratitude to his Majesty, for his tender Concern for the Welfare of this Country, and for that particular Instance of his great Goodness towards them, which must fill the Hearts of all his loyal Subjects in this Part of Britain, and promised, with great Cheerfulness, to prepare without Loss of Time, by themselves and Committees of their Number, Propositions to be laid before his Majesty, for answering the Ends of his Majesty's most gracious Intentions.

"Upon the Eighth of July a large Committee was appointed to consider and devise such Methods as might most effectually answer his Majesty's most gracious." Intention of encouraging the Trade of Fishing, and other Manufactures of this Part of the united Kingdom, and impowered them to receive Proposals relative thereto, from any particular Royal Borough, or any other Society, or private Persons, &c."

"On the Twelfth of July particular Instructions were drawn up for this Committee, who were to sit after the rising of the Convention, and were appointed to have their Plan in readiness to be laid before the next Convention, which was then appointed to meet at Edinburgh upon the first Wednesday of November following. This Committee was directed to take the Advice and Assistance of, and to consult with all Persons who had Skill and Experience, in any of the Branches of Trade or Manufacture that might be propos'd to be improven, and were specially directed in their Plan to propose a Method for the Application of

"the whole Monies that might annually arise for the Purposes intended by his Majesty, in such Manner, as the Distribution might be diffusive, and secured cffectually against Misapplication; and, as it might not be charged with the ordinary Expence of Management, it being the Intention of the Convention, from their earnest Desire to promote the publick Good, and thereby, to the utmost of their Power, to second his Majesty's gracious Intentions, voluntarily to propose, that they should defray the ordinary expence of Management."

'This Committee met very often to receive in, and consider Proposals that were sent them from different Places of the Country, upon the Subject-matters committed to them, and, at all those Meetings, several Gentlemen, skilled in Trade and Manufactures, who were not Members, assisted; and upon the Eighth of · November 1726. they presented to the general Convention a particular Plan for the Distribution and Application of the several Funds destined by Law for the Improvement of Fisheries and Manufactures, to be laid before his Majesty, which, after due Consideration, and some 'Amendments made, was approven of by the Convention. The Sum of this Plan is ingrest in his present 'Majesty's Letters Patents, bearing Date at St. James's July 5. and passed the Seals July 18. 1727. which are printed.

'The Convention, at the same Time, appointed their annual Committee to prepare the Heads of an Act of Parliament for regulating the Linen-manufacture; and the annual Committee did, the same Day, pursuant to the Powers and Instructions given them by the Convention, take under their Consideration, "That the

" future Happiness and Welfare of their Country, very " much depended on the Success of their Proposals, and that it was their Duty to do every Thing in their "Power to make the same effectual, and did authorize " and impower one of their Number to repair to London " upon their Expence, and there, in Name and Behalf of " the Royal Boroughs, to lay before his Majesty, in cobedience to his most gracious Letter, the general and " particular Plans agreed upon by the Convention, for " promoting the Fisheries and other Manufactures of " this Part of the united Kingdom, and Distribution of " the Funds to the particular Purposes therein mentioned, " and to endeavour to obtain such Acts of Parliament as " might be most effectual for promoting, encouraging, " and regulating the Linen-trade, agreeable to the Heads "then approven by the said Committee." All which are contained in the said Act of Parliament itself, which was past that same Session of Parliament; and this Act was printed by itself, and several Thousand Copies of it were dispersed.

In consequence of this Application from the Royal Boroughs, another Act of Parliament was past that same Session, directing the Appropriation of all the Funds formerly provided by Parliament (which till then had never been applied) to the several Purposes for which they were designed. These Funds are severally enumerated in the Act itself, and are particularly resumed in his Majesty's Letters Patents, wherein, pursuant to the Powers vested in the Crown by the said Act, the several Uses and Purposes to which they are to be applied, are specially directed, and, agreeable to the Act, Twenty-one Commissioners and Trustees are therein named and appointed, and the several Matters

committed to their Trust, are therein likewise specially directed: And I shall here beg Leave to refer the Reader, for his better Information, to the Patent itself, which was printed by Order of the Trustees.

These Commissioners and Trustees, pursuant to the Directions of the Charter, held their first Meeting in the Borough Room at Edinburgh upon the Twentieth of July 1727. and then proceeded to lay down proper Rules and Methods for their own Procedure, and directed Books to be prepared for that Purpose. In concert with the Royal Boroughs they made Choice of a well-qualified Gentleman to be their Secretary, whose Conduct ever since has very much justified their Choice. His Sussiciency, Diligence, Accuracy and Exactness, and singular Fidelity in the Discharge of this great Trust committed to him, have given universal Satisfaction.

'The Trustees, in obedience to the Directions given them by their Charter, applied themseves directly to the first Part of their Work, namely, to prepare and form a particular Plan of Distribution of the Funds, upon the several Conditions therein specially set forth. This Plan was finished, printed, and publish'd the seventeenth of November 1727. to which I also beg Leave to refer the Reader for a full Information.

The Rules and Regulations, appointed, by the Act of Parliament, to be observed in the Linen-manufacture, took Place the First of November in the same Year 1727. Since this Period, we have happily turned our Eyes upon the Improvement of our Manufactures, which is now a common Subject in Discourse, and this contributes not a little to its Success. People thereby pick up Knowledge and Information, by Degrees, of our Faults and Defects in the Management of our Manufactures, and of the proper Ways to cure and amend them.

The Trustees bestow their Time and Attendance upon the Service of the Publick without Fee or Reward. And I observe, from their Minutes, that their Meetings are regular and frequent. It appears almost from every · Sederunt, that their Service is of great Use and Importance to the Country, and contributes greatly to advance the Improvement and Extension of our Fisherics and Manufactures of every Kind. Many missive Letters, for the Solution of Doubts and Questions, Petitions and Applications for Encouragements of various Kinds, ' upon different Branches, &c. Memorials and Complaints of Abuses, Defects, slovenly and unprofitable Practices in the Management of many Parts of the Manufacture, and Proposals of Improvements, and of the most frugal and expeditious Methods of carrying on several Branches to the best Advantage, are frequently sent to the Secretary from every Corner of the Country. And I observe, ' from their Minutes, that all these are always duly ' weighed and considered by the Trustees, and Satisfac-'tion, by regular Answers, given to the Persons who send them. The good Effects of a Correspondence of this Kind are obvious.

I might here enter into a particular Detail of the whole Proceedings of the Trustees, from the Commencement of their Trust, to this Time, were it not that such an Account would swell this Preface to a greater Length than the Discourse itself; and that their whole Conduct, in the Distribution and Application of the Funds, under their Care, in each Year, is summed up in their annual Report to the King; and that, pursuant to the Directions of his Majesty's Charter, a Duplicate or true Copy of this Report is annually given in, within thirty Days after Christmas, to the annual Committee of

the Royal Boroughs, and is by them laid before the general Convention in July thereafter, where it lies upon the Table during the Sitting of the Convention, to be perused by all the Members; and that these Reports are all in the Hands of the Clerks to the Royal Boroughs, where any Person may have Access to see them; any Person may likewise have Access to the Minutes of Procedure of the Trustees, at any Time, in the Hands of their Secretary.

Persons of all Ranks express, on many Occasions, a generous Concern for the publick Good, and an honest Curiosity to be particularly informed of the State and Progress of our Manufactures, since they have become the Objects of the Care and Concern of the Publick; what Effects the Observations of the Regulations of the Linen Act of Parliament have had upon the Improvement of Linen Cloth in its Quality; what new Branches of that Trade formerly unknown to us, have been introduced at the publick Charge: How far these are already improven; and what other Parts are still to be introduced, improven and extended, and how far the Application of the publick Funds, destined by Law for the Encouragement of our Fisheries and Manufactures, have already contributed towards these Ends.

Many are desirous, and have been long expecting to see something publisht upon this Head; and the Author observing that nothing of that Kind hath hitherto appeared, he lately resolved, notwithstanding of the just Sense he has of his own Unfitness for the Performance, to bestow as much Time (as his necessary Attendance upon his own private Affairs would allow him) to reduce his Observations on this Subject, in which he has been pretty much conversant, to Writing, to the end

that others of better Skill, and more Knowledge in these Matters, may be excited to Publish something of the same Kind to better Purpose. And now, that nothing of this Sort appears from any other Hand, he has adventured to send it abroad, such as it is, and submits it to every Reader, who, he hopes, will consider it with the same View he had in it, namely, to create a Spirit of Industry and Diligence in the People, to promote the Improvement and Extension of our Manufactures, at least of such of them as are, or may be carried on with the greatest Profit, upon which the Happiness and Prosperity of this Country depends.

In the first Part, he takes Notice of Idleness, and the bad Effects of it, as it hurts Individuals, and as it affects the whole Body of the People nationally; and proposes a few Rules of Police, for suppressing of Theft and Begging, and imploying of the Poor in Work-houses. He then speaks of the Causes of the Non-improvement of our Grounds, and of the great Advantages of Agriculture; and proposes the same Method for the Improvement of our Lands, by which the Estates of England were at first improven.

In the second Part, he treats of Industry as the Source of national Wealth and Power, and of the common Motives to Industry; of Trade and Manufactures in general, of our Trade in particular, and of the Staples manufactures of England, and of this Country; of the Causes of the Neglect and Non-improvement of our Staple; of such Branches of Manufacture as are now carried on with Loss; of several Trades that now are, and are liable to be overstockt, and proposes some Methods to prevent this; of the Improvement and Extension of our Staple, as the only Way to imploy

\* all our spare Hands of every Condition; of the Plantation Trade, and the great Benefit of these Settlements in America to their Mother Country, especially if they were duly encouraged to raise Materials for Homemanufactures; of the Necessity of the Improvement and Extension of the Manufacture of home-made Linen Cloth in Scotland, England and Ireland.

In the third Part, he gives a particular Account of the State and Condition of the Linen-manufacture of this Country, as it is at this Time, and of its Progress since the First of November 1727. Upon Perusal of this Part since it was printed, he observes something, he intended to have spoke of, omitted, namely, a bad Practice in the Sale of Linen Yarn, of false and short Tale notwithstanding of the Directions of the Act of Parliament to the contrary.

This is said to be owing to the Use of Hand-reels, a Method of making up Yarn so uncertain and precarious, that no Persons who use them, can possibly be exact in their Numbers of Threads. No Buyer can pretend to tell the Threads of every Cut of Yarn he buys, much less can the Stamp-master controul the Tale of all the Yarn that is presented to Sale in a Fair or Market; and as Yarn can be subjected to no Stamp or other certain Check, if the Buyer discover not the Fraud until he come to sort his Yarn for Use, it will then be too late for him to recur upon the Seller.

The most probable Way to cure and prevent this Evil, is to introduce the Practice of Check-reels every where, and if the Funds appropriated for encouraging the Linen-trade might allow it, it is propos'd that the Trustees, for the more speedy furnishing of the Country with Check-reels, might give annually a certain Number,

by Way of Prizes upon Spinning, in the same Way that spinning Wheels are propos'd to be given at the small spinning Schools: And when any Alteration or Amendment of the Linen Act of Parliament is propos'd, the Use of Hand-reels may be discharg'd, and every false Tale of Yarn subjected to a severe Penalty, because every Mistake in a Check-reel must be made with a fraudulent Intention to deceive the Buyer.

Another Practice discharg'd by Law, still prevails in several Places in the North, that proves a Loss to the Spinners, which is the Use of the eleven-quarter Reel, altho' the Act directs that all Yarn shall be made up by the ten-quarter Reel, being two Yards and an Half, or ninety Inches in Circumference, and that all Reels, wherever found, other than 2½ Yards, or 90 Inches in Circumference, shall, at the Sight of the proper Officer, be destroyed, and all Yarn otherwise made up shall be confiscated. All Stamp-masters ought therefore to be strictly enjoined to make diligent Search for all such illegal Reels, and to seize all Yarn otherwise made up than as the Law directs.

The Use of Weights and Scales is the only sure Way to prove Yarn, both as to its Quantity and Fineness; every good Weaver uses this Method in making
up a Parcel of Yarn for every Piece of Cloth, because
he discovers, to a Certainty, if all the Yarn intended to
be used in the same Piece, is precisely of the same
Fineness; for two equal Quantities, or Cuts of Yarn,
containing the same Number of Threads each, and each
Thread of the same Length, if they differ in Weight,
must also differ in Fineness. This Practice would
likewise be of great Use to the Dealers in Yarn; they
have no more to do than to tell one Cut, and to prove

call the rest by Weight with it, and every Cut that differs in Weight, must likewise differ either in Fineness, or in Tale and Quantity.

. The Parliament of Ireland give great Funds for the Improvement of their Linen-manufacture, no Defect is sooner discovered, that can be supplied by Encouragement, than it is done. The Trustees in Ireland gave, at one Time, 10000 Check-reels, which were all made, and sent and distributed to the Spinners in different Places of the Country, at the publick Charge; they also at several Times have made great Numbers of good Looms, completely mounted, of the best Kind, and give them gratis to the best Weavers. They are likewise careful to remove, by publick Laws, every Thing that has the least Appearance of a Discouragement to the Linen-trade. They, by Act of Parliament, exempted Linen Cloth of every Kind from the Payment of all e petty Customs, or small Duties that were in Use to be s paid upon it at weekly Markets and Country Fairs.

'This Act well deserves our Consideration, to put our Linen-trade upon the same Footing of Freedom and 'Immunity with that of Ireland. Those petty Duties are a Part of the Revenue of those Boroughs and Towns, where Linen Cloth and Linen Yarn are sold at weekly Markets and Fairs; and a very small Part of the Revenue they are; for the collecting of them costs very near as much as they yield. The Manner of raising those small Customs occasions frequent Com-' plaints and Disputes between the Dealers and Collectors, which hurt the Dealers, in their Imagination, and the · Communities themselves in Reality: For when the Dealers take Offence, they often fall on Ways to dispose of their Goods, without bringing them to Market; and

this so far diminishes the Trade, and the Consumption
of Provisions in those Towns where the Markets and
Fairs are held.

The Town-council of Dundee had this Matter under their Consideration some Years ago, and very wisely they remitted the Duties that used to be paid on Linen Cloth. They struck this small Branch of their Revenue out of their Rent-roll, and exempted Linen Goods of every Kind from the Payment of Custom of every Kind. The Effect of this was, that numbers of Country Weavers, who used to carry their Cloth for Sale to the Towns that ly nearest them, where the same Duties are still levied, do now bring their Cloth to Dundee, although it lyes at a much greater Distance from them.

I must humbly beg Leave to submit this, with the other Matters proposed in the following Discourse, to the Consideration of the Royal Boroughs in their next general Convention, to be held in July 1734. They are the Guardians of Trade and Manufacture, and the chief Gainers and Losers by both: And when this Matter is duly weighed, they will, no doubt, prefer their real Interest, (which obviously depends upon the Improvement and Extension of our Staple-manufacture) to this imaginary Branch of a Trifle of Revenue, scarce worth collecting, and prepare a proper Application to Parliament for exempting Linen Goods of every Kind from the Payment of all Duties and petty Customs whatever, either at weekly Markots, or in Country Fairs.

The Parliament of Ireland did likewise (for the Encouragement of Weavers) by a public Law, allow any Weaver to set up and carry on his Trade in any Town for Incorporation in the Kingdom wherever he pleased,

onotwithstanding any Monopolies or seclusive Privileges that had been formerly granted in favours of any Company or Corporation of Weavers. The Weavers in this City are indeed exceedingly easy upon this Head, they are in Use to admit any good Tradesman to the Freedom of their Incorporation, upon Terms that are easy and reasonable: But if any Foreigner or Stranger, who is a 'good Weaver, inclined to set up his Trade in any Town or Burgh, without being a Freeman or a Member of the Incorporation; it would prove a very great Encouragement to the Linen-manufacture, if they were allowed to work and carry on their Trade, where they imagined they could do it to the best Advantage, upon this single Condition on their Part, Residence, and weaving of good Cloth as the Law directs: And if all Weavers were likewise excemed from all publick Burdens, and Parishoffices, it would be the better, and contribute much to 'increase their Number.

It is observed, that any diligent young Lad, of an ordinary Genius, who applies himself close to his Business, can work and finish a Piece of Cloth very well under the Direction of a good Master, when he has been but two Years at the Trade: But it is found from Experience, that no man ought to be intrusted to sort and size a Parcel of Yarn, to warp, put in the Loom, weave and finish a Piece of Cloth by himself, before he has wrought constantly six or seven Years at least, under the Eye of a skilful Master. It is therefore proposed, when any Amendment is made to the Linen Act, that there ought to be a Clause in it to this Purpose, to restrain any Weaver from setting up as a Master, until he has wrought constantly under a good Master or Masters for the Space of seven Years, and

then to be allowed to practise their Trade as Masters
wherever they please, upon finding Bail, as the Law
directs, to conform themselves to the Observation of
all the Rules and Regulations contained in the Linen
Act of Parliament.

In the fourth and last Part of this Discourse, the Author takes notice of the Advantages of our Situation in an Island, that our Security depends chiefly upon our naval Force, and that our Navigation depends chiefly upon our Fisheries, which ought therefore with great Care to be encouraged. He speaks of several Discouragements and Hardships, that several Branches of our Fisheries labour under at present, and proposes some Methods for relieving them, and of several probable Ways for improving and extending our Fishing-trade in every Branch, by proper Encouragement.

\*Throughout the whole of this Discourse, the Author has spoke his Mind, with Freedom, of our Abuses, bad Habits, and unfrugal Practices of our Tradesmen and Dealers of different Kinds, as they occurred to him; and in this, he hopes, he has given no Offence, as, it is apparent from his Manner of writing, he intended none. It is a Privilege peculiar to the Subjects of free States, to speak or write what they think, and to publish what they write, so long as they observe the Rules of Decency, and express that Regard and Respect for Dignities, and Persons of high Rank, and in high Offices, that the Nature, Peace, and good Order of every civil Society requires.

'The Liberty or Servitude of a Nation, appears as much from their Writings, as from any other Part of their Conduct in Life. Free States are liable to be disturbed by Faction, and Party-struggles for publick

Imployments: And their Writers, especially of History and Biography, discover a Biass for that Side to which they are attach'd; but both Parties speak out their Sentiments with great Boldness and Freedom. Indecent Liberties are often taken with Men in Power, and even these are sometimes of Use; they serve to check and controul the Conduct of great Men, to put them on their Guard to confine themselves, in all their Actions, within the Bounds prescribed by Law, which is their greatest Security. The Conduct of Princes, Ministers, and other great Men, is, in free States, variously represented, as the several Writers affect; but, by comparing the Accounts of both Sides, the Truth is easily discerned.

Whereas, under arbitrary Governments, their Writings are stuft with Panegyrick and fulsome Flattery:
Every Man in Power is a great and a good Man, at least
so long as his Power remains with him; and the worst
and weakest of Princes are dubb'd with the Characters
of the best and greatest, so long as they live. The same
Characters are given to a Julius Cesar, or an Oliver Cromwel, (who betrayed their Country, and trampled upon
Law and Liberty) that properly belong to a George Castriot,
a William Wallace, or a Prince of Orange, who spent their
Lives in the Defence of Law and Liberty, and devoted
themselves to the Service of their Country, to rescue the
People from Servitude and the Bondage of a foreign
Yoke.

When an enslaved Nation have the rare Happiness to be blest with the Reign of a Titus or a Trajan, then, and not till then, the Truth and true Characters of former Tyrants come out: Then the Spirit of Liberty revives, and Truth is allowed to walk abroad in Daylight, during the short Season of such a Sun-shine.

This is apparent from the Writings of Tacitus, where the justest Sentiments of Liberty, and the strongest Disposition to assert it, appears almost in every Page: But so strong an Impression do the Restraints of Tyrants make upon the Minds of Men, that Tacitus appears, or many Occasions, to be under a Kind of Awe and Dread of going too far: So terrible is uncontroulable Power, even in the Hands of the best of Princes:

The Author submits his Observations, upon the several Subjects he treats of, to the Examination and Judgment of every candid and impartial Reader; and hopes, those who discover any Errors, Mistakes, Defects, or Omissions, will publish their Remarks with the same Intention that he has done, for the Benefit of the Publick: Or if they incline not to put themselves to that Trouble, if they transmit them to Mr. Flint, Secretary to the Trustees, where the Author may have Access to see them, they may be published by Way of an Appendix or Supplement to this Discourse; or if another Edition shall be wanted, by Way of Notes, in the proper Places to which they refer.'

In a subsequent part of the work, the author gives, in a note, the quantities of linens, stamped during the first five years after the passing of the Linen Act, which I shall also copy.

• The Linen Act of Parliament commenced the first • November 1727. There was stamped for Sale the first • Year preceeding first November 1728. in the West, and • Countries on the Southside of the River of Tay.

	Yards.	Value.		
In the Countries 3,1,136,723	1,047,2544	L.66850	10	01
	1,136,7234	L.36461	18	11
'Total Quantity,	2,183,978	L.103312	09	08

```
Second Year preceeding first November 1729.
South, - - - 1,213,013\frac{1}{2}
                                 L.59815
                                           14
                                                09
North,
        - - - 2,012,142<del>1</del>
                                    54568
                                                114
                                 L.114383
4 Total,
        - - - 3,225,155}
                                           19
                                                08<sup>7</sup>
'Increas'd 1729.
                 1,041,1771
                                    11071
                                           10. 00
      'Third Year preceeding first November 1730.
South,
         - - 1,537,011
                                 L.68777
                                           00
                                                094
North, - - - 2,218,651
                                    62485 15
                                                027
'Total,
        - - - 3,755,622;
                                L.131262
                                           15
                                               114
Increase, - -
                    530,5061
                                    16878
                                           16
                                               03:
     Fourth Year preceeding first November 1731.
'South, - - - 1,621,6791
                                 L.79477
                                           18
                                                044
North, - - - 2,269,93½
                                   66178
                                           15
                                               101
                   3,891,573
                                L.145656
'Total, - - -
                                           14
                                               03
Increase, - - -
                    135,9101
                                   14393
                                           18
                                               03
     'Fifth Year preceeding first November 1732.
'South, - - - 1,751,0384
                                               07
                                 L.86566
                                          17
North, -
           - - 2,633,7944
                                   81955
                                          17
                                               034
                                L.168322
                                               101
'Total, - - 4,384,8321
                                           14
                    493,2594
                                   22666
                                           00
                                               074
Increase, - - -
  'This is besides Cloth made for private Use, of which
clarge Quantities of high pric'd Cloth for Shirting have
been lately made since the Commencement of this Act.
'The Values are taken up by the Stamp-masters at the
· lowest Estimate.
 Increased in five Years, in consequence of the
Execution of this Act of Parliament, and the small
```

Fig. 7 Encouragements in Quantity, - - 2,200,854. Yards, Fin Value, - - - - - L.65,010 5 2

In the year 1784, the quantity was 19,138,593 yards, valued at  $L.932,617:1:11\frac{1}{4}$ ; so that, from the year 1732, until 1784, the increase of yards was  $14,753,761\frac{1}{4}$ , and of value  $L.764,294:7:6\frac{1}{4}$ .

The author, it will be observed, ascribes the promotion of the linen manufacture and its extension, during the years which he quotes, to the salutary effects of the Linen Act, and this encourages him to offer many proposals of restriction and encouragement, some of which have been enumerated. But the unprecedently rapid improvement of the manufacture of cotton, which was then hardly known, and which was not prosecuted to any extent until many years afterwards; with which the legislature have scarcely, if at all, interfered; which has neither been cherished by bounties, nor fettered by statutory restrictions, affords sufficient grounds to doubt at least the truth of his hypotheses, and to trace the extension of manufactures to very different causes.

It is a very trite observation, that mankind will always purchase where they are cheapest and best served, but its truth cannot be disputed, and it applies forcibly in the present case. The invention of the art of spinning cotton by machinery, which originated in England, and which, whether invented or not, was brought into practice by the late Sir Richard Arkwright; and the many subsequent improvements which have been made in that art, are, unquestionably, the primary and consequent causes of the almost incredible extension of the cotton manufacture. The first web, entirely of cotton, which was woven in Scotland, was manufactured by Mr. James Monteith of Anderston, near Glasgow, about the year 1773. Both the warp and woof of this web were spun in this country by women, upon the common small wheel.

The introduction of cotton warps in Lancashire was not much earlier, for the first calicoes were made in 1772. Little, however, was done in weaving goods wholly of cotton, until the water, or engine twist, was generally introduced about 1780. Some water twist was indeed brought to Scotland for sale, so early as 1776, but it did not begin to be generally used for warps until some years afterwards. From that period, the manufacture began gradually to extend, and the invention of the mule jenny, which came generally into use a few years afterwards, enabled the spinners to produce warps fitted for much finer muslins, than any which had been spun upon the water frames. The manufacture now extended with astonishing rapidity, and the application of power to drive the mules, together with many other improvements, both in the machinery and economy of cotton mills, whilst they daily ameliorated the quality of the yarn, rapidly reduced the prime cost of This, again, very soon produced a it to the spinner. competition, which by generally supplying, and frequently overstocking the market, reduced the price to the manufacturer; and the same competition naturally arising among manufacturers, the prices, as will ever be the case under similar circumstances, were lowered to dealers, and, consequently, to consumers. The want of stamp-masters, bounties, penalties, &c. have never been felt in the cotton trade; and, consequently, it is fair to presume, that whatever extension has taken place in the linen, was not occasioned by the operation of these expedients.

Some frauds, indeed, must have been practised, where goods could not be sufficiently examined by the purchaser, and to these the cotton is equally exposed as the linen yarn, for it is equally impossible, in either case, to count or examine every thread. But these have always been found

to cure themselves, without the necessity of legal interference, by the loss of character, and consequent difficulty of sale which they occasioned. The same consequence has always resulted after the yarn has been manufactured into cloth; for the price has, in general, borne a pretty fair proportion to the quality, when the goods were of a similar description, and equally in demand at the particular market. It is, however, fair to admit that some restrictions, for the prevention of frauds, might have been necessary, when the inhabitants of a country were little acquainted with the principles of trade; but these restrictions become totally useless, and often vexatious, at a more advanced period.

At the present advanced stage of the cotton manufacture, a good spinner, with the assistance of three children, can work two power-mules of 300 spindles each, and from every spindle of these two machines, can produce, of an average fineness, say No. 72, 12 hanks of 840 yards each, weekly, making in all 7200 hanks, or six millions and forty-eight thousand yards, when the mules are well constructed, and the stuff good, and well prepared. What the reduction of labour is between this and the old practices of spinning by the distaff or common wheel, it is not easy to ascertain, for to the labour of the spinner, is to be added that proportion of the labour of all those, employed in the preparatory processes, which are necessary to supply him with materials. Besides the number quoted, 72, although now esteemed rather coarse than fine, is very much finer than any thing ever spun in this country in the old way. I have heard the reduction of labour estimated at the proportion of 200 to 1, but I should suppose it much more.

The position of Dr. Smith, that "It is the natural effect

of improvement to diminish gradually the real price of almost all manufactures," was never, perhaps, more strikingly exemplified, than in this manufacture, which has entirely arisen since his work was published. No. 73, was currently sold in the year 1787, for thirty-six shillings and sixpence per pound weight. In 1792, for nine shillings and eightpence-halfpenny; and in 1807, for four shillings and fourpence-halfpenny. During the same period, the raw material has, upon the whole, rather advanced than declined in price, fluctuating between two and three shillings per pound. Occasional scarcity has, indeed, at times, produced a temporary rise of price, and when the market was again fully supplied, a depression has taken place in this, as in all other commodities. On the average, however, the money price has not varied greatly, the exchangeable value may perhaps rather have sunk, for the price of freight occasioned by the war premium of insurance, and the rise of seamen's wages, naturally form part of the money price. Taking, therefore, the average price of cotton wool, fit for this number of yarn, during these years, to have been two shillings and sixpence per pound (which is very high) in the first price quoted (1787), the price of labour, interest of capital, waste of machinery, and spinner's profit, will be thirty-four shillings. In the second (1792), seven shillings and twopence-halfpenny; and in the third (1807), one shilling and tenpence-halfpenny. In the last instance, the price of manufacturing is, probably, more than the calculation gives; but the comparison between the value of the material in its raw state, and after being spun, does not affect this calculation more than the others, perhaps not so much; for it will be observed, that the two years, formerly quoted, were years of peace, the last a year of most extensive war.

During the same period, the general price of labour has constantly increased; a very singular proof of the prodigious efficacy of judiciously applied improvement in the mechanical arts.

In the manufacture of linen, and other goods woven from flax, no reduction of labour to nearly equal extent has been effected. Machinery for spinning flax has, indeed, been invented, and constructed upon a plan pretty similar to that used for cotton. This machinery has been found useful in effecting some reduction, especially in the coarser kinds of linen yarn; but the very nature of the raw material presents obstacles to the improvement of the spinning of flax by machinery, which do not exist with regard to cotton, nor even in the same proportion The fibres of flax, although very strong, with wool. from their length, and inelasticity, are not nearly so well calculated for the process of drawing by rollers as the cotton, which is short in the staple, and extremely elastic. Further mechanical inventions and experiments, if judiciously conducted, may, no doubt, still greatly improve the art of spinning flax, but there seem to be unsurmountable physical objections, to its ever becoming a rival to the cotton in price.

Here, then, seem natural reasons, sufficient to account for the very different advances which these two manufactures have made. The linen trade, like a ricketty child, unable to stand upon its own legs, has constantly required to be cherished and fostered by bounties. That, at this moment given upon the coarse goods, manufactured chiefly in the county of Angus, is not less than twenty-five to thirty per cent. ad valorem. The cotton, on the contrary, from the superior facilities which it presents, has, by the mere enterprise of individuals, risen with the

growth of a giant; so far from requiring aid or encouragement from the state, the rave material has been for some years an object of taxation; and, short as its course has been, it has already reached that advanced stage of trade, where the chief difficulty lies in finding markets and consumers for the supply.

The great reduction of labour, and, consequently, of price, which has taken place in the cotton manufacture, lyes, however, almost wholly in those stages of the process of manufacture, which bring the raw material into yarn. Much has not yet been effected in the weaving, nor does it appear to afford facilities, nearly equal to those which presented themselves, and have been seized upon in the spinning. The great improvement in the quality of the yarn, and the dexterity acquired by extensive practice, have, no doubt, considerably reduced the prices of weaving, but a good deal remains still to be done.

In a national point of view, this has become of very great importance, for the high price of labour in this country, renders every means of facilitating all the operations of manufacturing, not only peculiarly desirable, but essentially necessary.

Until the continent of Europe was almost completely shut against us, the immense exportation of cotton yarn has sufficiently proved, that our great superiority lay in the spinning, and that, in many instances, foreigners have found it, at least, equally beneficial to employ their own looms, as to purchase cloth in this market. Considerations such as these have actuated a number of persons, for some years past, to endeavour to reduce the expence of weaving, particularly plain coarse goods, by various mechanical contrivances, and modes of economy. Of these I shall now endeavour to give some account.

Cotton yarn is wound upon the spindle, in the form of a cone, and these are called cops. The usual practice has been to reel these cops into hanks, for the conveniency of starching, dying, or bleaching, when required. When plain white goods are to be manufactured, starching only is required for the warps; for the process of bleaching takes place after the yarn has been made into cloth. After starching, the next process is winding, and then warping, as noticed in the first Essay. The first means of saving labour, are by the omission of the process of reeling, and by winding the yarn at once from the cop upon the bobbin, by means of a machine, by which a number of bobbins are wound at the same time. To accomplish the starching, different experiments have been made.

It has been considered a very desirable object, if practicable, to starch and dry the yarn in the cop, before undergoing any of the subsequent processes. The chief obstruction was found to arise from the dense form in which the yarn was rolled together, which rendered it difficult both to impregnate the cop thoroughly with the starch, and afterwards to dry it. To remove the first, an expedient was found, by exposing the cops to the operation of the starch in an exhausted receiver; for it was considered, that when the pressure of the atmosphere was removed, the starch would penetrate easily to the very heart of the cop. Upon trial, this was found to succeed very well, but the drying was still found excessively tedious, and the glutinous nature of the starch rendered the subsequent operation of winding very difficult. I am not aware that these impediments have as yet been effectually removed, nor that the plan of starching in the cop, has been brought into practice. The general mode, therefore, is to wind the yarn from the cop upon the bobbin, to warp the yarn by the common process, and to starch the warp in the chain. Of the winding machines, different kinds have been constructed, some driven by the hand, others by the foot like a turning-lath, and others by the application of power. The latter mode is unquestionably the best, where it can be applied, for where a number of bobbins are running at the same time, the person who attends the machine will be sufficiently employed in removing obstructions, knotting threads, which occasionally break, and other necessary operations, without being also obliged to drive the machine, either by the foot or hand. When power is employed, if the cops are well built, it is very seldom necessary to stop the machine, for any bobbin may be stopped without affecting the others. But when driven by the hand, or even by the foot, when any impediment occurs, it is generally necessary to stop the whole, until that is removed. By this, much time is lost, and, of course, the work produced by one person much less.

For the reasons already stated, I am sorry that I cannot give drawings of these machines. They are simple in their principle and operation. The bobbins are placed upon vertical spindles, similar to the spindle frame of a mule, and the spindles are driven by cotton bands, from a hollow tin cylinder, or drum, in the same way. The threads are traversed upon the bobbin, by a wheel similar to the common heart traverse, as it is called, used in water spinning. The most recent and best constructed, which I have seen, is that lately introduced by Mr. James Dunlop, at Barrowfield, near Glasgow. As the bobbins are in general wound rather in the form of a barrel than perfectly flat, Mr. Dunlop constructs his traverse wheel so,

that one side of it should wind the yarn equally on every part of the bobbin, and the other side so that the traverse should be gradually retarded at the middle of the bobbin. and accelerated at each end. By these means, more yarn is wound upon the middle than the ends, at every alternate traverse, and the yarn gradually arising in the middle, the bobbin assumes the barrel shape. A small quantity of starch is applied to the yarn during this operation, by means of a horizontal wooden cylinder, revolving on its axis in a trough filled with starch, over the upper surface of which the threads pass in their progress from the cop to the bobbin. It is calculated, that a woman, by one of these machines, can wind about 70 spyndles of yarn, of an average number, say No. 70 to 80, in a day. Eight or ten years ago, the price of winding No. 70, on the common wheel, was about twopence per spyndle. Although these prices are now considerably reduced, still a considerable saving must take place by using the machines, where business is conducted upon a scale sufficiently extensive to employ them constantly. In dyed warps, it does not appear that this plan of economy has, as yet, produced any beneficial effect. Yarn can only be dyed in the hank, and, consequently, the process of reeling cannot be saved. I have seen winding machines, constructed for the purpose of winding dyed yarn from the hank, but these machines were so frequently stopped by the breaking which took place, in consequence of the yarn being both weakened and matted together by the dye stuffs, that no saving, in point of expence, was effected by employing them.

A general system of economy in the manufacture of cotton cloths was, some years ago, introduced at Stockport, near Manchester, and partly imitated in Scotland; of which I shall now proceed to give some account.

This system, in so far as regards the preparatory processes, is not very much different from that already described. The cloths manufactured were plain, and rather coarse. A portion of warp, composed of water twist, was wound from the bobbins upon which it was spun, upon a roller or beam. A certain number of these beams being combined, the yarn was again wound from these upon another beam, which formed one half of the warp. By these means, the operations of winding and warping were wholly omitted. The warp received no starch in the process. The next object, was to avoid that combination of operations which form the chief obstacle to the speed of weaving. A machine was therefore invented, for the purpose of dressing a whole web, before it was put into the loom, that the subsequent operation of weaving might not be impeded. Two beams, each containing one half of the warp, being placed at opposite extremities of the machine, the warp was gradually wound from these beams, upon another beam placed in the centre, and elevated above the other parts of the machine. During this process, each part was supplied with the stuff for dressing, by means of a horizontal roller, revolving in a trough containing the stuff, in a manner similar to that used in the winding machine. The dressing was then brushed into the yarn, by means of two brushes, one applied to the upper, and the other to the under surface of the warp. These brushes received a motion, similar to that communicated by a weaver's hands in the common process; and this motion was effected by cranks, the brushes being sufficiently long to include the whole breadth of the warp. After this, the warps passing under rollers, placed to guide the direction, met upon the centre beam, immediately under which was placed an apparatus, consisting of a horizontal axis, to which were attached six or eight flat boards, diverging from the centre, like the radii of a circle. These, by a rapid motion round the axis, generated a current of air, for drying the warp after being dressed and brushed, previous to its being wound upon the receiving beam. During the process of dressing, the threads were kept distinct in the wet state, by passing through two or three coarse reeds, placed at convenient distances from each other. The lease was preserved by a set of heddles, through which the warp passed, after being dried, and before being wound upon the beam. Upon the beam were flanches of wood, to keep the selvages of the warp perpendicular, and the whole at an equal breadth.

The only improvement in the construction of the loom, was an apparatus for winding up the cloth as it was woven; and, consequently, saving the time necessary to shift the cloth at intervals, or, as it is generally called, to draw bores. The apparatus consisted of ratchet wheels, moved by a hanging catch, to which motion was given by a lever attached at right angles, to the upper extremity of the swords of the lay, above the centres. Some saving must, undoubtedly, have been produced by this plan, in weaving plain coarse fabrics; but many obstacles presented themselves against it. The chief of these obstacles occurred in the dressing.

It has been already remarked in the first Essay, that the stuff used for dressing, although it increases the strength, tenacity, and smoothness of the warp, is not fitted to resist the operation of the atmosphere for any length of time, especially when in a very dry state. It may be easily conceived, that in the early stages of weaving, especially in a cold or moist climate, this defect

would not excite much attention, nor produce much inconvenience. Weavers' shops, in those days, and even still, are almost universally upon the ground floor, and are only floored with earth. In consequence of this, the air in the shops is generally moist and humid, and from the process of only dressing a small portion of warp at once, and weaving it up almost immediately afterwards, little inconvenience is found. In one respect, the facility with which the dressing material is acted on by a current of air, seems rather advantageous. For, as the weaver dries his warp, after being dressed, merely by setting the air in motion by a fan, moved by his hands, greater difficulty of drying would both fatigue the operator and impede his progress. But in the efforts now making to improve the economy of weaving, nothing appears more likely to promote the end, than a total division of the labour of dressing and weaving, and this can only be fully effected, by dressing a whole warp at once. It will also be necessary, that this warp should be of considerable length to produce any saving. For as much time will be employed in drawing a short web through the heddles and reed, as a long one, or in twisting one web to the end of another. Now, until means are devised to preserve the warp in a proper state for weaving, until a whole web can be wrought, it does not appear that this object can be fully accomplished. Besides this, in establishing extensive manufactories and regular economy, it would be expensive and inconvenient, if not impracticable, to have all the buildings only one story high, more especially if the looms are to be driven by the application of power. I have stated, in the first Essay, the practice of weaving in India in the open air. Since the time when that Essay was written, I have earnestly inquired of different persons who have resided

in India, concerning the stuff used for dressing in that country; but I am sorry to say, that the results of these inquiries have been far from satisfactory. None of those with whom I have conversed, being immediately concerned with the business, any observations which they had made were merely cursory and transient. They agree, however. that the substance used is a decoction of rice, formed by boiling the rice with a small quantity of water, and then expressing the juice. This juice, when cooled, forms a thick glutinous substance. I have been also informed, that before using it for dressing, it undergoes a certain process of fermentation; but whether this fermentation is produced, or accelerated, by any mixture, or if it is entirely caused by the weather, I have not been able to learn. Whether also the stuff is used after undergoing a partial or complete fermentation, I am still equally ignorant.

In this country, the common flour or potatoe dressing, is generally considered to be better after it has been fermented, especially in very dry or hot weather. Yest or barm is, therefore, sometimes mixed with it, to promote fermentation. Butter milk is also sometimes added, and, as before noticed, herring brine or other saline substances. But while these experiments are only made by operative weavers, totally unacquainted with the laws of chemical combination; and while the warp is to be dried by the manual operation of the fan, there seems to be little reason to expect much discovery in this part of the art. It seems not unreasonable to conjecture, that any substance capable of adding to the smoothness and tenacity of the warps, and which would resist the operation of the atmosphere for a considerable time, if not too expensive for common use, would answer the purpose. It seems also probable, that a substance which, when dried,

would possess this property, must also require a much greater portion, either of circulation of air, or artificial heat, to reduce it from the wet to the dry state, in a reasonable time. But these are merely given as probable conjectures, and without a train of accurate and judicious experiments, it is not probable, that much practical benefit will be derived.

A second disadvantage, incidental to all the dressing machines hitherto contrived, has much impeded their practical utility. In the common process of dressing, the threads of warp, when in the wet state, have always a tendency to cohere, or stick together, and the agitation of the air, produced by the fan, naturally increases this tendency. To prevent this, the yarn is slightly brushed at intervals, while drying. The same tendency to cohesion, occurs in warps dressed by machinery, and presents a very great obstacle to their speed. The reeds through which the warp passes, are intended, in some measure, to remove this, but the great friction caused by the yarn passing through them in a wet state, and their tendency to be clogged by the dressing, are serious disadvantages. From these causes, threads are frequently broken, and when this is the case, the operation must be suspended, the machine stopped, and the warp left in a wet state, until these threads are repaired. When the threads are tied, it is necessary, in most cases, to pass them through all the reeds; and this, necessarily, occupies a considerable portion of time. Of course, when many are to be tied, the operations of brushing and fanning are so long suspended, that the warp frequently gets entangled, and is separated with difficulty, and often with more breakage. Besides this, when long exposed, it is

often too much dried and hardened by the mere action of the air, to be in a proper state for weaving.

A dressing machine, somewhat different in principle, was invented since, by Mr. Quintin Macadam, Anderston, and brought into practice by Mr. John Monteith, at his manufactory, at Pollockshaws, near Glasgow. For this machine, a patent has been obtained. The warp, as in the other, is wound from two beams at the ends of the machine, and after being dressed and dried, is lodged upon a beam in the middle. The chief novelty in this machine consists in the brushes, which are constructed on cylinders, similar to those of a carding engine. The circumference of these cylindrical brushes, being placed in contact with the under surface of the warp, they communicate the brushing by revolving upon their own axles. Upon each end of the machine, there are two of these cylinders, and two circular wooden fans to agitate the air. Between the brushes, the first fan is placed, to dry the warp partially after the first brushing. receives the second brushing, and is completely dried by the second fan, which is placed between the second brush and the receiving beam.

This mode of brushing the warp between the wet and dry state, assimilates the operation of the machine more to the common manual process, and may, in that respect, be productive of some advantage; but it does not appear, that the inconveniences arising from the chemical properties of the dressing, or the friction caused by the reeds, are more obviated by this machine than the former.

For another process, essentially useful in dressing yarn, no provision, whatever, is made in either of these machines. This is picking the warp, previous to the application of the dressing. With all the improvements in spinning, no

yarn is entirely free from inequalities, lumps, and snarls. Every good and careful weaver is at pains to remove these, and any knots which may have been carelessly tied in the preparatory processes, both to prevent obstructions in his sheds, and to improve the appearance of his cloth, when woven. As this process depends upon discrimination and selection, and consequently involves an operation of the mind, it is impossible to effect it by mere machinery. It seems, however, perfectly possible, that this part of the operation may be effected by human labour, and the remaining operations, which are uniform, by machinery, with considerable economical advantage. experiment of this nature was lately made, upon a small scale, by Mr. Dunlop, at Barrowfield, but has not as yet been sufficiently followed up, to enable us to decide practically upon its merits in point of quality, or of the saving The machine constructed, of labour actually produced. combined the principle of dressing by the common manual operation, and part of that of the two dressing machines, already noticed. The web was warped on the common warping mill, and beamed in the usual way. The beam upon which the warp was rolled, was then placed in the machine, in a situation similar to the yarn beam of a common loom. At the other extremity of the machine, was the beam for receiving the yarn when dressed, placed nearly in the same situation as the cloth beam of a loom. The heddles, lay, and reed, were, of course, omitted, and the lease was preserved by three rods, exactly in the common way. When the web was stretched in the machine, in a direction nearly horizontal, the receiving beam being only raised a few inches above the other, to afford the operator more facility in picking and brushing, the operation commenced. The rods were

combed down, from the receiving to the discharging beam, the warp picked and brushed by manual labour, in the usual way, and the lease rod placed on its edge. Under the warp was a circular wooden fan, which was now set in motion by the power, while the operator continued to brush the warp while drying. The fan was inclosed in a circular wooden box, with an aperture only in the upper part of its circumference. During the operation of drying, this box was moved upon its centre by a common heart traverse; and as the air set in motion by the circular revolution of the fan, could only escape by the aperture, whose position might be varied at pleasure, every part could be sufficiently dried, without any part being too much hardened. When the yarn was sufficiently dried, the portion of warp which had been dressed, was wound, by another part of the machinery, from the discharging upon the receiving beam, and a fresh portion of warp presented to undergo the same operation, which was repeated in the same manner, until the whole warp was dressed and wound upon the receiving beam, which was then carried from the dressing machine to the loom. To this process, as here described, there certainly occur some serious objections; but from what I saw of the principles and effects of it, I am inclined to think, that something of a similar kind, if prosecuted with judgment, energy, and perseverance, might be essentially useful, in promoting the process of weaving both linen and cotton goods, upon principles of economy superior to any yet introduced, more especially if the chemical part can also be improved. I shall shortly state my reasons for adopting this opinion, premising, as usual, that it ought to be considered merely as hypothetical; no opportunity of practical proof being yet in existence. The first defect which appears in the process, is the conducting the operation of brushing, by manual labour, instead of using power. Every weaver knows that the situation of his body bending over a warp, while picking or dressing his web, is painful and fatiguing to an uncommon degree. It is only the intervals of ease, which he enjoys, while weaving up what he has dressed, when the body is in an erect and natural posture, and the small proportion of his time employed in dressing, which enables him to support this. But in this process, the body must be almost incessantly in this fatiguing and unnatural position; for no sooner has he finished the dressing of one portion of warp, than he must commence another.

Whatever allowance may be made for the effects of habit, in accustoming the human body to support exertions, which, when first tried, prove uncommonly fatiguing, I am inclined to doubt, whether any practice would enable a man to work incessantly at this operation for a sufficient number of hours daily, to render it productive. Besides this, so much is to be done by the hand, and so little by the power, that it does not appear, that, although a division of labour is created, almost any consequent reduction can be expected. By moving the brushes by power, the toil of the operator will be at an end, so soon as he has combed and picked his warp, excepting, that it will be necessary to set his brushes first in motion, and afterwards his fan; or, the first of these may engage the second at a proper time. In this interval, by placing two machines together, he may be employed in combing and picking another warp, and thus, without impeding the operation, the labour of one man may keep two, or, perhaps, three machines employed, with less fatigue and exhaustion, than would be necessary for one. The picking and combing of the warp, when yarn is well spun, which is now generally the case, especially in cotton, requires much less time and labour than the brushing; consequently, one warp might be combed and picked much faster than the other could be sufficiently dressed, dried, and wound upon the receiving beam.

To a plan of this kind, it may be objected, that the motion of the brushes is not uniform, nor the range equal in all stages of the process. Weavers find it necessary to brush that part of the warp nearest to the yarn beam first, and gradually to extend the range of the brushes, until they have brushed the whole undressed warp. The reason of this is as follows. Every kind of yarn has upon it a certain proportion of loose stuff, not sufficiently incorporated by the twine, to retain its situation, when acted upon by the brushes. Therefore, when the whole range of the stretched warp is brushed at once, these loose particles are drawn by the brushes to the lease rod, or varn beam. In a few dressings, these accumulate to such a degree, that they mat the yarn together, and form very serious obstructions to the operations of weaving. But when the warp is gradually dressed from the lease rod upwards, the glutinous nature of the dressing makes those nearest to the beam adhere to the yarn, before the uppermost are touched by the brushes. Of consequence, instead of being all collected in one point, they are scattered over the whole surface of the warp, and occasion little, if any, impediment. That it would be of advantage to imitate this motion in brushing, by machinery, seems very reasonable to suppose, for the same effects would be produced in both ways. But the great, and almost boundless variety of motion which may be communicated by machinery, in the hands of an ingenious mechanic, would prove quite sufficient to surmount any obstacle which might arise here.

This mode of dressing, if adopted and perfected, would obviate every objection against the others, except that which arises from the quality of the dressing, and even here the disadvantage would be considerably lessened. In the first place, the facility of picking the warp would be of great service, by removing impediments, both to the succeeding parts of the dressing process, and the subsequent operations of weaving. 2dly, All obstacles, arising from the friction of the reeds, would be removed; for none are necessary in this process. This would also prevent any necessity of suspending the operation in the wet state, which produces so much difficulty in the other modes. For any threads, which might be broken during the brushing, would be brushed down to the lease rod, where they would remain, without producing any injury, until the web was sufficiently dried, and they might then be knotted, before the dressed yarn was wound upon the receiving beam. 3dly, Every dressing might be equally dressed and dried, which is of most essential importance, and if speedily wound up when in a proper state, might remain so for a considerable time; for only the last yarn rolled on the beam, would be much exposed to the action of the air. Lastly, were it found by experience, that one person could keep three, or even two, of these machines in constant motion, I am persuaded, that the labour of that person would produce more work, and superior in quality, to that effected by any other scheme, which has been tried.

I have thrown these hints, which occurred to me upon comparing the various modes of dressing which have been tried, loosely together, for the consideration of those who are interested in the prosecution and improvement of this branch of the manufacture. As this is still in a state of infancy, I have done this with considerable diffidence; for as I have never been practically employed in constructing or employing machinery of this description, facts and considerations, important in practice, may have escaped my notice. In all mechanical inventions and improvements, experience has convinced me, that before proceeding to put them in practice, the theories and principles should be maturely weighed, and the obstacles likely to arise, with the means of removing them, carefully investigated. Even when all this has been done, unforeseen difficulties always occur, which can only be surmounted by decision, energy, and perseverance.

I now come to consider the various plans, which have been lately adopted for the purpose of working the weaving loom, by the application of power. Many experiments, upon a small scale, have been made for a considerable number of years past, and looms, upon various plans, constructed. The first attempt to establish a regular manufactory of this description, in Scotland, was, I believe, that of Mr. Robert Millar, at Milton Printfield, Dumbartonshire, which is still prosecuted. These looms, for which a patent was obtained, receive their motion from treddles, moved by those excentric wheels, which are known among mechanics by the name of wipers.

Another loom, the origin of which I believe to be English, but which has lately been introduced in Scotland to considerable extent, is the crank loom. The last, invented by Mr. Johnson, and brought into practice by Mr. Robert Shirreff, for which also a patent has been granted, is the vertical loom.

In these looms, different modes of construction have been adopted, without any material deviation from the same general principle. The plan of weaving by power has been so recently introduced, and hitherto confined to so few hands, that it is natural to suppose, that many improvements still remain to be made, and that much difference of opinion, respecting the relative merits of the different plans does, and will, for a considerable time, exist. I shall, for these reasons, confine my observations and descriptions to the principal moving parts of each, leaving the connections, and framing of the machines, to the judgment and discretion of those, who may apply them to practice.

With the exception of the motion for winding up the cloth, and unwinding the warp, which is rotatory on the axes of the beams, all the motions of a loom are alternate, or reciprocating. The two methods, most common among mechanics, of producing these motions, are cranks and wipers, or excentric wheels.

The reciprocating motion derived from the revolution of a crank on its own axis, is not uniform, but accelerated at one time, and retarded at another. By means of wipers, the motion may be made uniform, accelerated, or retarded, at any part of the revolution, according to the effect which the engineer wishes to produce. In many machines, this property gives the wiper a very decided advantage over the crank; but, in the weaving loom, the retardation of the crank, so far from being disadvantageous, is of considerable service.

In Plate 14. will be found representations of the chief working parts of the different power looms; and as the vertical loom is the one most recently invented, I have given a profile and transverse elevation of it, from drawings, for which I am indebted to Mr. Shirreff.

## WIPER LOOM.

Fig. 1. is a representation of the way of moving the heddles in this loom, so as to open the sheds. This figure is a profile elevated section of the heddles L, connected with the treddles S, much in the same way as in a common loom. In some power looms, the cords above the heddles pass over pullies, as in the figure; in others, Jacks are used, as in the common loom. The motion is given to this loom, by a horizontal cross shaft, upon which are a number of wipers. A section of this shaft, with the double wiper, which sinks the two treddles alternately, is represented at S.

These wipers may be constructed for any range of motion, in the following manner. Describe a circle of a convenient diameter on the piece of wood, or other substance, which is to form the wiper. Having considered the range which the wiper is to communicate to the treddle, draw a diameter line through the circle, and upon this line set off the length of the proposed range on the outside of the circle. At this point, describe a second circle concentric with the first, and divide the circumference into a great number of equal parts. From the centre draw a radius to each of these divisions, and the wiper will be ready for setting off. If a uniform reciprocating motion is wanted during the whole revolution of the wiper, it is only necessary to divide the space between the inner and outer circle into as many equal parts as half the number of radii. Set off one of these parts on the first radius line, two on the second, three on the third, and so on, until the whole are set off, when the semi-circumference of the wiper will be marked off; and the same operation reversed, will give the other or returning side. This forms exactly the common heart traverse. In the figure, a few radii are drawn upon S, to show the principle; but it will appear that each of these two wipers is constructed on half the circle, so that each may operate alternately on its respective treddle, when both sheds will be opened by one revolution of the shaft. As it is necessary that the shed should remain open while the shuttle is passing through, all the range must be set off some time before the wiper arrives at the centre, and the extremity left circular to suspend the motion for the time required. This is the case with the two wipers at S.

Fig. 2. is a profile elevation of the apparatus for moving the lay. E is the lay vibrating on its centres above, as in the common loom. The lay is pulled back by the operation of the wipers S upon the treddle R, by means of the connection represented in the figure. After the shuttle has passed through the shed, the lay is pulled forward by a weight attached to a cord or belt, passing over a pully, as represented. These wipers are also constructed on semi-circles, that the lay may operate twice in one revolution, as well as the heddles. Both wipers, however, operate upon the same treddle, as they are only intended to repeat the same motion, while those which move the heddles must reverse the shed. There is an apparatus of this kind at each side of the loom, to keep the lay steady. The wipers for this motion are upon the same shaft with those for the heddles. some power looms, the swords of the lay are reversed, and move in centres below. There are different ways

for driving the shuttle. In some, the driver cords are attached to the point of a lever with two cross tails, as represented by T, Fig. 3. This lever, being placed perpendicularly under the warp, with its flat side parallel to the horizontal shaft, and moving freely on its centre, the cross tails are alternately struck by two pieces of iron, fixed to the shaft, as represented at U, in Fig. 7. and, by moving the lever, drive the shuttle across the web. In other looms, two treddles are used, which are moved alternately, by wipers on the shaft, and produce the same effect. Various means are also used for winding up the cloth, of which some notice will be taken when we come to consider the vertical loom. In the mean time, we proceed to the

## CRANK LOOM.

In this loom no treddles are necessary, for the motion is communicated directly by the cranks. profile of the heddles, and section of the heddle crank shaft. The shape of the cranks will appear by Fig. 5. where a small portion of the shaft is represented in a transverse direction. Fig. 6. is a profile of the lay, and section of the lay crank shaft. Fig. 7. is a transverse view of the shaft, to show the way of disposing the cranks. It will be obvious, that in this loom two horizontal shafts are necessary, for only one stroke of the lay can be effected by a whole revolution of the lay shaft, whereas in the wiper loom the double wiper gives two. These shafts are placed parallel to each other, and on the same level, the heddle cranks being perpendicularly under the heddles, and the lay cranks behind. As it is necessary that the lay shaft should revolve twice, while the heddle shaft revolves once, the latter takes its motion from the former, by a spur wheel and pinion, as represented by Fig. 8. The wheel, containing double the number of teeth of the pinion, is fixed on the heddle shaft, the pinion on the lay shaft. The pully, which receives the motion from the power, is also on the lay shaft. The swords of the lay are lengthened below the boxes, to bring the connecting rods level with the shaft, and these connecting rods, in both motions, are usually of iron. The shuttle motion is effected by either of the two plans formerly described. We now come to the last invention, the

## VERTICAL LOOM.

Fig. 14. is a profile elevation of two of these looms, constructed at opposite sides of the same frame, and will convey a tolerably correct idea of their framing and appearance. Fig. 15. is a transverse elevation of one end. The remaining figures on the plate, 9 to 13 inclusive, are the several working parts. The whole reciprocating motions of the vertical loom, are also effected by cranks, and these cranks are upon two shafts.

A is a balance wheel on the lay crank shaft, one side of which is so much heavier than the other, as to counterpoise the weight of the lay and swords, and make them ascend and descend with equal ease. The swords rise and sink between sheers, or guides, to keep them steady.

B is the pully which takes the motion from the power, and which is also on the lay shaft.

C is the lay shaft, with a crank at either end, similar to those of the crank loom.

D is a wheel on the heddle shaft, receiving motion from a pinion of half the number of teeth on the lay shaft, as in the crank loom.

E is the lay and boxes, with the reed placed horizontally, and on which the shuttle runs.

F is the yarn beam, from which the warp ascends perpendicularly through the mounting.

G is the cloth beam above, for receiving the cloth when woven.

H the wheels by which the cloth is wound up.

I is the lever and fork, for engaging or disengaging the machine at pleasure.

K is a catch, by which the loom will be instantly stopped, if the shuttle should remain in the shed. All the power looms have contrivances of this kind, which will be more particularly noticed afterwards.

The nature and construction of each particular motion will appear more plainly, by inspecting the supplementary figures.

Fig. 9. contains a profile of the horizontal heddles, and the apparatus for moving them.

At L are the heddles, placed horizontally, and guided by belts, passing over pullics before and behind. To one of these belts is attached one end of the bended lever M, moving freely on its centre, and the other end of which is connected with the crank N. The shape of this shaft and crank will be plainly seen in Fig. 10. Besides the crank for the heddles, upon this shaft is a projecting stud P, operating like a crank for giving motion to the shuttle. Fig. 11. is a profile elevation of the apparatus by which the shuttle motion is communicated. O is a sliding bar which moves freely in two bushes backward and forward. Upon the edge of this

slider, is a rack which moves a pinion Q, fixed upon an upright shaft, on the upper part of which is a cross lever, to which are attached two leather thongs, which are also connected with the drivers. The stud P, the end of which appears here like a round dot, moving round in a hollow elliptical piece, forming part of the slider, alternately moves it rapidly backward and forward, by means of the catches above and below. This motion drives the cross lever upon the top of the upright shaft to the right and left alternately, by means of the pinion Q, and thus the motion is communicated to the drivers.

Fig. 12. is a ground plan of the rack and pinion.

Fig. 13. is an outline of the plan for winding up the cloth. On the axis of the cloth beam is fixed a wheel, on the outside of which is a ratchet wheel, loose upon the axis. This ratchet, one tooth of which is represented, is moved by a catch, jointed to the end of a spring connected with a lever; the other end of this lever is connected with the lay. This spring may be slackened, or stiffened at pleasure. Every time the lay rises, the spring and lever are pulled down, to move the ratchet one tooth; but the spring is made sufficiently slack, to yield without moving the ratchet, unless assisted by the stroke of the reed upon the fell of the cloth. Consequently, if the weft breaks, no winding-up motion is produced. This is very necessary; for, were the loom to go a shot or two without weft, and the cloth to be wound up, it must either be let back, or a large unwested interval would be produced. Upon the ratchet is fixed a pinion, which moves a wheel turning loosely upon a stud. Another pinion, fixed to this wheel, gives the motion to the fast wheel on the axis of the cloth beam, and consequently to the beams. The relative numbers of these wheels and pinions, must depend on the quantity of west in a given space, and they must be sitted on so as to be easily altered at pleasure.

In all the different experiments upon weaving by power, hitherto made, it has been found advantageous to confine the shuttle when lodged in either box, to prevent it from recoiling. This has been effected by a circular piece of wood, pressed through one of the edges of the box by a slight spring, which yields to the pressure of the shuttle when entering, and by its friction, prevents the recoil. It is also material to disengage the loom from the power instantly, if the shuttle should stop in the shed; for if driven up by the lay, much damage will be the probable consequence. This disengaging motion, is taken from these springs, which are connected by bended levers, and a wire across the lay, so that either will operate. In the vertical loom, the disengaging lever. I, is strongly pressed by a spring, to force out the driving pully, whenever the catch above is lifted. To the spring for securing the shuttle, an upright piece of iron K, moving on a joint is attached. When the spring is pressed back by the shuttle, the upper part of this is thrown forward, clear of a notch in an upright slide, attached to the disengaging catch; but if one spring is not pressed, K not being thrown forward, will strike the notch, and instantly disengage the machine. The contrivances for disengaging the other looms, are exactly upon the same principle, a little differently modified to suit the construction of the looms.

When the vertical loom is to work yarn which requires dressing, an iron roller is placed where the yarn beam is represented, and the beam itself in a small additional frame, parallel to, and on a level with the roller,

so that the part to be dressed is in a horizontal position, as in a common loom. Every power loom is generally furnished with a circular fan, such as formerly described, placed under the warp, and which is occasionally set in motion to dry the yarn after being dressed. Two pair of temples are generally used in power weaving.

It is not easy to decide, justly, upon the comparative merits of these looms, and upon this subject a considerable difference of opinion still prevails. The wipers are, without doubt, susceptible of a modification of the motion, to suit different fabrics, in a much greater degree than the cranks; but in the coarse fabrics, hitherto woven by power, the crank motions are found sufficiently correct. The mode of striking up the lay, by means of a weight, is found productive of one very considerable inconvenience. The force of the lay has a tendency to slacken, and, consequently, to spread the warp, and when the shed closes in this state, the threads are apt to obstruct each other, and occasion breaking. A very simple and ingenious apparatus, has lately been added to the vertical loom, to obviate this disadvantage, which also attends the crank loom, although not to an equal degree. This is merely a flat board, the edge of which is parallel to the warp, and which moves on centres. By means of two bended levers, connected by cords, or thongs, to the lay, this board presses the warp when the shed closes, and recedes from it when the shed is opened. Thus the warp is kept uniformly tight. The same contrivance might easily be applied to either of the other looms.

The vertical loom certainly appears to possess some decided advantages over the others.

1stly, It occupies a much smaller space of room, and, consequently, in a large manufactory, a considerable sav-

ing might be effected, both in the expense of building, and in that of shafts and other mill work.

2dly, From the shuttle running upon the reed, a larger pirn may be used, without any risk of injuring the warp by friction.

3dly, When it is necessary to dress the warp, which, in power weaving, is usually done without stopping the loom, it presents the following very important advantage. The operator, while dressing, remains exactly in the same situation as when attending the working, and can, therefore, see in a moment, any thing which may go wrong; whilst in the other looms, the person, while attending the working, must be in front, and when dressing, behind, where it is very difficult to see any obstruction which may happen before the reed.

In the 1st Essay, some remarks were made on the danger and inconvenience arising from working a loom beyond a proper rate of velocity. Practical experience has uniformly proved this to be highly injurious in the manual operation, and I am fully convinced, it must be equally, if not more prejudicial, in weaving by power. It has been common to drive power looms at the rate of 80 or 90 shots per minute, and attempts have even been made, to accelerate this velocity much beyond 100 shots. Mechanics know that even rotatory motion, when urged beyond a moderate speed, always fails in producing the effect expected. This has been sufficiently proved in spinning, where almost all the motions are rotatory. In weaving, where there are no less than three reciprocating motions, the effect must be still more injurious, especially in the lay and heddle motions. The shuttle, indeed, may be driven with considerable swiftness, for no injury can arise from this, unless the shuttle is thrown out of the box, or the west too much strained and frequently broken. Suppose, as in Essay 1st, a 10004 shawl cloth, with 1200 west, to be woven at the rate of 80 shots per minute. This will give a yard in 30 minutes, or 24 yards per day of 12 working hours, if no stop were to take place. I cannot state with certainty, what has been the greatest quantity of cloth of this description produced by power looms. The average quantity on the vertical loom, I have been informed, is about 15 yards, so that, if the loom works at the velocity quoted, more than one third of the time must be lost by stopping. Besides, I do not think that goods of this description have, in general, so much weft as I have taken in the calculation. Upon the whole, I should suppose 70 to 80 shots to be the maximum of velocity, at which it is prudent to drive a power loom, even with the coarsest and strongest materials; and if these looms are applied to weave finer and lighter fabrics, I suspect even this velocity must be considerably diminished.

The last plans of economy in weaving, which it will be necessary to discuss, are those which relate to the insertion of the weft. The process of winding the weft upon the pirn, whether from the hank or the cop, is tedious, and, consequently, expensive. Two means of reducing this expense, have been devised. The first of these is, by placing the cop itself in the shuttle upon a skewer, by which the whole expense of winding is saved. As the cops, however, are generally too large for an ordinary shuttle, it has been usual to compress them. This is effected by means of two hollow inverted cones, generally of brass, with a hole through the vertex of each to admit the skewer. The cop being placed upon the skewer, the two cones are pressed together by means of

a lever or screw. The cop, being between the cones, is thus compressed to a much smaller space than it originally occupied. The compression is most effectual when the cop has been boiled, but this can only be done when the west is to be inserted in a wet state.

Machines have also been lately constructed for winding a number of pirns at the same time. The principle is entirely the same with that of the machine for winding the warp bobbins. The only difference is in the shape of the traverse, which must be constructed to wind the yarn in the form of a cone, instead of being flat or barrel shaped. Those which I have seen are turned by the hand, which I cannot think is proper, for the same reason which I stated before; namely, that in all these machines, the person who attends ought to have both hands free, and should be at liberty to shift from one part of the machine to another, to remove obstructions, and knot broken threads. I do not think that these machines are, as yet, very generally employed, and, perhaps, they have not yet reached such a state of improvement, as to render the use of them an object of much importance, in point of economy.

## ESSAY VII.

ON THE

### MANUFACTURING OF CLOTH.

HAVING concluded our account of the operative processes and modes of economy, connected with the Art of Weaving, it only remains in this Essay to discuss the subjects which form more properly the province of the manufacturer, or foreman, than of the operative tradesman. The great extension of the business in modern times, and the competition naturally arising from this, have, of late, attracted the attention of most manufacturers, more to the mercantile than the operative part of the profession. Any investigation of this part of the business is evidently foreign to the plan of this work, and would render this part of it, rather an Essay upon commerce, than upon any branch of the Art of Weaving.

Much of the business of the person who superintends the manufacturing department, has been discussed in the preceding Essays; for a thorough knowledge of the operative part of the business is essentially necessary, to enable him to conduct that department with propriety. There only remain, therefore, two points to be investigated. The first, is the selection of proper yarn, to form the fabric required; the second, the calculations necessary to ascertain the prime cost of the goods, as a direction to the salesman.

A very essential part of the business of a skilful manufacturer is, to adapt the fineness of the warp which he uses to the reed, so as to produce the fabric of cloth required, whether light or heavy. This is called

#### CAAMING, OR SLEYING.

LITTLE has been done to reduce this to any regular system, and, hitherto, the rules generally laid down are nothing else than the results of observation and experience. For this reason, the tables for caaming almost every species of cloth, are almost as various as the manufacturers who use them; and scarce any two people agree upon this subject. That this is a great desideratum in the theory of weaving, will be readily admitted, and that it may be reduced to geometrical precision, there seems no room to doubt.

The only attempt which I have ever seen, to analize geometrically the construction of yarn, and, consequently, its application to the manufacture of cloth, is contained in a small tract, printed by Robert Urie, Glasgow, 1759, and entitled, "An Essay on the construction of Sleying Tables, by a Manufacturer."

An uncommon portion of ingenuity, and considerable mathematical knowledge is displayed in this work. It has now become so scarce, that I have only met with one printed copy, considerably mutilated; but, having been favoured with the perusal of the original manuscript, by a gentleman of Glasgow, related to the Author, I shall

endeavour to give a short account of his method, and of the principles upon which his calculations are founded.

In the first place, the author considers every thread as a cylinder, and, of course, justly infers, that supposing the density of every thread to be equal, the matter contained in it would be as the square of the diameter multiplied into the length. He also concludes, that as every thread, in proportion to its fineness, requires more twisting in the process of spinning, that, therefore, the fibres which compose the thread, will be more condensed in fine yarn than coarse, and that, consequently, the diameter of a fine thread will be less than that of a coarse one, in proportion to its weight.

He further assumes, that the base of one thread being to the base of another, as the squares of their diameters, and the circumgyrations by which the twine is produced, directly as their diameters; that the ratio of one thread to another will be, as the cube of each diameter, or, which is the same thing, as the square multiplied into the diameter.

The following extract from this curious little tract, will serve to convey the author's opinions in his own words

"A RIGHTLY CONSTRUCTED SLEYING-TABLE is a scheme which exhibits the proper reeds for disposing warp-yarns, of every given degree of fineness, in such a manner, that (due regard being had to the quality, and insertion of the weft) all the cloths, produced from those different warps, shall be exactly similar in fabric or compacture."

In order to compose such a scheme for any one species of cloths, the following data are previously requisite.

- 1. The number of the reed, employed in making the cloth, the fabric of which is intended for the model.
  - 2. The fineness of the warp-yarn of said cloth. And,
- The fineness of the warp, the reed for which is
   sought.
- By the number of the reed is understood the number of splits, or rather of the intervals of the splits contained in a given dimension; without having any regard to the number of those intervals that may in fact have been occupied by the warp: for the reed is precisely the scale by which the distance between the threads of the warp is regulated; and it equally affects the fabric of the cloth, whether the breadth of the cloth be a yard, or an inch.
- whether the breadth of the cloth be a yard, or an inch. The comparative fineness of any two parcels of yarn may be ascertained by the number of threads, of a determinate length, contained in a given weight of the one, compared with the number of threads of the same length, contained in the same weight of the other; due regard being always had to the degree of compression which the mass of each receives in the spinning. For, if two parcels of equal weight, but of different fineness, be spun from the same materials, and the degree of compression · be precisely the same; the threads in both, like all other cylinders of equal solidity, will reciprocate their bases and altitudes: in proportion as the base of the one thread is diminished, i. e. as it becomes finer than the other; the altitude will be increased, i. e. it will become longer than the other: and if the threads of both parcels be wound up in convolutions of equal circumference, there will be a greater number of those convolutions in the one parcel than in the other, in proportion as the one is finer than the other: and the two bases will be to each other inversely as the lengths of the threads.

Thus, if the number of convolutions in the coarser parcel
be a, and the number in the finer be b; the base of the
coarser will be to the base of the finer, b: a; or, \(\frac{1}{a}:\frac{1}{b}.\)

But the parcel that has the greater number of convolutions, in a given weight, will have its thread more compressed by the action of the spinning-wheel, than the parcel which has the less number in the same weight. How this comes about falls to be explained a little.

Every country-girl knows, that, in making yarns, for · like purposes, and from the same materials, her wheel must be oftener turned round in spinning a finer thread of a given length, suppose a yard of the parcel b, than in spinning a coarser thread of the same length, suppose • a yard of the parcel a. The reason is this: all yarns that are spun from the same materials, and destined to · like purposes in manufacture, how different soever they ' may be with respect to fineness, ought to be equally hard, or equally slack in the twine: that is to say, the fibres, which compose their surfaces, ought to be twisted to the same degree of tension. Now, as the two threads of the • parcels a and b are supposed to have been spun from the same materials; if they are likewise supposed to be designed for similar purposes, they ought so to be twisted, as that the superficial fibres of both may become equally tense; these of the one, with those of the other. But the periphery of the base of the finer thread being less than the periphery of the base of the coarser; the sue perficial fibres of the finer will be less stretched by a given number of circumgyrations than the superficial fibres of the coarser thread will be by the same number: and in order to give the same degree of tension to the superficial fibres of the finer thread with that of the su-· perficial fibres of the coarser; the number of circumgyrations must be increased, by how much the periphery
of the base of the finer is less than the periphery of the
base of the coarser.

· However, though the superficial fibres of the finer thread, in receiving the same degree of tension with those of the coarser, require a greater number of circumgyrations; that greater number will be effected by a less force than what is needful to produce the less number which the coarser thread requires. In other words, 4 the superficial fibres of the finer thread, taken together, will be stretched to any given degree, by a less force than what is needful to stretch the superficial fibres of the coarser thread, taken together, to the same degree. For the superficial fibres of the two threads are evidently as the surfaces of the two threads: and in order to give them the same degree of tension, the forces applied to them ought to be in the same ratio. Now, as the two ' threads are of the same length, and the base of the finer thread less than the base of the coarser, its periphery, and therefore its surface, will be less than that of the coarser; and the force, required to give its superficial fibres the same degree of tension with those of the coarser will likewise be less. Thus the two threads being of the same length, their surfaces, omitting the bases, will be as the peripheries of their bases; and the peripheries of their bases are as the diameters of their bases; and their bases are as the squares of their diameters: therefore, the surfaces of the two threads will be as the square roots of their bases. But their bases are to each other, upon the supposition of an equal compression, 4: 3; their surfaces will then be, and the forces employed against them ought to be,  $\sqrt{a}:\sqrt{b}$ : and as t is less than to the will be less than the v's ' as has been said.

But although the force applied to the surface of the · finer thread, in the spinning, be less than what is applied \* to the surface of the coarser; the finer will be more comspressed than the coarser. For while the compressing · forces diminish and increase in the ratio of the surfaces of the threads, i. c. in the ratio of the peripheries of their bases, and, consequently, in the ratio of their diameters; the masses of the threads diminish and increase in the ratio of their bases, i. e. in the duplicate ratio of their diameters: the force, then, which is applied to the surface of the finer thread, though less than what is applied to the surface of the coarser, will bear a greater oproportion to the mass upon which it acts, than the · force which acts upon the coarser bears to the mass of the coarser. The finer thread, therefore, being sube jected to a force proportionally greater than that which affects the coarser thread, will be more strongly compressed than the coarser, and become more dense, and less bulky, i. e. finer, by how much its mass is more diminished than the compressing force which is employed against it.

It appears, then, that two things are to be regarded in ascertaining the comparative fineness of a yard of the parcel a, and a yard of the parcel b; the mass of each, and the force applied to the surface of each, in the spinining. As the threads are of equal lengths, their masses will be as their bases; and the forces applied to them are as the peripheries of their bases, or as the diameters of their bases respectively: the two threads will, therefore, be to each other in a ratio compounded of the ratios of these two. Thus their bases being, forces equal or apart,  $\frac{1}{a}$ :  $\frac{1}{b}$ ; and the forces,  $\frac{1}{a}$ :  $\frac{1}{b}$ ; the coarser thread will be to the finer,  $\frac{1}{a}$   $\frac{1}{a}$   $\frac{1}{b}$ .

· These things being premised, the question to be discussed is simply this:—If yarn, the number of which in • a given weight is a, and, consequently, its finenes  $\frac{1}{a} \sqrt{\frac{1}{a}}$ , be properly sleyed, for any one sort of cloth, in a reed, the number of which upon a given dimension is c; in what reed, of the same dimension, ought yarn to be sleyed, for cloth of the same fabric, the number of which, in the same weight, is b, and its fineness # 1? Here, for the present, let it be admitted, that the 'yarn, the fineness of which is  $\frac{1}{4}\sqrt{\frac{1}{a}}$ , is sleyed by one thread only in each interval of the reed c; and that the ' yarn, the fineness of which is tw't, is to be sleyed in the same manner: and let it further be allowed that the intervals of the reed c are so exactly commensurate to • the threads  $\frac{1}{4}\sqrt{\frac{1}{4}}$ , that each thread is touched upon both sides by its neighbouring splits, without being pressed by them, and thereby deprived of its cylindrical form. These things granted, each interval of the reed c will be equal to the diameter of the circular base of the cylindrical thread contained in it. Now, as circles are to each other as the squares of their diameters; so, vice versa, the square of the diameter of one circle will be to the square of the diameter of another circle, as the one circle is to the other. But the circular bases of the • two threads are,  $\frac{1}{a}\sqrt{\frac{1}{a}}:\frac{1}{b}\sqrt{\frac{1}{b}}$ ; and an interval of c, or  $\frac{1}{b}$ , is equal to the diameter of a thread \( \frac{1}{a} \sqrt{\frac{1}{a}} \); therefore, the

square of t\* will be to the square of an interval of the

<sup>\*</sup> Here it is presumed, that the thickness of each of the splits, in the one reed, is to the thickness of each of those, in the other, inversely as the number of splits, in the one, to the number of those in the other.

<sup>&</sup>lt;sup>4</sup> The strictest regard is due to this proportion in making reeds for the <sup>4</sup> same sorts of cloth; as otherwise, the best scheme of sleying, that can <sup>5</sup> be devised, will, in many instances, be rendered impracticable.

reed sought,  $\frac{1}{a}\sqrt{\frac{1}{a}}:\frac{1}{b}\sqrt{\frac{1}{b}}$ . Or, to express it in the alternate way,

• Each interval, then, of the reed x will be equal to the • diameter of a thread  $\frac{1}{4}\sqrt{\frac{1}{6}}$  in the same manner that an • interval of c is equal to the diameter of a thread  $\frac{1}{4}\sqrt{\frac{1}{6}}$ . • And if it should be supposed, that an interval of c is • commensurate to two, three, four, or any given num• ber of threads  $\frac{1}{4}\sqrt{\frac{1}{6}}$ ; it will follow, that an interval of • x will be equally commensurate to the same number of • threads  $\frac{1}{4}\sqrt{\frac{1}{6}}$ .

And if an interval of c, equal to the diameters of a given number of threads  $\frac{1}{4}\sqrt{\frac{1}{4}}$ , have only a part of that number sleyed into it; and an interval of  $\kappa$ , equal to the diameters of the same number of threads  $\frac{1}{4}\sqrt{\frac{1}{4}}$ , have the like part of that number sleyed in it; the empty space in the interval c will be to that of the interval  $\kappa$ , as the one interval is to the other; and the occupied space in the other, in the same ratio: and the empty space in the interval  $\kappa$  will be to the thread, or threads, contained in that interval, as the empty space in the interval c is to what is contained in it.

In like manner, if there be sleyed into an interval of c a greater number of threads  $\frac{1}{a}\sqrt{\frac{1}{a}}$  than that interval is equal to the diameters of; and an equal number of threads  $t\sqrt{t}$  be sleyed into an interval of x; the threads in the interval c, will be to the threads in the interval x, as the one interval is to the other: and the excess in the one will be to the excess in the other in the same ratio: and the excess in the interval c, will be to the threads in the interval c, as the excess in the in-

• Hence, if yarn  $\frac{1}{a}\sqrt{\frac{1}{a}}$  be high-sleyed, or thick-set in the reed c; the yarn  $\frac{1}{b}\sqrt{\frac{1}{b}}$  will be so likewise in the reed x:
• if the former be low-sleyed, or thin-set; so will the latter: and, universally, whatever the fabric of the cloth made from the one is, such will the fabric of that made from the other be; so far as the fabric of cloth depends upon the sleying of its warp.

The method, however, which obtains here, in Scot-LAND, of coming at the comparative fineness of yarns, is onot by taking the number of convolutions in a given weight; but by-what amounts to the same thing-the weight of a given number of convolutions. For instance; a spyndle, which, in this country, is the highest denomination of yarn, contains 5760 convolutions of two yards and an half in circumference; or, to use the common • phrase, 5760 threads, ten quarters of a yard in length. Now, if a spyndle weighs a pound; to say that it does so, is, in effect, the same as saying that there are 5760 threads in a pound. Again, if another spyndle weighs a quarter of a pound; with respect to this second, to say that a spyndle is equal to a quarter of a pound; or that a pound contains four times the number of threads of this yarn that it does of the former, comes to the same thing. And, no doubt, it is much easier in assorting any considerable quantity of yarn, to weigh it by half, or even by quarter, spyndles; and then to class the different parcels according to their respective weights \*, than it would be, first to divide the quantity into pounds; and then-sit down, and count the number of threads in each pound; and after that-to range

<sup>• &#</sup>x27;This supposes that every spyndle has its full tale: and, indeed, 
• partly owing to wise regulations, and partly to national honesty, there
• is little ground of complaint here.

the several parcels according to the number of threads in the pound. But then, this easier method varies the state of the terms, as well as the terms themselves, in cascertaining the comparative fineness of yarns; and, consequently, varies the operation in finding the value of x. For, as in any two yarns, that are spun from the 4 same materials, the number of threads in a given weight, of the one, is to the number of threads in the same weight. of the other, inversely as the bases of the threads, abstract from their compression; so the weight of a given onumber, of the one, is to the weight of the same number of threads, of the other, directly as their bases. This is evident from the example just now given: there it is seen that a pound contains four times the number of the finer yarn that it does of the coarser; at the same time, a spyndle of the coarser is four times the weight of a spyndle of the finer. And, in every case, as threads of the same length and density have their masses in the ratio of their bases; so, e contra, their bases will be in the ratio of their masses. Now, as the two spyndles are spun from the same materials; their masses will be as their weights: and as they are of the same length, their bases will be in the ratio of their masses, i. e. in the ratio of their weights: and as the compressing force, applied, in the spinning, to the surfaces of threads, of the same length, is in the ratio of the square root of the mass; and the mass is as the weight; the two spyndles will be to each other directly as their weights into the square roots of their respective weights. Thus, if the weight of a spyndle of yarn be d, the number of which in a pound is a; and the weight of another spyndle be e, the number of which in a pound is b; the comparative fineness of the two is equally ascertained by saying, that the coarser is to the finer,  $d\sqrt{d}$ :  $e\sqrt{e}$ ; or,  $\frac{1}{d}\sqrt{\frac{1}{d}}$ ;  $e\sqrt{f}$ . In either case, the value of x will turn out to be the same—whether the question be stated *inversely*, as the numbers; or directly, as the weights.

At the time when this extract was written, all the yarn manufactured into cloth was spun by the distaff, or common spinning wheel. For this reason, the ingenious author had not the same opportunities, which now exist, of calculating with accuracy the ratio of twine which every size or grist of yarn required; nor the effect of that twine upon the thread, considered as a cylinder. The mule jenny, from the nature of its operation, is well calculated for this computation; for as a given length is spun at every draught of the mule, it becomes very easy to ascertain with great accuracy the average twine which every number requires in that length, and, consequently, in any other length.

If the principle, that the increase of twine necessary for fine yarn above coarse, by compressing the stuff more, diminishes the thickness or diameter of the thread be correct, the whole of the subsequent reasoning must be allowed to be strictly mathematical, and the deduction perfectly conclusive.

But there seems just reason to doubt the accuracy of this part of his hypothesis, because he appears to have entirely overlooked an effect of the operation of spinning upon the yarn, very important to be taken into the calculation. When any kind of material is prepared for spinning, the fibres are all placed parallel to each other, and the subsequent operation of twisting gives them the cohesion necessary to give the thread a proper degree of strength and solidity. The natural effect of this is, that the fibres, by the twining, deviate from a straight line into

that of a spiral or screw; and the same quantity of materials when twined, become considerably shorter than before. In spinning cotton yarn upon the mule, the carriage, after being drawn out to its full length, evidently recedes again towards the rollers, as the twine increases; and when the stuff is not equal, the coarse threads always begin to break, before the fine ones are sufficiently twined. In the twisting of ropes, where the diameter is great, this effect is still more perceptible. From this the natural inference seems to be, that the increase of twine diminishes the length, not the diameter of the thread. No allowance whatever is made for the shrinking in the length by our Author's hypothesis, but the whole is supposed to affect the diameter, which is evidently not the case.

But it may be supposed, that as the twine increases some diminution may take place, both in the length and in the diameter; and it becomes necessary to ascertain whether this is really the case, and if so, what ratio these bear to each other, before a correct rule for caaming or sleying can be found.

To ascertain these points, I made different inquiries, calculations, and experiments, the results of which I shall now lay before the reader, leaving him to decide, whether the conclusion which I have drawn from them is satisfactory or not.

It is perfectly impossible, by any known instrument, to measure the actual diameter of fine yarn with any degree of accuracy, but a rope of considerable diameter may easily be measured; and as it seemed probable that the same ratio might exist in coarse spinning, as in fine, my first inquiries were directed to this branch of spinning. The form which the strands of a rope assume,

when twisted, is exactly similar to that of a common screw. I, therefore, first endeavoured to compare the one with the other, and observe the effect. mechanics know the way in which the spiral is marked on a wooden or iron screw, before it is cut, by drawing a succession of right angled triangles upon a piece of paper, equal in length to the circumference of the cylinder upon which the screw is to be cut. This piece of paper is afterwards pasted round the cylinder, when the hypothenuses of the triangles form the spiral lines. Upon the same principle, the circumference of a rope may be considered as the base of a triangle; the distance between the parts of the same strand, after one whole revolution, as the perpendicular; and the spiral described by the strand in revolving, as the hypothenuse. Now as the rope shortens as the twine increases, the strands will be forced nearer to each other. Consequently, the perpendicular will decrease in length, and the angle at the base will become more acute.

The report of practical ropemakers is, that a shroud laid rope shortens one third in the twisting. Let us, therefore, suppose, that when the strands are laid, before twining, the circumference, or base line, is three inches, and the perpendicular the same. When the rope has been fully twined, the perpendicular will be only two inches, and if the diameter of the rope has continued the same, the base will still be three inches. Now, by a very simple operation in right angled trigonometry, the angle at the base, forming the obliquity of the spiral, will be 33° 42°, which, by inspecting the common run of ropes, will be found very nearly the case. From this we may infer, that the whole contraction and compression has been in the length, and that the diameter has undergone

no diminution. Next, as every thread, when twisting, appears to shorten in proportion to the twine which it receives, it seemed expedient to inquire what ratio the twine of different numbers of cotton yarn bear to each other, and how far this coincided, or differed from that of the effect which the Author of the extract just quoted supposes twining to produce, in diminishing the diameter.

Upon applying to several extensive spinners, I found their answers, in general, to be, that the twine required for different numbers was as the square roots of the numbers. One of these answers, given to me by Mr. Dunlop of Barrowfield Mill, I shall quote.

The number of twists upon an inch of yarn being given, say No. 70=24. To find the proper twist for No. 60, the proportion will be

**√**70:24:: **√**60:22.2

The number of twists for every inch of the following numbers of yarn, is

No. 50	20.2	80	25,6
60	22.2	90	27.2
70	24.	100	28.6

From the above, it will appear, that the ratio of twine is exactly the same as the Author assumed that of diminution to be, or directly as the diameter of the cylinder, which is, therefore, the square root of the number.

This seems a second proof, that the whole compressing power of the twine is exerted upon the length.

I next tried the following practical experiment: Having bored a very smooth hole, of an inch diameter, in a piece of hard wood, I passed through it a number of pieces of soft smooth twine about 30 feet long. When

the twine was stretched without being twisted, the board could be shifted with little difficulty along them. I then twisted them, and found the length to decrease sensibly as the twine increased, but upon the diameter I could perceive no difference. When pretty hard twined, indeed, from the oblique form which the strands had assumed, it was more difficult to shift the board than before; but this appeared to rise more from friction, than any increase of diameter; diminution there was certainly none.

From these different trials, it seems to result, that the shortening of any thread or rope, proceeds from the fibres or strands of which it is composed changing their direction from a longitudinal to an oblique or spiral position; and that no further compression is produced than what is necessary to bring them all into close contact. Were more compression produced than the fibres would yield to, the diameter must increase instead of diminishing, for, as at every twist, the length, or altitude, becomes less, the stuff, when no longer susceptible of compression, must swell in thickness. But so great a quantity of twine as would effect this, so far from being of any service to yarn, would be extremely injurious.

These considerations induce me to believe, that the fibres of every kind of material from which yarn is spun, undergo nearly an equal degree of compression, and that, therefore, the diameters may be estimated as those of other solid cylinders. The general rule which has been adopted seems, on this account, to be the best for practical use. This is, that the square roots of the numbers are as the measure of the reeds, to produce similar fabrics. For example, if No. 40 of cotton yarn is wrought in a 1200

reed, and it is necessary to work cloth of a similar fabric in one of 1600, the proportion will be

12: 440::16: 471.1

The fraction may be thrown away, and the number required will be 71. But as the extraction of roots by common arithmetic, is tedious, and not generally known, the same effect will be produced by squaring the reeds. The operation will then stand thus,

 $12 \times 12$  or  $12^2 = 144$  and  $16 \times 16$ , or  $16^2 = 256$ , therefore, 144 : 40 : : 256 : 71.1

The difference between this plan and that of the essay quoted, is, that this is as the squares, the other as the cubes of the diameters. No precise definition has ever been given of what really is similarity of fabric in cloth. Both of the preceding plans, are formed upon the idea that the diameter of the threads of warp should be in proportion to the measure of the reed; and this is, perhaps, the best way of fixing the standard. If we suppose that every thread touches the one next to it in a coarse fabric, and upon that supposition calculate what will produce the same effect in a fine web, we will naturally call it a similar fabric. To a certain degree, it will be so; but when we consider cloth as a solid, although the threads of the fine web should be placed as much in contact as those of the coarse, the thickness of the cloth will be diminished in the arithmetical ratio of the respective diameters. In this case, I do not mean by the word thickness, the crowding together of warp and west, which is the sense in which it is generally used by weavers; but the distance from the under to the upper superficies of the cloth. Upon the whole, by far too little attention has

been paid to reduce this part of the business of fabricating cloth to any regular system. It is certainly proper to have some fixed standard, and from this every manufacturer may deviate, according to the fashion of the times, or the taste of his customers.

We come now to the last part of this work, and upon this it will not be necessary to go much into detail. This is to consider the arithmetical part of the business of a manufacturer. It is the only part of the business which has been introduced into books, formerly written on the subject of weaving, and it is, therefore, less necessary to enlarge upon it. For practical purposes, a few tables may be useful, which I shall add in a miscellaneous way, with such remarks as may seem necessary.

#### COMPUTATION OF LINEN YARN,

THE circumference of the reel, for linen yarn, is fixed, by the Act of Parliament, at 90 inches, or 2½ yards, Once round this is called a thread, and the quantities of yarn are measured as follows:

```
21 yards
 1 thread =
                       300
                            do.
120 threads=1 cut
 2 cuts =1 heer
                   == 600
                            do.
                   = 1800 do.
 3 heers = 1 slip
 2 slips = 1 hank
                   = 3600
                             do.
 2 hanks =1 hesp
                   = 7200
                            do.
 2 hesps = 1 spyndle=14400
```

In general, however, the calculations are made by spyndles, heers, cuts, and threads, the intermediate divisions being omitted. The length of warps, as formerly stated, is rated by the number of English, or mill ells of forty-five inches, or five quarters each.

There are two ways of calculating the warp of webs necessary.

1st, Given the quantity of warp and breadth in porters, to find the length which will be produced in ells.

For this, the common practical rule is, multiply the spyndles by 288, and divide the product by the number of porters; the quotient is the answer.

One example will be sufficient.

Given 34 spyndles of yarn, to warp a web 72 porters broad.

Required the length in ells.  $288 \times 34 = 10192$  and  $10192 \div 72 = 141\frac{40}{73}$  ells. Thus the answer is 141 ells and 20 inches.

This rule is chiefly useful to customer weavers, who find it necessary to accommodate the length of their webs, to the quantity of warp which they receive.

2d, Given the length in ells, and breadth in porters, to find the warp required.

This rule is exactly the converse of the former; namely, multiply the ells by the porters, and divide by 288.

Given 100 ells 56 porters wide.

Required the quantity of warp.

100 × 56=5600 and 5600 ÷ 288=19 11 or

19 spyndles, 11 heers, and 1 cut.

This is chiefly used in extensive manufactories, where they have large quantities of warp, and make their webs uniform lengths for the sake of regularity.

The following Table is calculated upon these principles, and may be useful to save calculation in common practice. On the top, are the lengths in ells; and in the first column, the porters in the breadth. The remaining

columns, contain the quantity required for each of the respective lengths at the top. It is made as comprehensive as the limits of the work will admit. Other lengths may be found, by adding two or more of those given to make the number required. For instance, if 75 ells are required, take 50, and the half of 50; or take 50, 10 twice, and 5, and so of others. It may, in some cases, be shorter, to subtract one length from another. Suppose 95 ells; 5 subtracted from 100, will give the answer.

Both the calculations and the Table, it is to be remarked, are computed exactly to the length of the reel, and number of yards in the spyndle, without any allowance for waste, breakage, short measure, or count. But as this can never be expected, it is customary to allow one heer, to every spyndle, for these deficiences, and even this allowance is often found too little.

TABLE OF WARPS.

TABLE OF

ers.								ELI	.s.				······································			
Porters.		1	l			2				3				4		
	s.	н.	c.	T.	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.
18	0	1	1	0	0	3	0	0	0	4	1	0	0	6	0	0
19	0	1	1	20	0	3	0	40	0	4	1	60	0	6	0	80
20	0	1	1	40	0	3	0	80	0	5	0	0	0	6	1	40
21	0	1	1	60	0	3	1	0	0	5	0	60	0	7	0	0
22	0	1	1	80	0	3	1	40	0	5	1	0	0	. 7	0	80
23	0	1	1	100	0	3	1	80	0	5	1	60	0	7	1	40
24	0	2	0	0	0	4	0	0	0	6	0	0	0	8	0	0
25	0	2	0	20	0	4	0	40	0	6	0	60	0	8	O	80
26	0	2	0	40	0	4	0	80	0	6	1	0	0	8	1	40
27	0	2	0	60	0	4	1	0	0	6	1	60	0	9	0	0
28	0	2	0	80	0	4	1	40	0	7	0	0	0	9	0	80
29	0	2	0	100	0	4	1	80	0	7	0	60	0	9	1	40
30	0	2	1	0	0	5	0	0	0	7	·1	0	0	10	0	0
31	0	2	1	20	0	5	0	40	0	7	1	60	0	10	0	80
32	0	2	1	40	0	5	0	80	0	8	0	0	0	10	1	40
33	0	2	1	60	0	5	1	0	0	8	0	60	0	11	0	0
34	0	2	1	80	0	5	1	40	0	8	1	0	0	11	0	80
35	0	2	1	100	0	5	1	80	0	8	1	60	0	11	1	40
36	0	3	0	0	0	6	0	0	0	9	0	0	0	12	0	0
37	0	3	0	20	0	6	0	40	0	9	0	60	0	12	0	80
38	0	3	0	40	0	6	0	80	0	9	1	0	0	12	1	40
39	0	3	0	60	0	6	1	0	0	9	1	60	0	13	0	0
40	0	. 3	0	80	0	6	1	40	0	10	0	0	0	13	O	80
41	0	3	0	100	0	6	1	80	0	10	0	60	0	13	.1	40
	١								1				ı			

## MANUFACTURING. 307

WARPS.

ers.								ELI	Ls.							
Porters.			5			1	0			5	0			10	0	
	s.	н,	C	. т.	s.	н.	c.	т.	s.	н.	c.	т.	5.	н.	c.	т.
18	0	7	1	0	0	15	0	0	3	3	0	0	6	6	0	0
19	0	7	1	100	0	15	1	80	3	7	0	40	6	14	0	80
20	0	8	0	80	0	16	1	40	3	11	0	80	6	22	1	40
21	0	8	1	60	0	17	1	0	3	15	1	0	7	7	0	0
22	0	9	0	40	0	18	0	80	3	19	1	40	7	15	0	80
23	0	9	1	20	0	19	0	40	3	23	1	80	7	23	1	40
24	0	10	0	. 0	0	20	0	0	4	. 4	0	0	8	8	0	0
25	0	10	0	100	0	20	1	80	4	8	0	40	8	16	0	80
26	0	10	1	80	0	21	1	40	4	12	0	80	9	0	. 1	40
27	0	11	0	60	0	22	1	0	4	16	1	0	9	9	0	0
28	0	11	1	40	0	23	0	80	4	20	1	40	9	17	0	80
29	0	12	0	20	1	0	0	40	5	0	1	80	10	1	1	40
30	0	12	1	0	1	1	0	0	5	5	0	0	10	10	0	0
31	0	12	1	100	1	1	1	80	5	9	0	40	10	18	0	80
32	0	13	0	80	1	2	1	40	5	13	0	80	11	2	1	40
33	0	13	1	60	1	3	1	o	5	17	1	0	11	11	0	0
34	0	14	0	40	1	4	0	80	5	21	1	40	11	19	0	80
35	0	14	1	20	1	5	0	40	6	1	1	80	12	3	1	40
36	0	15	0	0	1	6	0	0	6	6	0	0	12	12	0	0
37	0	15	0	100	1	6	1	80	6	10	0	40	12	20	0	80
38	0	15	1	80	1	7	1	40	6	14	0	80	13	4	1	40
39	0	16	0	60	1	8	1	0	6	18	1	0	13	13	0	0
40	0	16	1	40	1	9	0	80	6	22	1	40	13	21	0	80
41	0	17	0	20	1	10	0	40	7	2	1	80	14	5	1	40

TABLE OF

ers.								ELI	Ls.							
Porters.		]	ì			2	;			3				4		_
	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.
42	0	3	1	0	0	. 7	0	0	0	10	1	0	0	14	0	0
43	0	3	1	20	0	: <b>7</b>	0	40	0	10	1	60	0	14	0	80
44	0	. 3	1	40	0	. 7	0	80	0	11	0	0	0	14	1	40
45	0	3	1	60	0	7	1	σ	0	11	0	60	0	15	0	0
46	0	.3	1	80	0	7	1	40	0	11	1	0	0	15	0	80
47	0	.3	1	100	0	. 7	1	80	0	11	1	60	0	15	1	40
48	0	4	0	0	0	8	0	0	0	12	0	0	0	16	0	0
49	0	4	0	20	0	8	0	40	0	12	0	60	0	16	0	80
50	0	4	0	40	0	8	0	80	0	12	1	0	0	16	1	40
51	0	4	0	60	0	· 8	1	0	0	12	ኀ	60	0	17	0	0
52	0	4	0	80	0	· 8	1	40	0	13	0	0	0	17	0	80
53	0	4	0	100	0	. 8	1	80	0	13	0	60	0	17	1	40
54	0	4	1	0	0	·. 9	0	0	0	13	1	0	0	18	0	0
55	0	4	1	20	0	9	0	40	0	13	1	60	0	18	0	80
56	0	4	1	40	0	9	0	80	0	14	0	0	0	18	1	40
57.	0	4	1	60	0	. 9	1	0	0	14	0	60	0	19	0	0
58	0	4	1	80	0	9	1	40	0	14	1	0	0	19	0	80
59	0	4	1	100	0	9	1	80	0	14	1	60	0	19	1	40
60	0	5	0	0	0	10	0	0	0	15	0	0	0	20	0	0
61	0	5	0	20	0	10	0	40	0	15	0	60	0	20	0	80
<b>62</b> ·	0	5	0	40	0	10	0	80	0	15	1	0	0	20	1	40
63	0	5	0	60	0	10	1	0	0	15	1	60	0	21	0	O
64	0	5	0	80	0	10	1	40	:0	16	0	0	0	21	0	80
65	0	5	0	100	0	10	1	80	0	16	ò	60	0	21	1	40
	1				1				l				i			

WARPS.

ers.								ELI	Ls.	•						
Porters.			5			10	0			5	0			10	0	
	s.	н.	C.	т.	s.	н.	c.	т.	s.	н.	c.	T.	S.,	н.	c.	т.
42	0	17	1	0	1	11	0	0	7	7	0	. 0	14	14	0	. 0
43	0	17	1	100	1	11	1	80	7	11	0	40	14	22	0	80
44	0,	1	>	80	1	12	1	40	7	15	0	80	15	6	1	40
45	0.	18	1	<b>6</b> 0	1	13	1	0	7	19	1	0	15	15	0	0
46	0	19	0	40	1	.14	0	80	7	23	1	40	15	23	0	80
47	0	19	1	20	.1	(15	0	40	8	. 3	1	80	16	7	1	40
48	0	20	0	0	1	.16	0	0	8	-8	0	0	16	16	0	0
49	0	20	0	100	1	16	1	80	8	12	0	40	17	0	0	80
<i>5</i> 0	o	20	1	80	1	17	1	40	8	16	0	80	17	8	1	40
-51	0	21	0	60	1	18	1	0	.8	20	1	0	17	17	0	0
52	0	21	1	40	1	19	0	80	9	0	1	40	18	1	0	80
<b>5</b> 3	0	22	0	20	1	20	0	40	9	4	1	80	18	9	1	40
54	0	22	1	0	1	21	0	0	9	9	0	0	18	18	0	0
55	0	22	1	100	1	21	1	80	9	13	0	40	19	2	0	80
56	0	23	0	80	1	22	1	40	9	17	0	80	19	10	1	40
57	0	23	1	60	1	23	1	0	9	21	1	0	19	19	0	C
<b>5</b> 8	1	0	0	40	2	. 0	0	80	10	1	1	40	20	. 3	0	80
<b>5</b> 9	1	0	1	20	2	1	0	40	10	. 5	1	80	20	11	1	40
60	1	1	0	0	2	2	0	0	10	10	ð	0	20	20	0	0
61	1	1	0	100	2	2	1	80	10	14	0	40	21	4	0	80
62	1	1	1	80	2	3	1	40	10	.18	0	80	21	12	1	40
63	1	2	0	60	2	: 4	1	0	10	22	1	0	21	21	0	. 0
64	1	2	1	40	2	<b>5</b>	0	80	11	. 2	. 1	40	22	5	0	80
65	1	3	0	20	2	6	0	40		6	1	80	22	13	1	40

TABLE OF

ers.								EL	Ls.							
Porters.			1			2	?			9	3			4		
	s.	н.	С	. т.	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.
66	0	5	1	0	0	11	0	0	0	16	1	0	0	22	0	0
67	0	5	1	20	0	11	0	40	0	16	1	60	0	22	0	80
68	0	5	1	40	0	11	0	80	0	17	0	0	0	22	1	40
69	0	5	1	60	0	11	1	0	0	17	0	60	0	23	0	0
70	0	5	1	80	0	11	1	40	0	17	1	0	0	23	0	80
71.	0	5	1	100	0	11	1	80	0	17	1	60	0	23	1	40
72	0	6	0	0	0	12	0	0	0	18	0	0	1	0	0	0
73	0	6	0	20	0	12	0	40	0	18	0	60	1	0	0	80
74	0	6	0	40	0	12	0	80	0	18	1	0	1	0	1	40
75	0	6	0	60	0	12	1.	0	0	18	1	60	1	1	0	0
76	0	6	0	80	0	12	1	40	0	19	0	0	1	1	0	80
77	0	6	0	100	0	12	1	80	0	19	Ö	60	1	1	1	40
78	0	6	1	. 0	0	13	О'	0	0	19	1	0	1	2	0	0
79	0	6	1	20	0	13	0	40	0	19	1	60	1	2	0	80
80	0	6	1	40	0	13	0	80	0	20	0	0	1	2	1	40
81	0	6	1	60	0	13	1	o	0	20	0	60	1	3	0	.0
82	0	6	1	80	0	13	1	40	0	20	1	0	1	3	0	80
83	0	6	1	100	0	13	1	80	0	20	1	60	1	3	1	40
84	0	7	0	0	0	14	0	0	0	21	0	0	1	4	0	0
85	0	7	0	20	0	14	0	40	0	21	0	60	1	4	0	80
86	0	7	0	40	0	14	0	80	0	21	1	0	1	4	1	40
87	0	7	0	60	0	14	1	· 0	0	21	1	60	1	5	0	0
88	0	7	0	80	0	14	1	40	0	22	0	0	1	5	0	80
89	0	7	0	100	0	14	1	80	0	22	0	60	1	5	1	40

WARPS.

ers.								EL	LS.							
Porters.	_	,	<b>5</b> .	•		10	0			5	0			10	0	
<del>*************************************</del>	s.	н,	C	т.	s.	Ή.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.
66	1	3	1	0	2	7	0	0	11	11	0	0	22	22	0	0
67	1	3	1	100	2	7	1	80	11	15	0	40	23	6	0	80
68	1	4	0	80	2	8	1	40	11	19	0	80	23	14	1	40
69	1	4	1	60	2	9	1	0	11	23	1	O	23	23	0	0
70	1	5	0	40	2	10	0	80	12	3	1	40	24	7	0	80
71	1	5	1	20	2	11	0	40	12	7	1	80	24	15	1	40
72	1	6	0	0	2	12	0	0	12	. 12	0	0	25	0	0	0
73	1	6	0	100	2	12	1	80	12	16	0	40	25	8	0	80
74	1	6	1	80	2	13	1	40	12	20	0	80	25	16	1	40
75	1	7	0	60	2	14	1	0	13	0	1	O	26	1	0	0
76	1	7	1	40	2	15	0	80	13	4	1	40	26	9	0	80
77	1	8	0	20	2	16	0	40	13	8	1	80	26	17	1	40
78	1	8	1	0	2	17	0	0	13	13	0	o	27	2	0	0
79	1	8	1	100	2	17	1	80	13	17	0	40	27	10	0	80
80	1	9	0	80	2	18	1	40	13	21	0	80	27	18	1	40
81	1	9	1	60	2	19	1	0	14	1	1	0	28	3	0	0
82.	1	10	0	40	2	20	0	80	14	5	1	40	28	11	0	80
83	1	10	1	20	2	21	0	40	14	9	1	80	28	19	1	40
84	1	11	0	0	2	22	0	0	14	14	0	0	29	4	0	0
85	1	11	0	100	2	22	1	80	14	18	0	40	29	12	0	80
86	1	11	1	80	2	23	1	40	14	22	0	80	29	20	1	40
87	1	12	0	60	3	0	1	0	15	2	1	0	30	5	0	0
88	1	12	1	40	3	1	0	80	15	6	1	40	30	13	0	80
89	1	13	0	20	3	2	0	40	15	10	1	80	30	21	1	40
i				J				١								

TABLE OF

ers.					<del></del>			ELI	.s.							
Porters.		1	i <sup>i</sup>	:		2				3				4	:	_
	s.	н.	c.	T.	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.
90	0	7	1	0	0	15	0	0	0	22	1	0	1	6	0	0
91	0	7	1	20	0	15	0	40	. 0	22	1	60	1	6	0	80
92	0	7	1	40	0	15	0	80	0	23	0	0	1	6	1	40
93	0	7	1	60	0	15	1	0	0	23	0	60	1	7	0	0
94	0	7	1 '	80	0	15	1	40	0	23	1	0	1	7	0	80
95	0	7	1	100	0	15	1	80	0	23	1	60	1	7	1	40
96	0	8	0	0	0	16	0	0	1	0	0	0	1	8	0	0
97	0	8	0	20	0	16	0	40	1	0	0	60	1	8	0	80
98	0	8	0	40	0	16	0	80	1	0	1	0	1	8	1	40
99	0	8	0	60	0	16	1	0	1	0	1	60	1	9	0	0
100	0	8	0	80	0	16	1	40	1	1	0	0	1	9	0	80
101	o:	8	0	100	0	16	1	80	1	1	0	60	1	9	1	40
102	0	8	1	0	0	17	0	0	1	1	1	0	1	10	0	0
103	0	8	1	20	0	17	0	40	1	1	1	60	1	10	0	80
104	0	8	ł	<b>4</b> 0	0	17	0	80	1	2	0	0	1	10	1	40
105	0	8	1	60	0	17	1	0	1	2	0	60	1	11	0	0
106	0	8	1	. 80	0	17	1	40	1	2	1	0	1	11	0	80
107	o	8	1	100	0	17	1	80	1	2	1	60	1	11	1	40
108	0	9	0	0	0	18	0	0	1	.3	0	0	1	12	0	· O
109	0	9	0	· <b>2</b> 0	0	18	0	40	1	3	0	60	1	12	0	80
110	0	9	0	40	0	18	0	80	1	3	1	0	1	. 12	1	40
111	0	9	0	60	0	18	1	0	1	3	1	60	1	13	0	0
112	0	9	0	. 80	0	18	1	40	1	4	0	C	1	. 13	0	80
113	0	9	0	100	0	18	1	80	1	4	0	60	1	13	. 1	40
	1	_			l				١				1			

# manufacturing. 318

WARPS.

								ELI	.s.							
Porters.		Ę	5			10	)			50	)			10	0	
	s.	н.	c.	т.	s.	н.	c.	т.	s.	Hi	c.	т.	s.	н.	c.	т.
90	1	13	1	0	3	3	0	0	15	15	0	0	31	6	0	0
91	1	13	1	100	3	3	1	80	15	19	0	40	31	14	0	80
92	1	14	0	80	3	4	1	40	15	23	0	80	31	22	1	40
93	1	14	1	60	3	5	İ	0	16	3	1	0	32	7	0	0
94	1	15	0	40	3	6	0	80	16	7	1	40	32	15	0	80
95	1	15	1	20	3	7	0	40	16	11	1	80	32	23	1	40
96	1	16	0	0	3	8	0	0	16	16	0	0	33	8	0	0
97	1	16	0	100	3	8	1	80	16	20	0	40	33	16	0	80
98	1	16	1	80	3	9	1	40	17	0	0	80	34	0	1	40
99	1	17	0	60	3	10	1	0	17	4	ı	. 0	34	9	0	0
100	1	17	1	40	3	11	0	80	17	8	1	40	34	17	0	80
101	1	18	0	20	3	12	0	40	17	12	1	80	35	1	1	40
102	1	18	1	0	3	13	0	0	17	17	0	0	35	10	0	0
103	1	18	1	100	3	13	1	80	17	21	0	40	35	18	0	80
104	1	19	0	80	3	14	1	40	18	1	·O	80	36	2	1	40
105	1	19	1	60	3	15	1	0	18	5	1	0	36	11	0	0
106	1	20	0	40	3	16	0	80	18	9	1	40	36	19	0	80
,107	1	20	1	20	3	17	0	40	18	13	1	80	37	3	I	40
108	1	21	0	0	3	18	0	0	18	18	0	0	37	12	0	0
109	1	21	0	100	3	18	1	80	18	22	0	40	37	20	0	80
/110	1	21	1	<b>\$</b> 0	3	19	1	40	19	2	·O	80	38	4	1	40
111	1	22	0	60	3	20	1	0	19	6	1	0	38	13	0	0
112	1	22	1	40	3	21	0	:80	19	10	1	40	38	21	0	80
113	1	23	0	20	3	22	0	40	19	14	1	80	39	-5	1	40

TABLE OF

rs.								ELI	.s.							
Porters.		1	l			2				3				4		
	s.	н.	c.	т.	9.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.
114	0	.9	1	0	0	19	0	0	1	4	1	0	1	14	0	0
115	0	.9	1.	20	0	19	0	40	1	4	1	60	1	14	0	80
116	0	9	1.	40	0	19	0	80	1	5	0	0	1	14	1	40
117	0	9	1	60	0	19	1	0	1	5	0	60	1	15	0	0
118	0	9	1	80	0	19	1	40	1	5	1	0	1	15	0	80
119	0	.9	1	100	0	19	1	80	. 1	5	1	60	1	15	1	40
120	0	10	0	. 0	0	20	0	. 0	1	6	0	0	1	16	0	0
121	0	10	0	20	0	20	0	40	1	· 6	0	60	1	16	0	80
122	0	10	0	40	0	20	0	80	1	· 6	1	. 0	1	16	1	40
123	0	10	0	60	0	20	1	0	1	. 6	1	60	1	17	0	0
124	0	10	0	80	0	20	1	40	1	7	0	0	1	17	0	80
125	0	10	0	100	0	20	1	80	1	7	0	60	1	17	1	40
126	0	10	1	0	0	21	0	. 0	1	. 7	1	0	1	18	0	0
127	0	10	1	20	0	21	0	40	.1	. <b>7</b>	1	60	1	18	0	80
128	0	10	1	40	0	21	0	80	.1	. 8	0	r .0	1	18	1	40
129	0	10	1	60	0	21	1	. 0	1	. 8	0	60	1.	19	0	0
130	0	10	1	80	0	21	1	40	1	. 8	1	0	1	19	0	80
131	0	10	1	100	0	21	1	80	1	8	1	60	1	19	1	40
132	0	11	0	0	0	22	0	. 0	1	9	0	0	1	20	0	0
133	0	11	0	20	0	22	0	40	.1	. 9	Ø	60	1	20	0	80
134	0	11	0	40	0	22	0	80	.1	. 9	1	0	1	20	1	40
135	0	11	0	60	0	22	1	0	1	. 9	1	60	1	21	0	0
136	0	11	0	80	0	22	1	40	1	10	0	C	1	21	.0	80
137	0	11	0	100	0	22	1	80	1	10	0	60	1	21	1	40
	1				ì				ì				I			

WARPS.

ers.								ELI	.s.							
Porters.			5			10	)			50	0			10	0	
	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.
114	1	23	1	0	3	23	0	0	19	19	0	0	39	14	0	0
115	1	23	1	100	3	23	1	80	19	23	0	40	39	22	0	80
116	2	0	О,	80	4	0	1	40	20	3	1	80	40	6	1	40
117	2	0	1	60	4	1	1	0	20	7	1	0	40	15	0	0
118	2	1	0	40	4	2	0	80	20	11	1	40	40	23	0	80
119	2	1	1	20	4	3	0	40	20	15	l,	80	41	7	1	40
120	2	2	0	0	4	4	0	0	20	20	0	0	41	16	0	0
121	2	2	0	100	4	4	1	80	21	0	0	40	42	0	0	80
122	2	2	1	80	4	5	1	40	21	4	0	80	42	8	1	40
123	2	3	0	60	4	6	1	0	21	8	1	0	42	17	0	0
124	2	3	1	40	4	7	0	80	21	12	1	40	43	1	0	80
125	2	4	0	20	4	8	0	40	21	16	1	80	43	9	1	40
126	2	4	1	0	4	9	0	0	21	21	0	0	43	18	0	0
127	2	4	1	100	4	9	1	80	22	1	0	40	44	2	0	80
128	2	5	0	80	4	10	1	40	22	5	0	80	44	10	1	40
129	2	5	1	60	4	11	1	0	22	9	1	0	44	19	0	0
130	2	6	0	40	4	12	0	80	22	13	1	40	45	3	0	80
131	2	6	1	20	4	13	0	40	22	17	1	80	45	11	1	40
132	2	7	0	0	4	14	0	. 0	22	22	0	0	45	20	0	0
133	2	7	0	100	4	14	1	80	23	2	0	40	46	4	0	80
134	2	7	1	80	4	15	1	40	23	6	0	80	46	12	1.	40
135	2	8	0	60	4	16	1	0	23	10	1	0	46	21	0	0
136	2	8	1	40	4	17	0	80	23	14	1	40	47	5	0	80
137	2	9	0	20	4	18	0	40	23	18	1	80	47	13	1	40

TABLE OF

ers.	ELLS,															
Porters.	1				2			3				4				
	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.
138	0	11	1	0	0	23	0	0	1	10	1	Ò	1	22	0	0
139	0	11	1	20	0	23	0	40	1	10	1	60	1	22	0	80
140	0	11	1	40	0	23	0	80	1	11	0	. 0	1	22	1	40
141	0	11	1	60	0	23	1	0	1	11	0	60	1	23	0	Q
142	0	11	1	80	0	23	1	40	1	11	1	0	1	23	0	80
143	0	11	1	100	0	23	. 1	80	1	11	1	60	1	23	1	40
144	0	12	0	0	1	. 0	0	0	1	12	0	0	2	0	0	0
145	0	12	0	20	1	0	0	40	1	12	0	60	2	0-	0	80
146	0	12	0	40	1	0	0	80	1	12	1	0	2	0	1	40
147	0	12	0	60	1	0	1	0	, 1	12	1	60	2	1	0	0
148	0	12	0	80	1	0	1	40	1	13	0	. 0	2	1	0	80
149	0	12	0	100	1	0	1	80	1	13	0	60	2	1	1	40
150	0	12	1	. 0	1	1	0	0	1	13	1	o	2	2	0	0
151	0	12	1	20	1	1	0	40	1	13	1	60	2	2	0	80
152	0	12	ļ	40	1	1	0	80	1	14	0	O	2	2	1	40
153	0	12	1	60	1	1	1	0	1	14	0	60	2	3	0	Q
154	0	12	1	80	1	1	1	40	1	14	1	0	2	3	0	80
155	0	12	1	100	1	1	1	80	1	14	1	60	2	3	1	40
356	0	13	0	0	1	2	0	0	1	15	0	0	2	4	0	0
157	0	13	0	20	1	2	0	40	1	15	0	60	2	4	0	80
158	0	13	0	40	1	2	0	80	1	15	1	0	2	4	i	40
159	0	13	0	60	1	2	1	٥	1	15	1	60	2	5	0	0
160	0	13	0	80	1	2	1	40	1	16	0	0	2	5	0	80
161	0	13	0	100	1	2	1	80	1	16	0	60	2	5	1	40
		. •			l				l							

WARPS.

ers								ELI	LS.							
Porters.		į	5		10				50				100			
	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.	s.	н.	c.	т.
138	2	9	1	0	4	19	0	0	23	23	0	0	47	22	0	0
139	2	9	1	100	4	19	1	80	24	3	0	40	48	6	0	80
140	2	10	0	80	4	20	1	40	24	7	0	80	48	14	1	40
141	2	10	1	60	4	21	1	0	24	11	1	0	48	23	0	0
142	2	11	0	40	4	22	0	80	24	15	1	40	49	7	0	80
143	2	11	1	20	4	23	0	40	24	19	1	80	49	15	1	40
144	2	12	0	0	5	0	0	0	25	0	0	0	50	0	0	0
145	2	12	0	100	5	0	1	80	25	4	0.	40	50	8	0	80
146	2	12	1	80	5	1	1	40	25	8	0	80	50	16	1	40
147	2	13	0	60	5	2	1	0	25	12	1	0	51	1	0	0
148	2	13	1	40	5	3	0	80	25	16	1	40	51	9	0	80
149	2	14	0	20	5	4	0	40	25	20	1	80	51	17	1	40
150	2	14	1	0	5	5	0	0	26	1	0	0	52	2	0	0
151	2	14	1	100	5	5	1	80	26	<b>5</b>	0	40	52	10	0	80
152	2	15	0	80	5	6	1	40	26	9	0	80	52	18	1	40
153	2	15	1	60	5	7	1	0	26	13	1	0	53	3	0	0
154	2	16	0	40	5	8	0	80	26	17	1	40	53	11	0	80
155	2	16	1	20	5	9	0	40	26	21	1	80	53	19	1	40
156	2	17	0	Ö	5	10	0	0	27	2	0	0	54	4	0	0
157	2	17	0	100	5	10	1	80	27	6	0	40	54	12	0	80
158	2	17	1	80	5	11	1	<b>4</b> 0	27	10	0	80	54	20	1	40
159	2	18	0	60	5	12	1	0	27	14	1	0	55	5	0	0
160	2	18	1	40	5	13	0	80	27	18	1	40	55	13	0	80
161	2	19	0	20	5	14	0	40	27	22	1	80	55	21	1	40

THE principle upon which these calculations are founded is very simple, and may be very easily explained. As the length of a thread is 90 inches, or double the length of an ell, and there are two threads in every split, it is plain that one thread will make exactly one splitful of warp of one ell long. Of course, 240 threads, or one heer, will make 240 splitfuls, or 12 porters of the same length. Or, which is the same thing, a heer will make one porter 12 ells long. If, therefore, the number of ells be multiplied by the number of porters, and the product divided by 12, the number of heers will be found, and these again, divided by 24, will give the spyndles. But, 24 multiplied by 12 is 288; therefore, that is the number quoted for the divisor in the last case. The remainder, divided by 12, gives heers.

When the length admits, it is common to shorten the operation by multiplying dozens of ells by the porters. The divisor is then 24 for spyndles. For example, 100 ells is 84 dozens. Therefore,

 $8\frac{1}{3} \times 60$  porters = 500, and  $500 \div 24 = 20-20$ , or  $100 \times 60$  do. = 6000, and  $6000 \div 288 = 20-20$ , which give exactly the same result.

A very common length, in the muslin manufacture, is 100 ells. Another practical rule is, therefore, very generally used for this length. By the former rules it will be found, that 3 porters of 100 ells long, contain 1 spyndle 1 heer of warp. Therefore, divide the porters by 3, and add one heer for each spyndle in the quotient, and in proportion for any fraction of a spyndle. For example, 60 porters ÷ 3 = 20 spyndles, to which adding 20 heers, the result is as before.

Many other practical rules may be used, to answer particular lengths, upon the same principle.

When a warp contains what are called odd splits, they must be calculated as fractions of porters. The length may then be multiplied by the whole number of splits, and the quotient divided by 20, before the succeeding operations.

The size, or fineness, of linen yarn is ascertained by the weight of one spyndle, excepting the French, which is counted by the *pinee*, containing 28 heers.

#### COMPUTATION OF COTTON YARN.

The measure of the cotton reel has never been fixed by any act of Parliament, like the linen. The universal practice of the spinners, however, both in England and Scotland, is to use reels of 54 inches, or 1½ yards, in circumference. The account is as follows:

```
1 thread = 1½ yards
80 threads = 1 skein = 120 do.
7 skeins = 1 hank = 840 do.
18 hanks = 1 spyndle = 15,120 do.
```

It will be found, that the length of one spyndle of cotton, is to one spyndle of linen, exactly in the proportion of 21 to 20. An allowance of 5 per cent. has, therefore, been made in calculating the cotton reel, probably for waste during the successive operations which it undergoes.

From the prevalent desire of following old customs, the spyndle of cotton yarn is still almost universally counted by heers, cuts, and threads, as the linen; although both the length and divisions of the reel are totally different. By this mode, no account is made of the surplus 5 per cent. which is, therefore, supposed to be wasted. The following way is also adopted by some, which is founded on a similar principle to that of the linen: 18 hanks, or numbers, of cotton yarn being supposed equal to 24 heers of linen, the proportion is as 3 to 4. The divisor, therefore, in the same ratio, is taken to be 16 instead of 12. The rule, therefore, is, Multiply the length by the porters and divide by 16; the quotient will be hanks, or numbers, and these again divided by 18, will give spyndles. The former example, repeated in this way, will stand as follows:

$$100 \times 60 = 6000$$
,  $6000 \div 16 = 375$ , and  $375 \div 18 = 20-15$ 

The result is still the same, for, in the assumed ratio of 3 to 4, 15 hanks are exactly equal to 20 heers, each being 5 of a spyndle. Here then, also, the surplus 5 per cent. is left totally out of the account.

But were cotton yarn counted to its full extent, like linen, the account would stand thus:

21:20::20-15:19-16.095238 or 
$$\frac{2}{37}$$

As, however, there seems every reason to believe, that this allowance upon the cotton was merely intended to counterbalance waste, it appears most adviseable, whether the account is made by numbers or heers, to leave it entirely out. Besides, the linen reel is evidently adapted to the length of the ell to avoid fractions: the cotton, if counted to its full extent, is by no means so.

The size, or fineness, of cotton yarn is determined by the number of hanks in one pound, avoirdupoise weight.

## COMPUTATION OF WOOLLEN YARN.

In Scotland, the coarse woollen yarn spun by the hand has usually been reeled upon the same reel, and counted in the same way as the linen. The woollen yarn, spun by machinery, is usually reeled upon a reel 72 inches, or 2 yards in circumference, and the spyndle divided into 12 equal parts of 600 yards, or 2 heers, each. The calculations for linen will, therefore, serve equally well for woollen. The woollen, like the linen, is sized by the weight of the spyndle.

## COMPUTATION OF SILK.

THE silk, which is imported chiefly from Bengal and China, is never made up in any precise or determinate length, to assist computation or ascertain the fineness. In the preparatory processes, therefore, the only check is weighing the stuff when delivered and received.

After being warped, the warp may be weighed, and as the quantity of warp can then be ascertained, an estimate of its fineness may be formed, as in other yarn. When received, it is generally assorted merely by the eye, in three or four parcels of different fineness.

## COMPARISON OF REEDS.

IT has been noticed in the 1st Essay, that the scale of reeds in Scotland, has been ascertained by the number of splits in 34 inches for cambric, 37 inches for linen, cotton, woollen, and silk, and 40 inches, for holland. The 34 and 40 inch reeds are now completely exploded, and 37

inches, being the measure of the Scotch ell, is the universal standard. In Bolton and Manchester, the reeds are counted by the number of beers in 24½ inches. These beers sometimes contain 19, and sometimes 20 splits, or as they are called there, dents. The latter is the most prevalent. What is called a beer in England, therefore, in general, corresponds with what the Scotch weavers term a porter. At Stockport, the reeds are counted by the number of ends, or threads, in an inch. The dents, or splits, in two inches are, therefore, the number of the reed.

The two following Tables, will exhibit a comparative view of the Scotch 37 inch reed, with each of these. The first column contains the number by which the English reed is known. The second, the dents in one inch in integers and decimals. The third, the number of dents in an English yard of 36 inches. And the fourth, fifth, and sixth, the number of a Scotch reed of equal fineness, in hundreds, porters, and splits.

# COMPARATIVE TABLES OF REEDS.

# MANCHESTER AND BOLTON

# TABLE.

Reed.		Dents Yard.		P.	s.	Reed.		Dents Yard.	н.	P.	s.
20	16.49	593	6	0	9	. 54	44.53	1603	16	2	8
22	18.14	653	6	3	11	56	46.18	1662	17	0	8
24	19.79	712	7	1	12	58	47.83	1722	17	3	10
26	21.44	771	7	4	12	60	49.48	1781	18	1	11
28	23.09	831	8	2	14	62	51.13	1840	18	4	11
30	24.74	890	9	0	15	64	5 <b>2.</b> 78	1900	19	2	13
32	26.39	950	9	3	16	66	<b>54.4</b> 3	1959	20	0	13
34	28.04	1009	10	1	17	68	<b>56.0</b> 8	2018	20	3	14
36	29.69	1068	10	4	18	70	<b>57.</b> 73	2078	21	1	16
38	31.34	1128	11	2	19	72	59.38	2137	21	4	16
40	32.98	1187	12	1	0	74	61.03	2197	22	2	18
42	34.63	1247	12	4	2	76	62.68	2256	23	0	19
44	36.28	1306	13	2	2	78	64.32	2315	23	3	19
46	37.96	1366	14	0	4	' 80	65.97	2375	24	2	1
48	39.58	1425	14	3	5	90	74.22	2672	27	2	16
50	41.23	1484	15	1	5	100	82.47	2969	30	2	1
52	42.88	1543	15	4	6						
	1	1	1	1	ı	Į.	,	,	, ,	•	1

# STOCKPORT

TABLE.

No.	Dents Inch.	Dents Yard.	н.	P.	s.	No.	Dents Inch.	Dents Yard.	н.	Р.	s.
34	17	612	6	1	9	90	45	1620	16	3	5
38	19	684	7	0	3	94	47	1692	17	1	19
40	20	720	7	2	0	96	48	1728	17	3	16
44	22	792	8	0	14	100	50	1800	18	2	70
46	23	828	8	2	17	104	52	1872	19	1	4
50	25	900	9	1	5	106	53	1908	19	3	1
.54	27	972	9	4	19	110	55	1980	20	1	15
56	28	1008	10	1	16	114	57	2052	21	0	9
60	30	1080	11	0	10	116	58	2088	21	2	6
64	32	1152	11	4	4	120	60	2160	22	1	0
66	33	1188	12	1	1	124	62	2232	22	4	14
70	35	1260	12	4	15	126	63	2268	23	1	11
74	37	1332	13	3	9	130	65	2340	24	0	5
76	38	1368	14	0	6	134	67	2412	24	3	19
80	40	1440	14	4	0	150	75	2700	1	1	15
84	42	1512	15	2	14	166	83	2988	30	3	11
86	43	1548	15	4	11		İ	1			ļ
	1	[	ī	1	i			•	ı	•	•


To enable manufacturers to ascertain the measure of the reed by inspection, an instrument has been long used in Scotland, and more recently adopted in England. It combines the properties both of a microscope and micrometer, for, while the dimensions of the threads are magnified by a convex glass, the measure is ascertained by a hole in the bottom of the standard. Those used in Scotland, when correctly constructed, show one thread for every hundred splits. Of course, the diameter of the hole must be the two hundredth part of 37 inches.


The English glasses are calculated upon the same principle, to adapt them to their particular uses.


FINIS.


JAMES HEDDERWICK AND CO. PRINTERS, GLASGOW.

F.10 24













Property for the American










Promon de Jake Derrader Prantitation Co.








Fraga by John Duman ling the district Renal Relation. Indulated as the saction on Meetings











Ph.17'K 13.